

# **Programming with gtkmm 3**

---

Copyright © 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010 Murray Cumming

Permission is granted to copy, distribute and/or modify this document under the terms of the GNU Free Documentation License, Version 1.2 or any later version published by the Free Software Foundation; with no Invariant Sections, no Front-Cover Texts, and no Back-Cover Texts. You may obtain a copy of the GNU Free Documentation License from the Free Software Foundation by visiting their Web site or by writing to: Free Software Foundation, Inc., 59 Temple Place - Suite 330, Boston, MA 02111-1307, USA.

COLLABORATORS			
	<i>TITLE :</i> Programming with gtkmm 3		
<i>ACTION</i>	<i>NAME</i>	<i>DATE</i>	<i>SIGNATURE</i>
WRITTEN BY	Murray Cumming, Bernhard Rieder, Jonathon Jongsma, Ole Laursen, Marko Anastasov, Daniel Elstner, Chris Vine, David King, Pedro Ferreira, and Kjell Ahlstedt	March 26, 2025	

# Contents

<b>1</b>	<b>Introduction</b>	<b>1</b>
1.1	This book . . . . .	1
1.2	gtkmm . . . . .	1
<b>2</b>	<b>Installation</b>	<b>3</b>
2.1	Dependencies . . . . .	3
2.2	Unix and Linux . . . . .	4
2.3	Microsoft Windows . . . . .	5
<b>3</b>	<b>Basics</b>	<b>6</b>
3.1	Simple Example . . . . .	6
3.2	Headers and Linking . . . . .	7
3.3	Widgets . . . . .	8
3.4	Signals . . . . .	9
3.5	Glib::ustring . . . . .	9
3.6	Intermediate types . . . . .	10
3.7	Mixing C and C++ APIs . . . . .	11
3.8	Hello World in gtkmm . . . . .	12
<b>4</b>	<b>Changes in gtkmm 3</b>	<b>16</b>

---

---

<b>5</b>	<b>Buttons</b>	<b>18</b>
5.1	Button . . . . .	18
5.2	ToggleButton . . . . .	21
5.3	CheckButton . . . . .	22
5.4	RadioButton . . . . .	24
<b>6</b>	<b>Range Widgets</b>	<b>29</b>
6.1	Scrollbar Widgets . . . . .	29
6.2	Scale Widgets . . . . .	30
6.3	Example . . . . .	30
<b>7</b>	<b>Miscellaneous Widgets</b>	<b>38</b>
7.1	Label . . . . .	38
7.2	Entry . . . . .	42
7.3	SpinButton . . . . .	56
7.4	ProgressBar . . . . .	64
7.5	InfoBar . . . . .	69
7.6	Tooltips . . . . .	73
<b>8</b>	<b>Container Widgets</b>	<b>79</b>
8.1	Single-item Containers . . . . .	79
8.2	Multiple-item widgets . . . . .	96
<b>9</b>	<b>The TreeView widget</b>	<b>128</b>
9.1	The Model . . . . .	128
9.2	The View . . . . .	132
9.3	Iterating over Model Rows . . . . .	135
9.4	The Selection . . . . .	135
9.5	Sorting . . . . .	137
9.6	Drag and Drop . . . . .	138
9.7	Popup Context Menu . . . . .	139
9.8	Examples . . . . .	139

---

---

<b>10 Combo Boxes</b>	<b>168</b>
10.1 The model . . . . .	168
10.2 The chosen item . . . . .	169
10.3 Responding to changes . . . . .	169
10.4 Full Example . . . . .	170
10.5 Simple Text Example . . . . .	174
10.6 ComboBox with an Entry . . . . .	176
<b>11 TextView</b>	<b>185</b>
11.1 The Buffer . . . . .	185
11.2 Widgets and ChildAnchors . . . . .	187
11.3 Examples . . . . .	188
<b>12 Menus and Toolbars</b>	<b>192</b>
12.1 Actions . . . . .	192
12.2 Menubar and Toolbar . . . . .	193
12.3 Popup Menus . . . . .	195
12.4 Gio::Resource and glib-compile-resources . . . . .	196
12.5 Examples . . . . .	197
<b>13 ToolPalette</b>	<b>220</b>
13.1 Drag and Drop . . . . .	221
13.2 ToolPalette Example . . . . .	221
<b>14 Adjustments</b>	<b>237</b>
14.1 Creating an Adjustment . . . . .	237
14.2 Using Adjustments the Easy Way . . . . .	238
14.3 Adjustment Internals . . . . .	238
<b>15 Widgets Without X-Windows</b>	<b>240</b>
15.1 EventBox . . . . .	241

---

---

<b>16 Dialogs</b>	<b>244</b>
16.1 MessageDialog . . . . .	244
16.2 FileChooserDialog . . . . .	247
16.3 ColorChooserDialog . . . . .	252
16.4 FontChooserDialog . . . . .	256
16.5 Non-modal AboutDialog . . . . .	260
<b>17 The Drawing Area Widget</b>	<b>265</b>
17.1 The Cairo Drawing Model . . . . .	266
17.2 Drawing Straight Lines . . . . .	267
17.3 Drawing Curved Lines . . . . .	275
17.4 Drawing Arcs and Circles . . . . .	278
17.5 Drawing Text . . . . .	282
17.6 Drawing Images . . . . .	286
17.7 Example Application: Creating a Clock with Cairo . . . . .	290
<b>18 Drag and Drop</b>	<b>296</b>
18.1 Sources and Destinations . . . . .	296
18.2 Methods . . . . .	296
18.3 Signals . . . . .	297
18.4 DragContext . . . . .	298
18.5 Example . . . . .	298
<b>19 The Clipboard</b>	<b>302</b>
19.1 Targets . . . . .	302
19.2 Copy . . . . .	303
19.3 Paste . . . . .	303
19.4 Examples . . . . .	304

---

---

<b>20 Printing</b>	<b>315</b>
20.1 PrintOperation . . . . .	315
20.2 Page setup . . . . .	316
20.3 Rendering text . . . . .	317
20.4 Asynchronous operations . . . . .	317
20.5 Export to PDF . . . . .	318
20.6 Extending the print dialog . . . . .	318
20.7 Preview . . . . .	319
20.8 Example . . . . .	319
<b>21 Recently Used Documents</b>	<b>334</b>
21.1 RecentManager . . . . .	334
21.2 RecentChooser . . . . .	336
<b>22 Plugs and Sockets</b>	<b>344</b>
22.1 Overview . . . . .	344
22.2 Plugs and Sockets Example . . . . .	345
<b>23 Keyboard Events</b>	<b>350</b>
23.1 Overview . . . . .	350
23.2 Event Propagation . . . . .	354
<b>24 Timeouts, I/O and Idle Functions</b>	<b>359</b>
24.1 Timeouts . . . . .	359
24.2 Monitoring I/O . . . . .	363
24.3 Idle Functions . . . . .	366
<b>25 Memory management</b>	<b>370</b>
25.1 Widgets . . . . .	370
25.2 Shared resources . . . . .	372

---



---

<b>26 Glade and Gtk::Builder</b>	<b>374</b>
26.1 Loading the .glade file . . . . .	374
26.2 Accessing widgets . . . . .	375
26.3 Using derived widgets . . . . .	377
<b>27 Internationalization and Localization</b>	<b>385</b>
27.1 Preparing your project . . . . .	386
27.2 Marking strings for translation . . . . .	388
27.3 Expecting UTF8 . . . . .	390
27.4 Pitfalls . . . . .	391
27.5 Getting help with translations . . . . .	392
<b>28 Custom Widgets</b>	<b>393</b>
28.1 Custom Containers . . . . .	393
28.2 Custom Widgets . . . . .	404
<b>29 Multi-threaded programs</b>	<b>417</b>
29.1 The constraints . . . . .	417
29.2 Using Glib::Dispatcher . . . . .	418
29.3 Example . . . . .	419
<b>30 Recommended Techniques</b>	<b>429</b>
30.1 Application Lifetime . . . . .	429
30.2 Using a gtkmm widget . . . . .	430
<b>31 Building applications</b>	<b>431</b>
31.1 A trivial application . . . . .	432
31.2 Populating the window . . . . .	437
31.3 Opening files . . . . .	443
31.4 An application menu . . . . .	446
31.5 A preference dialog . . . . .	453
31.6 Adding a search bar . . . . .	464
31.7 Adding a side bar . . . . .	471
31.8 Properties . . . . .	482
31.9 Header bar . . . . .	494

---

<b>32 Contributing</b>	<b>506</b>
<b>A The RefPtr smartpointer</b>	<b>507</b>
A.1 Copying . . . . .	507
A.2 Dereferencing . . . . .	508
A.3 Casting . . . . .	508
A.4 Checking for null . . . . .	508
A.5 Constness . . . . .	509
<b>B Signals</b>	<b>510</b>
B.1 Connecting signal handlers . . . . .	510
B.2 Writing signal handlers . . . . .	512
B.3 Disconnecting signal handlers . . . . .	512
B.4 Overriding default signal handlers . . . . .	513
B.5 Binding extra arguments . . . . .	514
B.6 X Event signals . . . . .	514
B.7 Exceptions in signal handlers . . . . .	515
<b>C Creating your own signals</b>	<b>519</b>
C.1 Example . . . . .	520
<b>D Comparison with other signalling systems</b>	<b>523</b>
<b>E gtkmm and Win32</b>	<b>524</b>
<b>F Working with gtkmm's Source Code</b>	<b>525</b>
F.1 Setting up jhbuild . . . . .	525
F.2 Installing and Using the git version of gtkmm . . . . .	526
<b>G Wrapping C Libraries with gmmproc</b>	<b>528</b>
G.1 The build structure . . . . .	528
G.2 Generating the .defs files. . . . .	530
G.3 The .hg and .ccg files . . . . .	532

---

---

G.4	Hand-coded source files . . . . .	551
G.5	Initialization . . . . .	551
G.6	Problems in the C API. . . . .	552
G.7	Documentation . . . . .	553

---

# List of Figures

3.1	Hello World . . . . .	13
5.1	buttons example . . . . .	19
5.2	CheckButton . . . . .	22
5.3	RadioButton . . . . .	25
6.1	Range Widgets . . . . .	31
7.1	Label . . . . .	39
7.2	Entry . . . . .	43
7.3	Entry Completion . . . . .	46
7.4	Entry with Icon . . . . .	51
7.5	Entry with Progress Bar . . . . .	54
7.6	SpinButton . . . . .	58
7.7	ProgressBar . . . . .	65
7.8	InfoBar . . . . .	69
7.9	Tooltip . . . . .	73
8.1	Frame . . . . .	80
8.2	Paned . . . . .	83
8.3	ScrolledWindow . . . . .	88
8.4	AspectFrame . . . . .	92
8.5	Alignment . . . . .	94

---

---

8.6	Hello World 2 . . . . .	97
8.7	Box Packing 1 . . . . .	100
8.8	Box Packing 2 . . . . .	102
8.9	ButtonBox . . . . .	111
8.10	Grid . . . . .	116
8.11	Notebook . . . . .	119
8.12	Assistant . . . . .	122
9.1	TreeView - ListStore . . . . .	129
9.2	TreeView - TreeStore . . . . .	130
9.3	TreeView - ListStore . . . . .	140
9.4	TreeView - TreeStore . . . . .	144
9.5	TreeView - Editable Cells . . . . .	148
9.6	TreeView - Drag And Drop . . . . .	155
9.7	TreeView - Popup Context Menu . . . . .	162
10.1	ComboBox . . . . .	170
10.2	ComboBoxText . . . . .	174
10.3	ComboBox with Entry . . . . .	177
10.4	ComboBoxText with Entry . . . . .	181
11.1	TextView . . . . .	188
12.1	App and Main Menu . . . . .	197
12.2	Main Menu . . . . .	209
12.3	Popup Menu . . . . .	215
13.1	ToolPalette . . . . .	222
15.1	EventBox . . . . .	241
16.1	MessageDialog . . . . .	245
16.2	FileChooser . . . . .	248

---

---

16.3	ColorChooserDialog . . . . .	253
16.4	FontChooserDialog . . . . .	257
16.5	AboutDialog . . . . .	261
17.1	Drawing Area - Lines . . . . .	268
17.2	Different join types in Cairo . . . . .	271
17.3	Drawing Area - Thin Lines . . . . .	272
17.4	Drawing Area - Lines . . . . .	276
17.5	Drawing Area - Arcs . . . . .	279
17.6	Drawing Area - Text . . . . .	283
17.7	Drawing Area - Image . . . . .	287
18.1	Drag and Drop . . . . .	298
19.1	Clipboard - Simple . . . . .	305
19.2	Clipboard - Ideal . . . . .	308
20.1	Printing - Simple . . . . .	320
23.1	Keyboard Events - Simple . . . . .	351
23.2	Keyboard Events - Event Propagation . . . . .	354
28.1	Custom Container . . . . .	395
28.2	Custom Widget . . . . .	406
29.1	Multi-Threaded Program . . . . .	420
31.1	A trivial application . . . . .	433
31.2	Populating the window . . . . .	438
31.3	Opening files . . . . .	444
31.4	An application menu . . . . .	447
31.5	An preference dialog . . . . .	454
31.6	Adding a search bar . . . . .	465

---

---

31.7 Adding a side bar . . . . .	472
31.8 Properties . . . . .	483
31.9 Header bar . . . . .	495

---

## **Abstract**

This book explains key concepts of the gtkmm C++ API for creating user interfaces. It also introduces the main user interface elements ("widgets").



## Chapter 1

# Introduction

### 1.1 This book

This book explains key concepts of the gtkmm C++ API for creating user interfaces. It also introduces the main user interface elements ("widgets"). Although it mentions classes, constructors, and methods, it does not go into great detail. Therefore, for full API information you should follow the links into the reference documentation.

This book assumes a good understanding of C++, and how to create C++ programs.

We would very much like to hear of any problems you have learning gtkmm with this document, and would appreciate input regarding improvements. Please see the [Contributing](#) section for further information.

### 1.2 gtkmm

gtkmm is a C++ wrapper for [GTK+](#), a library used to create graphical user interfaces. It is licensed using the LGPL license, so you can develop open software, free software, or even commercial non-free software using gtkmm without purchasing licenses.

gtkmm was originally named gtk-- because GTK+ already has a + in the name. However, as -- is not easily indexed by search engines the package generally went by the name gtkmm, and that's what we stuck with.

#### 1.2.1 Why use gtkmm instead of GTK+?

gtkmm allows you to write code using normal C++ techniques such as encapsulation, derivation, and polymorphism. As a C++ programmer you probably already realise that this leads to clearer and better

---

organized code.

gtkmm is more type-safe, so the compiler can detect errors that would only be detected at run time when using C. This use of specific types also makes the API clearer because you can see what types should be used just by looking at a method's declaration.

Inheritance can be used to derive new widgets. The derivation of new widgets in GTK+ C code is so complicated and error prone that almost no C coders do it. As a C++ developer you know that derivation is an essential Object Orientated technique.

Member instances can be used, simplifying memory management. All GTK+ C widgets are dealt with by use of pointers. As a C++ coder you know that pointers should be avoided where possible.

gtkmm involves less code compared to GTK+, which uses prefixed function names and lots of cast macros.

### 1.2.2 gtkmm compared to Qt

Trolltech's Qt is the closest competition to gtkmm, so it deserves discussion.

gtkmm developers tend to prefer gtkmm to Qt because gtkmm does things in a more C++ way. Qt originates from a time when C++ and the standard library were not standardised or well supported by compilers. It therefore duplicates a lot of stuff that is now in the standard library, such as containers and type information. Most significantly, Trolltech modified the C++ language to provide signals, so that Qt classes cannot be used easily with non-Qt classes. gtkmm was able to use standard C++ to provide signals without changing the C++ language. See the [FAQ](#) for more detailed differences.

### 1.2.3 gtkmm is a wrapper

gtkmm is not a native C++ toolkit, but a C++ wrapper of a C toolkit. This separation of interface and implementation has advantages. The gtkmm developers spend most of their time talking about how gtkmm can present the clearest API, without awkward compromises due to obscure technical details. We contribute a little to the underlying GTK+ code base, but so do the C coders, and the Perl coders and the Python coders, etc. Therefore GTK+ benefits from a broader user base than language-specific toolkits - there are more implementers, more developers, more testers, and more users.

---

## Chapter 2

# Installation

### 2.1 Dependencies

Before attempting to install gtkmm 3.0, you might first need to install these other packages.

- sigc++-2.0
- gtk+-3.0
- glibmm-2.4
- cairomm-1.0
- pangomm-1.4
- atkmm-1.6

These dependencies have their own dependencies, including the following applications and libraries:

- pkg-config
  - glib-2.0
  - atk
  - pango
  - cairo
  - gdk-pixbuf-2.0
-

## 2.2 Unix and Linux

### 2.2.1 Prebuilt Packages

Recent versions of gtkmm are packaged by nearly every major Linux distribution these days. So, if you use Linux, you can probably get started with gtkmm by installing the package from the official repository for your distribution. Distributions that include gtkmm in their repositories include Debian, Ubuntu, Red Hat, Fedora, Mandriva, Suse, and many others.

The names of the gtkmm packages vary from distribution to distribution (e.g. `libgtkmm-3.0-dev` on Debian and Ubuntu or `gtkmm30-devel` on Red Hat Fedora), so check with your distribution's package management program for the correct package name and install it like you would any other package.

---

**Note**

The package names will not change when new API/ABI-compatible versions of gtkmm are released. Otherwise they would not be API/ABI-compatible. So don't be surprised, for instance, to find gtkmm 3.24 supplied by Debian's `libgtkmm-3.0-dev` package.

---

### 2.2.2 Installing From Source

If your distribution does not provide a pre-built gtkmm package, or if you want to install a different version than the one provided by your distribution, you can also install gtkmm from source. The source code for gtkmm can be downloaded from <https://download.gnome.org/sources/gtkmm/>.

After you've installed all of the dependencies, download the gtkmm source code, unpack it, and change to the newly created directory. gtkmm 3.24.2 and earlier can be built and installed with the following sequence of commands:

```
# ./configure
# make
# make install
```

gtkmm 3.24.3 and later can be built with Meson. See the `README` file in the gtkmm version you've downloaded.

---

**Note**

Remember that on a Unix or Linux operating system, you will probably need to be `root` to install software. The `su` or `sudo` command will allow you to enter the `root` password and have `root` status temporarily.

---

The `configure` script or **meson** will check to make sure all of the required dependencies are already installed. If you are missing any dependencies, it will exit and display an error.

By default, gtkmm if built with Meson or Autotools, will be installed under the `/usr/local` directory. On some systems you may need to install to a different location. For instance, on Red Hat Linux systems you might use the `--prefix` option with `configure`, like one of:

```
# meson setup --prefix=/usr <builddir> <srcdir>
# meson configure --prefix=/usr
# ./configure --prefix=/usr
```

**Warning**

You should be very careful when installing to standard system prefixes such as `/usr`. Linux distributions install software packages to `/usr`, so installing a source package to this prefix could corrupt or conflict with software installed using your distribution's package-management system. Ideally, you should use a separate prefix for all software you install from source.

---

If you want to help develop gtkmm or experiment with new features, you can also install gtkmm from git. Most users will never need to do this, but if you're interested in helping with gtkmm development, see the [Working with gtkmm's Source Code](#) appendix.

## 2.3 Microsoft Windows

GTK+ and gtkmm were designed to work well with Microsoft Windows, and the developers encourage its use on the win32 platform. However, Windows has no standard installation system for development libraries. Please see the [Windows Installation](#) page or the [gtkmm and Win32](#) appendix for Windows-specific installation instructions and notes.

---

## Chapter 3

# Basics

This chapter will introduce some of the most important aspects of gtkmm coding. These will be demonstrated with simple working example code. However, this is just a taster, so you need to look at the other chapters for more substantial information.

Your existing knowledge of C++ will help you with gtkmm as it would with any library. Unless we state otherwise, you can expect gtkmm classes to behave like any other C++ class, and you can expect to use your existing C++ techniques with gtkmm classes.

### 3.1 Simple Example

To begin our introduction to gtkmm, we'll start with the simplest program possible. This program will create an empty 200 x 200 pixel window.

#### Source Code

File: `base.cc` (For use with gtkmm 3)

```
#include <gtkmm.h>

int main(int argc, char *argv[])
{
    auto app =
        Gtk::Application::create(argc, argv,
            "org.gtkmm.examples.base");

    Gtk::Window window;
    window.set_default_size(200, 200);
```

```
    return app->run(window);  
}
```

We will now explain each line of the example

```
#include <gtkmm.h>
```

All gtkmm programs must include certain gtkmm headers; `gtkmm.h` includes the entire gtkmm kit. This is usually not a good idea, because it includes a megabyte or so of headers, but for simple programs, it suffices.

The next statement:

```
Glib::RefPtr<Gtk::Application> app = Gtk::Application::create(argc, argv, ↵  
    "org.gtkmm.examples.base");
```

creates a `Gtk::Application` object, stored in a `RefPtr` smartpointer. This is needed in all gtkmm applications. The `create()` method for this object initializes gtkmm, and checks the arguments passed to your application on the command line, looking for standard options such as `--display`. It takes these from the argument list, leaving anything it does not recognize for your application to parse or ignore. This ensures that all gtkmm applications accept the same set of standard arguments.

The next two lines of code create a window and set its default (initial) size:

```
Gtk::Window window;  
window.set_default_size(200, 200);
```

The last line shows the window and enters the gtkmm main processing loop, which will finish when the window is closed. Your `main()` function will then return with an appropriate success or error code.

```
return app->run(window);
```

After putting the source code in `simple.cc` you can compile the above program with `gcc` using:

```
g++ simple.cc -o simple `pkg-config gtkmm-3.0 --cflags --libs`
```

Note that you must surround the `pkg-config` invocation with backquotes. Backquotes cause the shell to execute the command inside them, and to use the command's output as part of the command line. Note also that `simple.cc` must come before the `pkg-config` invocation on the command line.

## 3.2 Headers and Linking

Although we have shown the compilation command for the simple example, you really should use the [Meson build system](#). The examples used in this book are included in the `gtkmm-documentation` package,

---

with appropriate build files, so we won't show the build commands in future. The `README` file in `gtkmm`-documentation describes how to build the examples.

To simplify compilation, we use `pkg-config`, which is present in all (properly installed) `gtkmm` installations. This program 'knows' what compiler switches are needed to compile programs that use `gtkmm`. The `--cflags` option causes `pkg-config` to output a list of include directories for the compiler to look in; the `--libs` option requests the list of libraries for the compiler to link with and the directories to find them in. Try running it from your shell-prompt to see the results on your system.

However, this is even simpler when using the `dependency()` function in a `meson.build` file with Meson. For instance:

```
gtkmm_dep = dependency('gtkmm-3.0', version: '>= 3.24.0')
```

This checks for the presence of `gtkmm` and defines `gtkmm_dep` for use in your `meson.build` files. For instance:

```
exe_file = executable('my_program', 'my_source1.cc', 'my_source2.cc',
    dependencies: gtkmm_dep,
    win_subsystem: 'windows',
)
```

`gtkmm-3.0` is the name of the current stable API. There was an older API called `gtkmm-2.4` which installs in parallel when it is available. There were several versions of `gtkmm-2.4`, such as `gtkmm 2.10` and there are several versions of the `gtkmm-3.0` API. Note that the API name does not change for every version because that would be an incompatible API and ABI break. Theoretically, there might be a future `gtkmm-4.0` API which would install in parallel with `gtkmm-3.0` without affecting existing applications.

If you start by experimenting with a small application that you plan to use just for yourself, it's easier to start with a `meson.build` similar to the `meson.build` files in the [Building applications](#) chapter.

If you use the older Autotools build system, see also the GNU site. It has more information about [autoconf](#) and [automake](#). There are also some books describing Autotools: "GNU Autoconf, Automake, and Libtool" by Gary Vaughan et al. and "Autotools, A Practitioner's Guide to GNU Autoconf, Automake, and Libtool" by John Calcote.

## 3.3 Widgets

`gtkmm` applications consist of windows containing widgets, such as buttons and text boxes. In some other systems, widgets are called "controls". For each widget in your application's windows, there is a C++ object in your application's code. So you just need to call a method of the widget's class to affect the visible widget.

Widgets are arranged inside container widgets such as frames and notebooks, in a hierarchy of widgets within widgets. Some of these container widgets, such as `Gtk::Grid`, are not visible - they exist only to arrange other widgets. Here is some example code that adds 2 `Gtk::Button` widgets to a `Gtk::Box` container widget:

---



```
m_box.pack_start(m_Button1);  
m_box.pack_start(m_Button2);
```

and here is how to add the `Gtk::Box`, containing those buttons, to a `Gtk::Frame`, which has a visible frame and title:

```
m_frame.add(m_box);
```

Most of the chapters in this book deal with specific widgets. See the [Container Widgets](#) section for more details about adding widgets to container widgets.

Although you can specify the layout and appearance of windows and widgets with C++ code, you will probably find it more convenient to design your user interfaces with Glade and load them at runtime with `Gtk::Builder`. See the [Glade and Gtk::Builder](#) chapter.

Although gtkmm widget instances have lifetimes and scopes just like those of other C++ classes, gtkmm has an optional time-saving feature that you will see in some of the examples. The `Gtk::make_managed()` allows you to create a new widget and state that it will become owned by the container into which you place it. This allows you to create the widget, add it to the container and not be concerned about deleting it, since that will occur when the parent container (which may itself be managed) is deleted. You can learn more about gtkmm memory management techniques in the [Memory Management](#) chapter.

## 3.4 Signals

gtkmm, like most GUI toolkits, is *event-driven*. When an event occurs, such as the press of a mouse button, the appropriate signal will be *emitted* by the Widget that was pressed. Each Widget has a different set of signals that it can emit. To make a button click result in an action, we set up a *signal handler* to catch the button's "clicked" signal.

gtkmm uses the libsigc++ library to implement signals. Here is an example line of code that connects a `Gtk::Button`'s "clicked" signal with a signal handler called "on\_button\_clicked":

```
m_button1.signal_clicked().connect( sigc::mem_fun(*this,  
    &HelloWorld::on_button_clicked) );
```

For more detailed information about signals, see the [appendix](#).

For information about implementing your own signals rather than just connecting to the existing gtkmm signals, see the [appendix](#).

## 3.5 Glib::ustring

You might be surprised to learn that gtkmm doesn't use `std::string` in its interfaces. Instead it uses `Glib::ustring`, which is so similar and unobtrusive that you could actually pretend that each

---

`Glib::ustring` is a `std::string` and ignore the rest of this section. But read on if you want to use languages other than English in your application.

`std::string` uses 8 bit per character, but 8 bits aren't enough to encode languages such as Arabic, Chinese, and Japanese. Although the encodings for these languages have now been specified by the Unicode Consortium, the C and C++ languages do not yet provide any standardised Unicode support. GTK+ and GNOME chose to implement Unicode using UTF-8, and that's what is wrapped by `Glib::ustring`. It provides almost exactly the same interface as `std::string`, along with automatic conversions to and from `std::string`.

One of the benefits of UTF-8 is that you don't need to use it unless you want to, so you don't need to retrofit all of your code at once. `std::string` will still work for 7-bit ASCII strings. But when you try to localize your application for languages like Chinese, for instance, you will start to see strange errors, and possible crashes. Then all you need to do is start using `Glib::ustring` instead.

Note that UTF-8 isn't compatible with 8-bit encodings like ISO-8859-1. For instance, German umlauts are not in the ASCII range and need more than 1 byte in the UTF-8 encoding. If your code contains 8-bit string literals, you have to convert them to UTF-8 (e.g. the Bavarian greeting "Grüß Gott" would be `"Gr\xC3\xBC\xC3\x9F Gott"`).

You should avoid C-style pointer arithmetic, and functions such as `strlen()`. In UTF-8, each character might need anywhere from 1 to 6 bytes, so it's not possible to assume that the next byte is another character. `Glib::ustring` worries about the details of this for you so you can use methods such as `Glib::ustring::substr()` while still thinking in terms of characters instead of bytes.

Unlike the Windows UCS-2 Unicode solution, this does not require any special compiler options to process string literals, and it does not result in Unicode executables and libraries which are incompatible with ASCII ones.

### Reference

See the [Internationalization](#) section for information about providing the UTF-8 string literals.

## 3.6 Intermediate types

Some API related to gtkmm uses intermediate data containers, such as `Glib::StringArrayHandle`, instead of a specific Standard C++ container such as `std::vector` or `std::list`, though gtkmm itself now uses just `std::vector` since gtkmm 3.0.

You should not declare these types yourself. You should instead use whatever Standard C++ container you prefer. glibmm will do the conversion for you. Here are some of these intermediate types:

- `Glib::StringArrayHandle` or `Glib::ArrayHandle<Glib::ustring>`: Use `std::vector<Glib::ustring>`, `std::list<Glib::ustring>`, `const char*[]`, etc.
- `Glib::ListHandle<Gtk::Widget*>`: Use `std::vector<Gtk::Widget*>`, `std::list<Gtk::Widget*>`, etc.

- `Glib::SListHandle<Gtk::Widget*>`: Use `std::vector<Gtk::Widget*>`, `std::list<Gtk::Widget*>` etc.

### 3.7 Mixing C and C++ APIs

You can use C APIs which do not yet have convenient C++ interfaces. It is generally not a problem to use C APIs from C++, and gtkmm helps by providing access to the underlying C object, and providing an easy way to create a C++ wrapper object from a C object, provided that the C API is also based on the GObject system.

To use a gtkmm instance with a C function that requires a C GObject instance, use the C++ instance's `gobj()` function to obtain a pointer to the underlying C instance. For example:

```
Gtk::Button* button = new Gtk::Button("example");
gtk_button_do_something_that_gtkmm_cannot(button->gobj());
```

To obtain a gtkmm instance from a C GObject instance, use one of the many overloaded `Glib::wrap()` functions. The C instance's reference count is not incremented, unless you set the optional *take\_copy* argument to `true`. For example:

```
GtkButton* cbutton = get_a_button();
Gtk::Button* button = Glib::wrap(cbutton);
button->set_label("Now I speak C++ too!");
```

The C++ wrapper shall be explicitly deleted if

- it's a widget or other class that inherits from `Gtk::Object`, and
- the C instance has a floating reference when the wrapper is created, and
- `Gtk::manage()` has not been called on it (which includes if it was created with `Gtk::make_managed()`), or
- `Gtk::manage()` was called on it, but it was never added to, or was later removed from, its parent.

`Glib::wrap()` binds the C and C++ instances to each other. Don't delete the C++ instance before you want the C instance to die.

In all other cases the C++ instance is automatically deleted when the last reference to the C instance is dropped. This includes all `Glib::wrap()` overloads that return a `Glib::RefPtr`.

## 3.8 Hello World in gtkmm

We've now learned enough to look at a real example. In accordance with an ancient tradition of computer science, we now introduce Hello World, a la gtkmm:

### Source Code

File: helloworld.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_HELLOWORLD_H
#define GTKMM_EXAMPLE_HELLOWORLD_H

#include <gtkmm/button.h>
#include <gtkmm/window.h>

class HelloWorld : public Gtk::Window
{
public:
    HelloWorld();
    virtual ~HelloWorld();

protected:
    //Signal handlers:
    void on_button_clicked();

    //Member widgets:
    Gtk::Button m_button;
};

#endif // GTKMM_EXAMPLE_HELLOWORLD_H
```

File: helloworld.cc (For use with gtkmm 3)

```
#include "helloworld.h"
#include <iostream>

HelloWorld::HelloWorld()
: m_button("Hello World")    // creates a new button with label "Hello ↵
  World".
{
    // Sets the border width of the window.
    set_border_width(10);

    // When the button receives the "clicked" signal, it will call the
    // on_button_clicked() method defined below.
    m_button.signal_clicked().connect(sigc::mem_fun(*this,
        &HelloWorld::on_button_clicked));
```

```
// This packs the button into the Window (a container).
add(m_button);

// The final step is to display this newly created widget...
m_button.show();
}

HelloWorld::~HelloWorld()
{
}

void HelloWorld::on_button_clicked()
{
    std::cout << "Hello World" << std::endl;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "helloworld.h"
#include <gtkmm/application.h>

int main (int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    HelloWorld helloworld;

    //Shows the window and returns when it is closed.
    return app->run(helloworld);
}
```

Try to compile and run it before going on. You should see something like this:



Figure 3.1: Hello World

Pretty thrilling, eh? Let's examine the code. First, the `HelloWorld` class:

---

```
class HelloWorld : public Gtk::Window
{
public:
    HelloWorld();
    virtual ~HelloWorld();

protected:
    //Signal handlers:
    virtual void on_button_clicked();

    //Member widgets:
    Gtk::Button m_button;
};
```

This class implements the "Hello World" window. It's derived from `Gtk::Window`, and has a single `Gtk::Button` as a member. We've chosen to use the constructor to do all of the initialisation work for the window, including setting up the signals. Here it is, with the comments omitted:

```
HelloWorld::HelloWorld()
:
    m_button ("Hello World")
{
    set_border_width(10);
    m_button.signal_clicked().connect(sigc::mem_fun(*this,
        &HelloWorld::on_button_clicked));
    add(m_button);
    m_button.show();
}
```

Notice that we've used an initialiser statement to give the `m_button` object the label "Hello World".

Next we call the Window's `set_border_width()` method. This sets the amount of space between the sides of the window and the widget it contains.

We then hook up a signal handler to `m_button`'s `clicked` signal. This prints our friendly greeting to `stdout`.

Next, we use the Window's `add()` method to put `m_button` in the Window. (`add()` comes from `Gtk::Container`, which is described in the chapter on container widgets.) The `add()` method places the Widget in the Window, but it doesn't display the widget. `gtkmm` widgets are always invisible when you create them - to display them, you must call their `show()` method, which is what we do in the next line.

Now let's look at our program's `main()` function. Here it is, without comments:

```
int main(int argc, char** argv)
{
```

```
Glib::RefPtr<Gtk::Application> app = Gtk::Application::create(argc, argv ←  
    , "org.gtkmm.example");  
  
HelloWorld helloworld;  
return app->run(helloworld);  
}
```

First we instantiate an object stored in a `RefPtr` smartpointer called `app`. This is of type `Gtk::Application`. Every gtkmm program must have one of these. We pass our command-line arguments to its `create()` method. It takes the arguments it wants, and leaves you the rest, as we described earlier.

Next we make an object of our `HelloWorld` class, whose constructor takes no arguments, but it isn't visible yet. When we call `Gtk::Application::run()`, giving it the `helloworld` Window, it shows the Window and starts the gtkmm *event loop*. During the event loop gtkmm idles, waiting for actions from the user, and responding appropriately. When the user closes the Window, `run()` will return, causing the final line of our `main()` function be to executed. The application will then finish.

## Chapter 4

# Changes in gtkmm 3

gtkmm-3.0 is a new version of the gtkmm API that installs in parallel with the older gtkmm-2.4 API. The last version of the gtkmm-2.4 API was gtkmm 2.24. gtkmm 3 has no major fundamental differences to gtkmm 2 but does make several small changes that were not possible while maintaining binary compatibility. If you never used the gtkmm-2.4 API then you can safely ignore this chapter.

gtkmm 3's library is called `libgtkmm-3.0` rather than `libgtkmm-2.4` and installs its headers in a similarly-versioned directory, so your `pkg-config` check should ask for `gtkmm-3.0` rather than `gtkmm-2.4`.

gtkmm 3 added some new classes:

1. `Gtk::AppChooser`, `Gtk::AppChooserButton`, `Gtk::AppChooserDialog` allow the user to select an installed application to open a particular type of content.
2. `Gtk::Grid` is a new container widget that will eventually replace `Gtk::Box` and `Gtk::Table`. It arranges its children according to properties of those children rather than its own layout details.
3. `Gtk::Switch` displays On/Off states more explicitly than `Gtk::CheckBox`. It may be useful, for instance, when allowing users to activate hardware.

gtkmm 3 also made several small changes to the API, which you will probably encounter when porting code that used gtkmm-2.4. Here is a short list:

1. `Gtk::CellLayout`, used by `Gtk::IconView`, `Gtk::TreeView::Column` and `Gtk::ComboBox`, now has a `Gtk::CellArea` which can be used to specify more details of how the `CellRenderers` are arranged and aligned.
  2. `Gtk::ComboBox` now derives from `CellLayout`, allowing easier layout and alignment of its `Gtk::CellRenderers`.
  3. `Gtk::Adjustment` and `IconSet` and `Gdk::Cursor` are now used via `Glib::RefPtr`.
-



4. `Gtk::Box`, `Gtk::ButtonBox`, `Gtk::IconView`, `Gtk::Paned`, `Gtk::ProgressBar`, `Gtk::ScaleButton`, `Gtk::Scrollbar` and `Gtk::Separator` now derive from `Gtk::Orientable`, allowing their orientation (vertical or horizontal) to be specified without requiring the use of a derived class such as `Gtk::HBox`.
5. `Gtk::IconView`, `Gtk::TextView`, `Gtk::TreeView` and other widgets derive from `Scrolable` instead of having their own methods such as `get_vadjustment()` and instead of having their own `set_scroll_adjustments` signal.
6. `Gtk::Style` and `Gtk::Rc` were removed, replaced by `Gtk::StyleContext`, and `Gtk::StyleProviders`, such as `Gtk::CssProvider`.
7. `Widget::on_expose_event()` was replaced by `Widget::on_draw()`, which assumes that `cairomm` is used for drawing, via the provided `Cairo::Context` and does not require you to call `Cairo::Context::clip()`.
8. `Gdk::RGBA` replaces `Color`, adding an alpha component for opacity. `Colormap` was removed, along with its awkward use to allocate colors.
9. `Gdk::Pixmap` and `Gdk::Bitmap` were removed in favour of `Gdk::Pixbuf`.
10. `Gdk::Drawable` was removed, with its methods moving into `Gdk::Window`.
11. We now use `std::vector` in several methods instead of the intermediate `*Handle` types to make the API clearer.

All deprecated API was removed in gtkmm 3.0, though there will be new deprecations in future versions.

As a first step to porting your source code to gtkmm-3.0 you should probably ensure that your application builds with the deprecated gtkmm-2.4 API disabled, by defining macro such as `GTKMM_DISABLE_DEPRECATED`. There are some autotools macros that can help with this by defining them optionally at build time. See the [gtkmm 3 porting wiki page](#) for more details.

---

## Chapter 5

# Buttons

gtkmm provides four basic types of buttons:

**Push-Buttons** `Gtk::Button`. Standard buttons, usually marked with a label or picture. Pushing one triggers an action. See the `Button` section.

**Toggle buttons** `Gtk::ToggleButton`. Unlike a normal Button, which springs back up, a ToggleButton stays down until you press it again. It might be useful as an on/off switch. See the `ToggleButton` section.

**Checkboxes** `Gtk::CheckButton`. These act like ToggleButtons, but show their state in small squares, with their label at the side. They should be used in most situations which require an on/off setting. See the `CheckButton` section.

**Radio buttons** `Gtk::RadioButton`. Named after the station selectors on old car radios, these buttons are used in groups for options which are mutually exclusive. Pressing one causes all the others in its group to turn off. They are similar to CheckBoxes (a small widget with a label at the side), but usually look different. See the `RadioButton` section.

Note that, due to GTK+'s theming system, the appearance of these widgets will vary. In the case of checkboxes and radio buttons, they may vary considerably.

## 5.1 Button

### 5.1.1 Constructors

There are two ways to create a Button. You can specify a label string in the `Gtk::Button` constructor, or set it later with `set_label()`.

---

To define an accelerator key for keyboard navigation, place an underscore before one of the label's characters and specify `true` for the optional `mnemonic` parameter. For instance:

```
Gtk::Button* pButton = new Gtk::Button("_Something", true);
```

Stock items have been recommended for use in buttons. From gtkmm-3.10 they are deprecated. They should not be used in newly-written code. However, the documentation of [namespace `Gtk::Stock`](#) shows recommended labels and named icons to show in buttons.

`Gtk::Button` is also a container so you could put any other widget, such as a `Gtk::Image` into it.

#### Reference

### 5.1.2 Example

This example creates a button with a picture and a label.




Figure 5.1: buttons example

#### Source Code

File: `buttons.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_BUTTONS_H
#define GTKMM_EXAMPLE_BUTTONS_H

#include <gtkmm/window.h>
#include <gtkmm/button.h>

class Buttons : public Gtk::Window
{
public:
    Buttons();
    virtual ~Buttons();

protected:
    //Signal handlers:
    void on_button_clicked();
```

```
//Child widgets:
Gtk::Button m_button;
};

#endif //GTKMM_EXAMPLE_BUTTONS_H
```

**File: buttons.cc (For use with gtkmm 3)**

```
#include "buttons.h"
#include <iostream>

Buttons::Buttons()
{
    m_button.add_pixlabel("info.xpm", "cool button");

    set_title("Pixmap'd buttons!");
    set_border_width(10);

    m_button.signal_clicked().connect( sigc::mem_fun(*this,
        &Buttons::on_button_clicked) );

    add(m_button);

    show_all_children();
}

Buttons::~Buttons()
{
}

void Buttons::on_button_clicked()
{
    std::cout << "The Button was clicked." << std::endl;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "buttons.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    Buttons buttons;

    //Shows the window and returns when it is closed.
```

```
return app->run(buttons);  
}
```

### 5.1.3 Signals

The `Gtk::Button` widget has the following signals, but all except the `clicked` signal are deprecated and should not be used in newly-written code:

**pressed** Emitted when the button is pressed. Use `Gtk::Widget::signal_button_press_event()` instead.

**released** Emitted when the button is released. Use `Gtk::Widget::signal_button_release_event()` instead.

**clicked** Emitted when the button is pressed and released.

**enter** Emitted when the mouse pointer enters the button's window. Use `Gtk::Widget::signal_enter_notify_event()` instead.

**leave** Emitted when the mouse pointer leaves the button's window. Use `Gtk::Widget::signal_leave_notify_event()` instead.

## 5.2 ToggleButton

`ToggleButtons` are like normal `Buttons`, but when clicked they remain activated, or pressed, until clicked again.

To retrieve the state of the `ToggleButton`, you can use the `get_active()` method. This returns `true` if the button is "down". You can also set the toggle button's state, with `set_active()`. Note that, if you do this, and the state actually changes, it causes the "clicked" signal to be emitted. This is usually what you want.

You can use the `toggled()` method to toggle the button, rather than forcing it to be up or down: This switches the button's state, and causes the `toggled` signal to be emitted.

`Gtk::ToggleButton` is most useful as a base class for the `Gtk::CheckButton` and `Gtk::RadioButton` classes.

Reference

---

## 5.3 CheckButton

`Gtk::CheckButton` inherits from `Gtk::ToggleButton`. The only real difference between the two is `Gtk::CheckButton`'s appearance. You can check, set, and toggle a checkbox using the same member methods as for `Gtk::ToggleButton`.

### Reference

#### 5.3.1 Example




Figure 5.2: CheckButton

### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLE_BUTTONS_H
#define GTKMM_EXAMPLE_BUTTONS_H

#include <gtkmm/window.h>
#include <gtkmm/checkbutton.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_clicked();

    //Child widgets:
```

```
    Gtk::CheckButton m_button;  
};  
  
#endif //GTKMM_EXAMPLE_BUTTONS_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"  
#include <iostream>  
  
ExampleWindow::ExampleWindow()  
: m_button("something")  
{  
    set_title("checkbutton example");  
    set_border_width(10);  
  
    m_button.signal_clicked().connect(sigc::mem_fun(*this,  
        &ExampleWindow::on_button_clicked) );  
  
    add(m_button);  
  
    show_all_children();  
}  
  
ExampleWindow::~~ExampleWindow()  
{  
}  
  
void ExampleWindow::on_button_clicked()  
{  
    std::cout << "The Button was clicked: state=" <<  
        << (m_button.get_active() ? "true" : "false") <<  
        << std::endl;  
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"  
#include <gtkmm/application.h>  
  
int main(int argc, char *argv[])  
{  
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");  
  
    ExampleWindow window;  
  
    //Shows the window and returns when it is closed.  
    return app->run(window);  
}
```

---

```
}
```

## 5.4 RadioButton

Like checkboxes, radio buttons also inherit from `Gtk::ToggleButton`, but these work in groups, and only one `RadioButton` in a group can be selected at any one time.

### 5.4.1 Groups

There are two ways to set up a group of radio buttons. The first way is to create the buttons, and set up their groups afterwards. Only the constructors without a `Gtk::RadioButton::Group` parameter are used. In the following example, we put 3 radio buttons in a group:

```
auto rb1 = Gtk::make_managed<Gtk::RadioButton>("button1");
auto rb2 = Gtk::make_managed<Gtk::RadioButton>("button2");
auto rb3 = Gtk::make_managed<Gtk::RadioButton>("button3");
rb2->join_group(*rb1);
rb3->join_group(*rb1);
```

We told gtkmm to put all three `RadioButton`s in the same group by using `join_group()` to tell the other `RadioButton`s to share group with the first `RadioButton`.

The purpose of `join_group()` is to make it easier to express that you want a given button to use a group established by another. There is another way to do this, using `get_group()` and `set_group()`. However, this has a pitfall: Note that you can't do

```
rb2->set_group(rb1->get_group());
```

because `get_group()` returns a `RadioButton::Group` by value, and an unnamed rvalue cannot be passed as the lvalue reference needed by `set_group()`. Instead, you must assign the result of `get_group()` to a variable and pass that to `set_group()` as an lvalue:

```
auto rb1 = Gtk::make_managed<Gtk::RadioButton>("button1");
auto rb2 = Gtk::make_managed<Gtk::RadioButton>("button2");
auto rb3 = Gtk::make_managed<Gtk::RadioButton>("button3");
auto group = rb1->get_group();
rb2->set_group(group);
rb3->set_group(group);
```

This works because the group is really a handle and therefore can be discarded once it has been used to tell the radio buttons to group with each other. Still, as `join_group()` does the same thing in one less line, you might not find much use for this pattern, but it is shown for completeness.

The second way to set up radio buttons is to make a group first, and then add radio buttons to it. Here's an example:

---



```
Gtk::RadioButton::Group group;  
auto rb1 = Gtk::make_managed<Gtk::RadioButton>(group, "button1");  
auto rb2 = Gtk::make_managed<Gtk::RadioButton>(group, "button2");  
auto rb3 = Gtk::make_managed<Gtk::RadioButton>(group, "button3");
```

We made a new group by simply declaring a variable, `group`, of type `Gtk::RadioButton::Group`. Then we made three radio buttons, using a constructor to make each of them part of `group`.

### 5.4.2 Methods

`RadioButtons` are "off" when created; this means that when you first make a group of them, they will all be off. Don't forget to turn one of them on using `set_active()`:

[Reference](#)

### 5.4.3 Example

The following example demonstrates the use of `RadioButtons`:




Figure 5.3: RadioButton

[Source Code](#)

File: `radiobuttons.h` (For use with `gtkmm 3`)

---

```
#ifndef GTKMM_EXAMPLE_RADIOBUTTONS_H
#define GTKMM_EXAMPLE_RADIOBUTTONS_H

#include <gtkmm/box.h>
#include <gtkmm/window.h>
#include <gtkmm/radiobutton.h>
#include <gtkmm/separator.h>

class RadioButtons : public Gtk::Window
{
public:
    RadioButtons();
    virtual ~RadioButtons();

protected:
    //Signal handlers:
    void on_button_clicked();

    //Child widgets:
    Gtk::Box m_Box_Top, m_Box1, m_Box2;
    Gtk::RadioButton m_RadioButton1, m_RadioButton2, m_RadioButton3;
    Gtk::Separator m_Separator;
    Gtk::Button m_Button_Close;
};

#endif //GTKMM_EXAMPLE_RADIOBUTTONS_H
```

**File: main.cc (For use with gtkmm 3)**

```
#include "radiobuttons.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    RadioButtons buttons;

    //Shows the window and returns when it is closed.
    return app->run(buttons);
}
```

**File: radiobuttons.cc (For use with gtkmm 3)**

```
#include "radiobuttons.h"
```

---

```
RadioButtons::RadioButtons() :
    m_Box_Top(Gtk::ORIENTATION_VERTICAL),
    m_Box1(Gtk::ORIENTATION_VERTICAL, 10),
    m_Box2(Gtk::ORIENTATION_VERTICAL, 10),
    m_RadioButton1("button1"),
    m_RadioButton2("button2"),
    m_RadioButton3("button3"),
    m_Button_Close("close")
{
    // Set title and border of the window
    set_title("radio buttons");
    set_border_width(0);

    // Put radio buttons 2 and 3 in the same group as 1:
    m_RadioButton2.join_group(m_RadioButton1);
    m_RadioButton3.join_group(m_RadioButton1);

    // Add outer box to the window (because the window
    // can only contain a single widget)
    add(m_Box_Top);

    //Put the inner boxes and the separator in the outer box:
    m_Box_Top.pack_start(m_Box1);
    m_Box_Top.pack_start(m_Separator);
    m_Box_Top.pack_start(m_Box2);

    // Set the inner boxes' borders
    m_Box2.set_border_width(10);
    m_Box1.set_border_width(10);

    // Put the radio buttons in Box1:
    m_Box1.pack_start(m_RadioButton1);
    m_Box1.pack_start(m_RadioButton2);
    m_Box1.pack_start(m_RadioButton3);

    // Set the second button active
    m_RadioButton2.set_active();

    // Put Close button in Box2:
    m_Box2.pack_start(m_Button_Close);

    // Make the button the default widget
    m_Button_Close.set_can_default();
    m_Button_Close.grab_default();

    // Connect the clicked signal of the button to
    // RadioButtons::on_button_clicked()
```

```
m_Button_Close.signal_clicked().connect(sigc::mem_fun(*this,
    &RadioButtons::on_button_clicked) );

// Show all children of the window
show_all_children();
}

RadioButtons::~RadioButtons()
{
}

void RadioButtons::on_button_clicked()
{
    hide(); //to close the application.
}
```

## Chapter 6

# Range Widgets

`Gtk::Scale` and `Gtk::Scrollbar` both inherit from `Gtk::Range` and share much functionality. They contain a "trough" and a "slider" (sometimes called a "thumbwheel" in other GUI environments). Dragging the slider with the pointer moves it within the trough, while clicking in the trough advances the slider towards the location of the click, either completely, or by a designated amount, depending on which mouse button is used. This should be familiar scrollbar behaviour.

As will be explained in the [Adjustment](#) section, all Range widgets are associated with a `Adjustment` object. To change the lower, upper, and current values used by the widget you need to use the methods of its `Adjustment`, which you can get with the `get_adjustment()` method. The Range widgets' default constructors create an `Adjustment` automatically, or you can specify an existing `Adjustment`, maybe to share it with another widget. See the [Adjustments](#) section for further details.

[Reference](#)

### 6.1 Scrollbar Widgets

These are standard scrollbars. They should be used only to scroll another widget, such as, a `Gtk::Entry`, or a `Gtk::Viewport`, though it's usually easier to use the `Gtk::ScrolledWindow` widget in most cases.

The orientation of a `Gtk::Scrollbar` can be either horizontal or vertical.

[Reference](#)

---

## 6.2 Scale Widgets

`Gtk::Scale` widgets (or "sliders") allow the user to visually select and manipulate a value within a specific range. You might use one, for instance, to adjust the magnification level on a zoomed preview of a picture, or to control the brightness of a colour, or to specify the number of minutes of inactivity before a screensaver takes over the screen.

As with `Scrollbar`s, the orientation can be either horizontal or vertical. The default constructor creates an `Adjustment` with all of its values set to `0.0`. This isn't useful so you will need to set some `Adjustment` details to get meaningful behaviour.

### 6.2.1 Useful methods

`Scale` widgets can display their current value as a number next to the trough. By default they show the value, but you can change this with the `set_draw_value()` method.

The value displayed by a scale widget is rounded to one decimal point by default, as is the `value` field in its `Gtk::Adjustment`. You can change this with the `set_digits()` method.

Also, the value can be drawn in different positions relative to the trough, specified by the `set_value_pos()` method.

[Reference](#)

## 6.3 Example

This example displays a window with three range widgets all connected to the same adjustment, along with a couple of controls for adjusting some of the parameters mentioned above and in the section on adjustments, so you can see how they affect the way these widgets work for the user.

---




Figure 6.1: Range Widgets

### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_RANGEWIDGETS_H
#define GTKMM_EXAMPLE_RANGEWIDGETS_H

#include <gtkmm.h>
```

```
class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_checkbutton_toggled();
    void on_combo_position();
    void on_adjustment1_value_changed();
    void on_adjustment2_value_changed();
    void on_button_quit();

    //Child widgets:
    Gtk::Box m_VBox_Top, m_VBox2, m_VBox_HScale;
    Gtk::Box m_HBox_Scales, m_HBox_Combo, m_HBox_Digits, m_HBox_PageSize;

    Glib::RefPtr<Gtk::Adjustment> m_adjustment, m_adjustment_digits, ↵
        m_adjustment_pagesize;

    Gtk::Scale m_VScale;
    Gtk::Scale m_HScale, m_Scale_Digits, m_Scale_PageSize;

    Gtk::Separator m_Separator;

    Gtk::CheckButton m_CheckButton;

    Gtk::Scrollbar m_Scrollbar;

    //Tree model columns:
    class ModelColumns : public Gtk::TreeModel::ColumnRecord
    {
    public:

        ModelColumns()
        { add(m_col_position_type); add(m_col_title); }

        Gtk::TreeModelColumn<Gtk::PositionType> m_col_position_type;
        Gtk::TreeModelColumn<Glib::ustring> m_col_title;
    };

    ModelColumns m_Columns;

    //Child widgets:
    Gtk::ComboBox m_ComboBox_Position;
    Glib::RefPtr<Gtk::ListStore> m_refTreeModel;
```

---



```
    Gtk::Button m_Button_Quit;
};

#endif //GTKMM_EXAMPLE_RANGEWIDGETS_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
:
    m_VBox_Top(Gtk::ORIENTATION_VERTICAL, 0),
    m_VBox2(Gtk::ORIENTATION_VERTICAL, 20),
    m_VBox_HScale(Gtk::ORIENTATION_VERTICAL, 10),
    m_HBox_Scales(Gtk::ORIENTATION_HORIZONTAL, 10),
    m_HBox_Combo(Gtk::ORIENTATION_HORIZONTAL, 10),
    m_HBox_Digits(Gtk::ORIENTATION_HORIZONTAL, 10),
    m_HBox_PageSize(Gtk::ORIENTATION_HORIZONTAL, 10),

    // Value, lower, upper, step_increment, page_increment, page_size:
    // Note that the page_size value only makes a difference for
    // scrollbar widgets, and the highest value you'll get is actually
    // (upper - page_size).
    m_adjustment( Gtk::Adjustment::create(0.0, 0.0, 101.0, 0.1, 1.0, 1.0) ),
    m_adjustment_digits( Gtk::Adjustment::create(1.0, 0.0, 5.0, 1.0, 2.0) ),
    m_adjustment_pagesize( Gtk::Adjustment::create(1.0, 1.0, 101.0) ),

    m_VScale(m_adjustment, Gtk::ORIENTATION_VERTICAL),
    m_HScale(m_adjustment, Gtk::ORIENTATION_HORIZONTAL),
    m_Scale_Digits(m_adjustment_digits),
    m_Scale_PageSize(m_adjustment_pagesize),

    // A checkbox to control whether the value is displayed or not:
    m_CheckButton("Display value on scale widgets", 0),

    // Reuse the same adjustment again.
    // Notice how this causes the scales to always be updated
    // continuously when the scrollbar is moved.
    m_Scrollbar(m_adjustment),

    m_Button_Quit("Quit")
{
    set_title("range controls");
    set_default_size(300, 350);

    //VScale:
```

```
m_VScale.set_digits(1);
m_VScale.set_value_pos(Gtk::POS_TOP);
m_VScale.set_draw_value();
m_VScale.set_inverted(); // highest value at top

//HScale:
m_HScale.set_digits(1);
m_HScale.set_value_pos(Gtk::POS_TOP);
m_HScale.set_draw_value();

add(m_VBox_Top);
m_VBox_Top.pack_start(m_VBox2);
m_VBox2.set_border_width(10);
m_VBox2.pack_start(m_HBox_Scales);

//Put VScale and HScale (above scrollbar) side-by-side.
m_HBox_Scales.pack_start(m_VScale);
m_HBox_Scales.pack_start(m_VBox_HScale);

m_VBox_HScale.pack_start(m_HScale);

//Scrollbar:
m_VBox_HScale.pack_start(m_Scrollbar);

//CheckButton:
m_CheckButton.set_active();
m_CheckButton.signal_toggled().connect( sigc::mem_fun(*this,
    &ExampleWindow::on_checkbutton_toggled) );
m_VBox2.pack_start(m_CheckButton, Gtk::PACK_SHRINK);

//Position ComboBox:
//Create the Tree model:
m_refTreeModel = Gtk::ListStore::create(m_Columns);
m_ComboBox_Position.set_model(m_refTreeModel);
m_ComboBox_Position.pack_start(m_Columns.m_col_title);

//Fill the ComboBox's Tree Model:
Gtk::TreeModel::Row row = *(m_refTreeModel->append());
row[m_Columns.m_col_position_type] = Gtk::POS_TOP;
row[m_Columns.m_col_title] = "Top";
row = *(m_refTreeModel->append());
row[m_Columns.m_col_position_type] = Gtk::POS_BOTTOM;
row[m_Columns.m_col_title] = "Bottom";
row = *(m_refTreeModel->append());
row[m_Columns.m_col_position_type] = Gtk::POS_LEFT;
row[m_Columns.m_col_title] = "Left";
row = *(m_refTreeModel->append());
```

---

```

row[m_Columns.m_col_position_type] = Gtk::POS_RIGHT;
row[m_Columns.m_col_title] = "Right";

m_VBox2.pack_start(m_HBox_Combo, Gtk::PACK_SHRINK);
m_HBox_Combo.pack_start(
    *Gtk::make_managed<Gtk::Label>("Scale Value Position:", 0), Gtk:: ←
    PACK_SHRINK);
m_HBox_Combo.pack_start(m_ComboBox_Position);
m_ComboBox_Position.signal_changed().connect( sigc::mem_fun(*this, & ←
    ExampleWindow::on_combo_position) );
m_ComboBox_Position.set_active(0); // Top

//Digits:
m_HBox_Digits.pack_start(
    *Gtk::make_managed<Gtk::Label>("Scale Digits:", 0), Gtk::PACK_SHRINK);
m_Scale_Digits.set_digits(0);
m_adjustment_digits->signal_value_changed().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_adjustment1_value_changed));
m_HBox_Digits.pack_start(m_Scale_Digits);

//Page Size:
m_HBox_PageSize.pack_start(
    *Gtk::make_managed<Gtk::Label>("Scrollbar Page Size:", 0),
    Gtk::PACK_SHRINK);
m_Scale_PageSize.set_digits(0);
m_adjustment_pagesize->signal_value_changed().connect(sigc::mem_fun(* ←
    this,
    &ExampleWindow::on_adjustment2_value_changed));
m_HBox_PageSize.pack_start(m_Scale_PageSize);

m_VBox2.pack_start(m_HBox_Digits, Gtk::PACK_SHRINK);
m_VBox2.pack_start(m_HBox_PageSize, Gtk::PACK_SHRINK);
m_VBox_Top.pack_start(m_Separator, Gtk::PACK_SHRINK);
m_VBox_Top.pack_start(m_Button_Quit, Gtk::PACK_SHRINK);

m_Button_Quit.set_can_default();
m_Button_Quit.grab_default();
m_Button_Quit.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_button_quit));
m_Button_Quit.set_border_width(10);

show_all_children();
}

ExampleWindow::~~ExampleWindow()
{
}

```

---

```
void ExampleWindow::on_checkbutton_toggled()
{
    m_VScale.set_draw_value(m_CheckButton.get_active());
    m_HScale.set_draw_value(m_CheckButton.get_active());
}

void ExampleWindow::on_combo_position()
{
    Gtk::TreeModel::iterator iter = m_ComboBox_Position.get_active();
    if(!iter)
        return;

    Gtk::TreeModel::Row row = *iter;
    if(!row)
        return;

    const Gtk::PositionType postype = row[m_Columns.m_col_position_type];

    m_VScale.set_value_pos(postype);
    m_HScale.set_value_pos(postype);
}

void ExampleWindow::on_adjustment1_value_changed()
{
    const double val = m_adjustment_digits->get_value();
    m_VScale.set_digits((int)val);
    m_HScale.set_digits((int)val);
}

void ExampleWindow::on_adjustment2_value_changed()
{
    const double val = m_adjustment_pagesize->get_value();
    m_adjustment->set_page_size(val);
    m_adjustment->set_page_increment(val);

    // Note that we don't have to emit the "changed" signal
    // because gtkmm does this for us.
}

void ExampleWindow::on_button_quit()
{
    hide();
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
```

---

```
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## Chapter 7

# Miscellaneous Widgets

### 7.1 Label

Labels are the main method of placing non-editable text in windows, for instance to place a title next to a `Entry` widget. You can specify the text in the constructor, or later with the `set_text()` or `set_markup()` methods.

The width of the label will be adjusted automatically. You can produce multi-line labels by putting line breaks ("`\n`") in the label string.

The label text can be justified using the `set_justify()` method. The widget is also capable of word-wrapping, which can be activated with `set_line_wrap()`.

`Gtk::Label` support some simple formatting, for instance allowing you to make some text bold, colored, or larger. You can do this by providing a string to `set_markup()`, using the **Pango Markup syntax**. For instance, `<b>bold text</b>` and `<s>strikethrough text</s>` .

**Reference**

#### 7.1.1 Example

Below is a short example to illustrate these functions. This example makes use of the `Frame` widget to better demonstrate the label styles. (The `Frame` widget is explained in the **Frame** section.) It is possible that the first character in `m_Label_Normal` is shown underlined only when you press the **Alt** key.

---




Figure 7.1: Label

### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Child widgets:
    Gtk::Box m_HBox;
    Gtk::Box m_VBox, m_VBox2;
    Gtk::Frame m_Frame_Normal, m_Frame_Multi, m_Frame_Left, m_Frame_Right,
```

```

    m_Frame_LineWrapped, m_Frame_FilledWrapped, m_Frame_Underlined;
    Gtk::Label m_Label_Normal, m_Label_Multi, m_Label_Left, m_Label_Right,
    m_Label_LineWrapped, m_Label_FilledWrapped, m_Label_Underlined;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

File: examplewindow.cc (For use with gtkmm 3)

```

#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
:
    m_HBox(Gtk::ORIENTATION_HORIZONTAL, 5),
    m_VBox(Gtk::ORIENTATION_VERTICAL, 5),
    m_VBox2(Gtk::ORIENTATION_VERTICAL, 5),
    m_Frame_Normal("Normal Label"),
    m_Frame_Multi("Multi-line Label"),
    m_Frame_Left("Left Justified Label"),
    m_Frame_Right("Right Justified Label"),
    m_Frame_LineWrapped("Line wrapped label"),
    m_Frame_FilledWrapped("Filled, wrapped label"),
    m_Frame_Underlined("Underlined label"),
    m_Label_Normal("_This is a Normal label", true),
    m_Label_Multi("This is a Multi-line label.\nSecond line\nThird line"),
    m_Label_Left("This is a Left-Justified\nMulti-line label.\nThird line"),
    m_Label_Right("This is a Right-Justified\nMulti-line label.\nThird line ←"),
    m_Label_Underlined("This label is underlined!\n"
        "This one is underlined in quite a funky fashion")
{
    set_title("Label");
    set_border_width(5);

    add(m_HBox);

    m_HBox.pack_start(m_VBox, Gtk::PACK_SHRINK);

    m_Frame_Normal.add(m_Label_Normal);
    m_VBox.pack_start(m_Frame_Normal, Gtk::PACK_SHRINK);

    m_Frame_Multi.add(m_Label_Multi);
    m_VBox.pack_start(m_Frame_Multi, Gtk::PACK_SHRINK);

    m_Label_Left.set_justify(Gtk::JUSTIFY_LEFT);
    m_Frame_Left.add(m_Label_Left);
    m_VBox.pack_start(m_Frame_Left, Gtk::PACK_SHRINK);

```

---



```

m_Label_Right.set_justify(Gtk::JUSTIFY_RIGHT);
m_Frame_Right.add(m_Label_Right);
m_VBox.pack_start(m_Frame_Right, Gtk::PACK_SHRINK);

m_HBox.pack_start(m_VBox2, Gtk::PACK_SHRINK);

m_Label_LineWrapped.set_text(
    "This is an example of a line-wrapped label. It "
    /* add a big space to the next line to test spacing */
    "should not be taking up the entire "
    "width allocated to it, but automatically "
    "wraps the words to fit. "
    "The time has come, for all good men, to come to "
    "the aid of their party. "
    "The sixth sheik's six sheep's sick.\n"
    "    It supports multiple paragraphs correctly, "
    "and correctly adds "
    "many      extra spaces. ");
m_Label_LineWrapped.set_line_wrap();
m_Frame_LineWrapped.add(m_Label_LineWrapped);
m_VBox2.pack_start(m_Frame_LineWrapped, Gtk::PACK_SHRINK);

m_Label_FilledWrapped.set_text(
    "This is an example of a line-wrapped, filled label. "
    "It should be taking "
    "up the entire      width allocated to it. "
    "Here is a sentence to prove "
    "my point. Here is another sentence. "
    "Here comes the sun, do de do de do.\n"
    "    This is a new paragraph.\n"
    "    This is another newer, longer, better "
    "paragraph. It is coming to an end, "
    "unfortunately.");
m_Label_FilledWrapped.set_justify(Gtk::JUSTIFY_FILL);
m_Label_FilledWrapped.set_line_wrap();
m_Frame_FilledWrapped.add(m_Label_FilledWrapped);
m_VBox2.pack_start(m_Frame_FilledWrapped, Gtk::PACK_SHRINK);

m_Label_Underlined.set_justify(Gtk::JUSTIFY_LEFT);
m_Label_Underlined.set_pattern (
    "_____ - _____ - _____"
    "    _  _____ ");
m_Frame_Underlined.add(m_Label_Underlined);
m_VBox2.pack_start(m_Frame_Underlined, Gtk::PACK_SHRINK);

show_all_children();

```

---

```
}

ExampleWindow::~ExampleWindow()
{
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## 7.2 Entry

### 7.2.1 Simple Use

Entry widgets allow the user to enter text. You can change the contents with the `set_text()` method, and read the current contents with the `get_text()` method.

Occasionally you might want to make an Entry widget read-only. This can be done by passing `false` to the `set_editable()` method.

For the input of passwords, passphrases and other information you don't want echoed on the screen, calling `set_visibility()` with `false` will cause the text to be hidden.

You might want to be notified whenever the user types in a text entry widget. `Gtk::Entry` provides two signals, `activate` and `changed`, for this purpose. `activate` is emitted when the user presses the Enter key in a text-entry widget; `changed` is emitted when the text in the widget changes. You can use these, for instance, to validate or filter the text the user types. Moving the keyboard focus to another widget may also signal that the user has finished entering text. The `focus_out_event` signal that `Gtk::Entry` inherits from `Gtk::Widget` can notify you when that happens. The [ComboBox with an Entry](#) section contains example programs that use these signals.

If you pass `true` to the `set_activates_default()` method, pressing Enter in the `Gtk::Entry` will activate the default widget for the window containing the `Gtk::Entry`. This is especially useful in dialog boxes. The default widget is usually one of the dialog buttons, which e.g. will close the

---

dialog box. To set a widget as the default widget, use `Gtk::Widget::set_can_default()` and `Gtk::Widget::grab_default()`.

## Reference

### 7.2.1.1 Simple Entry Example

This example uses `Gtk::Entry`. It also has two `CheckButtons`, with which you can toggle the editable and visible flags.




Figure 7.2: Entry

## Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_checkbox_editable_toggled();
    void on_checkbox_visibility_toggled();
    void on_button_close();
};
```

```
//Child widgets:
Gtk::Box m_HBox;
Gtk::Box m_VBox;
Gtk::Entry m_Entry;
Gtk::Button m_Button_Close;
Gtk::CheckButton m_CheckButton_Editable, m_CheckButton_Visible;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_Close("Close"),
  m_CheckButton_Editable("Editable"),
  m_CheckButton_Visible("Visible")
{
  set_size_request(200, 100);
  set_title("Gtk::Entry");

  add(m_VBox);

  m_Entry.set_max_length(50);
  m_Entry.set_text("hello");
  m_Entry.set_text(m_Entry.get_text() + " world");
  m_Entry.select_region(0, m_Entry.get_text_length());
  m_VBox.pack_start(m_Entry);

  // Note that add() can also be used instead of pack_xxx()
  m_VBox.add(m_HBox);

  m_HBox.pack_start(m_CheckButton_Editable);
  m_CheckButton_Editable.signal_toggled().connect( sigc::mem_fun(*this,
    &ExampleWindow::on_checkbox_editable_toggled) );
  m_CheckButton_Editable.set_active(true);

  m_HBox.pack_start(m_CheckButton_Visible);
  m_CheckButton_Visible.signal_toggled().connect( sigc::mem_fun(*this,
    &ExampleWindow::on_checkbox_visibility_toggled) );
  m_CheckButton_Visible.set_active(true);

  m_Button_Close.signal_clicked().connect( sigc::mem_fun(*this,
    &ExampleWindow::on_button_close) );
  m_VBox.pack_start(m_Button_Close);
```

```
m_Button_Close.set_can_default();
m_Button_Close.grab_default();

show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_checkbox_editable_toggled()
{
    m_Entry.set_editable(m_CheckButton_Editable.get_active());
}

void ExampleWindow::on_checkbox_visibility_toggled()
{
    m_Entry.set_visibility(m_CheckButton_Visible.get_active());
}

void ExampleWindow::on_button_close()
{
    hide();
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

### 7.2.2 Entry Completion

A `Entry` widget can offer a drop-down list of pre-existing choices based on the first few characters typed by the user. For instance, a search dialog could suggest text from previous searches.

---

To enable this functionality, you must create a `EntryCompletion` object, and provide it to the `Entry` widget via the `set_completion()` method.

The `EntryCompletion` may use a `TreeModel` containing possible entries, specified with `set_model()`. You should then call `set_text_column()` to specify which of your model columns should be used to match possible text entries.

Alternatively, if a complete list of possible entries would be too large or too inconvenient to generate, a callback slot may instead be specified with `set_match_func()`. This is also useful if you wish to match on a part of the string other than the start.

### Reference

#### 7.2.2.1 Entry Completion Example

This example creates a `Gtk::EntryCompletion` and associates it with a `Gtk::Entry` widget. The completion uses a `Gtk::TreeModel` of possible entries, and some additional actions.




Figure 7.3: Entry Completion

### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>
```

```

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_close();

    void on_completion_action_activated(int index);

    //See the comment in the implementation:
    //bool on_completion_match(const Glib::ustring& key, const Gtk::↳
        TreeModel::const_iterator& iter);

    //Tree model columns, for the EntryCompletion's filter model:
    class ModelColumns : public Gtk::TreeModel::ColumnRecord
    {
    public:

        ModelColumns()
        { add(m_col_id); add(m_col_name); }

        Gtk::TreeModelColumn<unsigned int> m_col_id;
        Gtk::TreeModelColumn<Glib::ustring> m_col_name;
    };

    ModelColumns m_Columns;

    typedef std::map<int, Glib::ustring> type_actions_map;
    type_actions_map m_CompletionActions;

    //Child widgets:
    Gtk::Box m_HBox;
    Gtk::Box m_VBox;
    Gtk::Entry m_Entry;
    Gtk::Label m_Label;
    Gtk::Button m_Button_Close;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
```

---

```
#include <iostream>

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Label("Press a or b to see a list of possible completions and actions ←
        ."),
  m_Button_Close("Close")
{
    //set_size_request(200, 100);
    set_title("Gtk::EntryCompletion");

    add(m_VBox);
    m_VBox.pack_start(m_Entry, Gtk::PACK_SHRINK);

    m_VBox.pack_start(m_Label, Gtk::PACK_EXPAND_WIDGET);

    m_Button_Close.signal_clicked().connect( sigc::mem_fun(*this,
        &ExampleWindow::on_button_close) );
    m_VBox.pack_start(m_Button_Close, Gtk::PACK_SHRINK);
    m_Button_Close.set_can_default();
    m_Button_Close.grab_default();

    //Add an EntryCompletion:
    auto completion =
        Gtk::EntryCompletion::create();
    m_Entry.set_completion(completion);

    //Create and fill the completion's filter model
    auto refCompletionModel =
        Gtk::ListStore::create(m_Columns);
    completion->set_model(refCompletionModel);

    // For more complex comparisons, use a filter match callback, like this.
    // See the comment below for more details:
    //completion->set_match_func( sigc::mem_fun(*this,
        //&ExampleWindow::on_completion_match) );

    //Fill the TreeView's model
    Gtk::TreeModel::Row row = *(refCompletionModel->append());
    row[m_Columns.m_col_id] = 1;
    row[m_Columns.m_col_name] = "Alan Zebedee";

    row = *(refCompletionModel->append());
    row[m_Columns.m_col_id] = 2;
    row[m_Columns.m_col_name] = "Adrian Boo";

    row = *(refCompletionModel->append());
```

---



```
row[m_Columns.m_col_id] = 3;
row[m_Columns.m_col_name] = "Bob McRoberts";

row = *(refCompletionModel->append());
row[m_Columns.m_col_id] = 4;
row[m_Columns.m_col_name] = "Bob McBob";

//Tell the completion what model column to use to
// look for a match (when we use the default matching, instead of
// set_match_func().
// display text in the entry when a match is found.
completion->set_text_column(m_Columns.m_col_name);

//Add actions to the completion:
//These are just extra items shown at the bottom of the list of possible
//completions.

//Remember them for later.
m_CompletionActions[0] = "Use Wizard";
m_CompletionActions[1] = "Browse for Filename";

for(const auto& the_pair : m_CompletionActions)
{
    auto position = the_pair.first;
    auto title = the_pair.second;
    completion->insert_action_text(title, position);
}

completion->signal_action_activated().connect( sigc::mem_fun(*this,
    &ExampleWindow::on_completion_action_activated) );

show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_close()
{
    hide();
}

/* You can do more complex matching with a handler like this.
 * For instance, you could check for substrings inside the string instead ↵
 * of the start,
 * or you could look for the key in extra model columns as well as the ↵
```

---

```

    model column that will be displayed.
    * The code here is not actually more complex - it's a reimplementaion of ↵
      the default behaviour.
    *
bool ExampleWindow::on_completion_match(const Glib::ustring& key, const
    Gtk::TreeModel::const_iterator& iter)
{
    if(iter)
    {
        Gtk::TreeModel::Row row = *iter;

        Glib::ustring::size_type key_length = key.size();
        Glib::ustring filter_string = row[m_Columns.m_col_name];

        Glib::ustring filter_string_start = filter_string.substr(0, key_length ↵
        );
        //The key is lower-case, even if the user input is not.
        filter_string_start = filter_string_start.lowercase();

        if(key == filter_string_start)
            return true; //A match was found.
    }

    return false; //No match.
}
*/

void ExampleWindow::on_completion_action_activated(int index)
{
    type_actions_map::iterator iter = m_CompletionActions.find(index);
    if(iter != m_CompletionActions.end()) //If it's in the map
    {
        Glib::ustring title = iter->second;
        std::cout << "Action selected: " << title << std::endl;
    }
}

```

**File: main.cc (For use with gtkmm 3)**

```

#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

```

```
//Shows the window and returns when it is closed.  
return app->run(window);  
}
```

## 7.2.3 Entry Icons

An Entry widget can show an icon at the start or end of the text area. The icon can be specified by methods such as `set_icon_from_pixbuf()` or `set_icon_from_icon_name()`. An application can respond to the user pressing the icon by handling the `signal_icon_press` signal.

### 7.2.3.1 Entry Icon Example

This example shows a `Gtk::Entry` widget with a named search icon, and prints text to the terminal when the icon is pressed.




Figure 7.4: Entry with Icon

#### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H  
#define GTKMM_EXAMPLEWINDOW_H  
  
#include <gtkmm.h>  
  
class ExampleWindow : public Gtk::Window  
{  
public:  
    ExampleWindow();  
    virtual ~ExampleWindow();  
  
protected:  
    //Signal handlers:
```

```

void on_icon_pressed(Gtk::EntryIconPosition icon_pos, const ↵
    GdkEventButton* event);
void on_button_close();

//Child widgets:
Gtk::Box m_VBox;
Gtk::Entry m_Entry;
Gtk::Button m_Button_Close;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

File: examplewindow.cc (For use with gtkmm 3)

```

#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_Close("Close")
{
    set_title("Gtk::Entry");

    add(m_VBox);

    m_Entry.set_max_length(50);
    m_Entry.set_text("Hello world");
    m_VBox.pack_start(m_Entry, Gtk::PACK_SHRINK);

    m_Entry.set_icon_from_icon_name("edit-find");
    m_Entry.signal_icon_press().connect( sigc::mem_fun(*this, &ExampleWindow ↵
        ::on_icon_pressed) );

    m_Button_Close.signal_clicked().connect( sigc::mem_fun(*this,
        &ExampleWindow::on_button_close) );
    m_VBox.pack_start(m_Button_Close, Gtk::PACK_SHRINK);
    m_Button_Close.set_can_default();
    m_Button_Close.grab_default();

    show_all_children();
}

ExampleWindow::~~ExampleWindow()
{
}

```

```
void ExampleWindow::on_icon_pressed(Gtk::EntryIconPosition /* icon_pos */, ↵
    const GdkEventButton* /* event */)
{
    std::cout << "Icon pressed." << std::endl;
}

void ExampleWindow::on_button_close()
{
    hide();
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## 7.2.4 Entry Progress

An `Entry` widget can show a progress bar inside the text area, under the entered text. The progress bar will be shown if the `set_progress_fraction()` or `set_progress_pulse_step()` methods are called.

### 7.2.4.1 Entry Progress Example

This example shows a `Gtk::Entry` widget with a progress bar.

---




Figure 7.5: Entry with Progress Bar

### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    bool on_timeout();
    void on_button_close();

    //Child widgets:
    Gtk::Box m_VBox;
    Gtk::Entry m_Entry;
    Gtk::Button m_Button_Close;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: `examplewindow.cc` (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_Close("Close")
```

```
{
    set_title("Gtk::Entry");

    add(m_VBox);

    m_Entry.set_max_length(50);
    m_Entry.set_text("Hello world");
    m_VBox.pack_start(m_Entry, Gtk::PACK_SHRINK);

    //Change the progress fraction every 0.1 second:
    Glib::signal_timeout().connect(
        sigc::mem_fun(*this, &ExampleWindow::on_timeout),
        100
    );

    m_Button_Close.signal_clicked().connect( sigc::mem_fun(*this,
        &ExampleWindow::on_button_close) );
    m_VBox.pack_start(m_Button_Close, Gtk::PACK_SHRINK);
    m_Button_Close.set_can_default();
    m_Button_Close.grab_default();

    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

bool ExampleWindow::on_timeout()
{
    static double fraction = 0;
    m_Entry.set_progress_fraction(fraction);

    fraction += 0.01;
    if(fraction > 1)
        fraction = 0;

    return true;
}

void ExampleWindow::on_button_close()
{
    hide();
}
```

File: main.cc (For use with gtkmm 3)

---

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## 7.3 SpinButton

A `SpinButton` allows the user to select a value from a range of numeric values. It has an `Entry` widget with increment and decrement buttons at the side. Clicking the buttons causes the value to 'spin' up and down across the range of possible values. The `Entry` widget may also be used to enter a value directly.

The value can have an adjustable number of decimal places, and the step size is configurable. `SpinButtons` have an 'auto-repeat' feature as well: holding down the increment or decrement button can optionally cause the value to change more quickly the longer the button is held down.

`SpinButtons` use an **Adjustment** object to hold information about the range of values. These Adjustment attributes are used by the Spin Button like so:

- `value`: value for the Spin Button
- `lower`: lower range value
- `upper`: upper range value
- `step_increment`: value to increment/decrement when pressing mouse button 1 on a button
- `page_increment`: value to increment/decrement when pressing mouse button 2 on a button
- `page_size`: unused

Additionally, mouse button 3 can be used to jump directly to the `upper` or `lower` values.

The `SpinButton` can create a default `Adjustment`, which you can access via the `get_adjustment()` method, or you can specify an existing `Adjustment` in the constructor.

---



### 7.3.1 Methods

The number of decimal places can be altered using the `set_digits()` method.

You can set the `spinbutton`'s value using the `set_value()` method, and retrieve it with `get_value()`.

The `spin()` method 'spins' the `SpinButton`, as if its increment or decrement button had been clicked. You need to specify a `Gtk::SpinType` to specify the direction or new position.

To prevent the user from typing non-numeric characters into the entry box, pass `true` to the `set_numeric()` method.

To make the `SpinButton` 'wrap' between its upper and lower bounds, use the `set_wrap()` method.

To force it to snap to the nearest `step_increment`, use `set_snap_to_ticks()`.

#### Reference

### 7.3.2 Example

Here's an example of a `SpinButton` in action:




Figure 7.6: SpinButton

### Source Code

File: examplewindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();
};
```

```
protected:
    //Signal handlers:
    void on_checkbutton_snap();
    void on_checkbutton_numeric();
    void on_spinbutton_digits_changed();
    void on_button_close();

    enum enumValueFormats
    {
        VALUE_FORMAT_INT,
        VALUE_FORMAT_FLOAT
    };
    void on_button_getvalue(enumValueFormats display);

    //Child widgets:
    Gtk::Frame m_Frame_NotAccelerated, m_Frame_Accelerated;
    Gtk::Box m_HBox_NotAccelerated, m_HBox_Accelerated,
        m_HBox_Buttons;
    Gtk::Box m_VBox_Main, m_VBox, m_VBox_Day, m_VBox_Month, m_VBox_Year,
        m_VBox_Accelerated, m_VBox_Value, m_VBox_Digits;
    Gtk::Label m_Label_Day, m_Label_Month, m_Label_Year,
        m_Label_Value, m_Label_Digits,
        m_Label_ShowValue;
    Glib::RefPtr<Gtk::Adjustment> m_adjustment_day, m_adjustment_month, ↵
        m_adjustment_year,
        m_adjustment_value, m_adjustment_digits;
    Gtk::SpinButton m_SpinButton_Day, m_SpinButton_Month, m_SpinButton_Year,
        m_SpinButton_Value, m_SpinButton_Digits;
    Gtk::CheckButton m_CheckButton_Snap, m_CheckButton_Numeric;
    Gtk::Button m_Button_Int, m_Button_Float, m_Button_Close;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

**File:** examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>
#include <cstdio>

ExampleWindow::ExampleWindow()
:
    m_Frame_NotAccelerated("Not accelerated"),
    m_Frame_Accelerated("Accelerated"),
    m_VBox_Main(Gtk::ORIENTATION_VERTICAL, 5),
    m_VBox(Gtk::ORIENTATION_VERTICAL),
    m_VBox_Day(Gtk::ORIENTATION_VERTICAL),
    m_VBox_Month(Gtk::ORIENTATION_VERTICAL),
```

```

m_VBox_Year(Gtk::ORIENTATION_VERTICAL),
m_VBox_Accelerated(Gtk::ORIENTATION_VERTICAL),
m_VBox_Value(Gtk::ORIENTATION_VERTICAL),
m_VBox_Digits(Gtk::ORIENTATION_VERTICAL),
m_Label_Day("Day: ", Gtk::ALIGN_START),
m_Label_Month("Month: ", Gtk::ALIGN_START),
m_Label_Year("Year: ", Gtk::ALIGN_START),
m_Label_Value("Value: ", Gtk::ALIGN_START),
m_Label_Digits("Digits: ", Gtk::ALIGN_START),
m_adjustment_day( Gtk::Adjustment::create(1.0, 1.0, 31.0, 1.0, 5.0, 0.0) ←
),
m_adjustment_month( Gtk::Adjustment::create(1.0, 1.0, 12.0, 1.0, 5.0, ←
0.0) ),
m_adjustment_year( Gtk::Adjustment::create(2012.0, 1.0, 2200.0, 1.0, ←
100.0, 0.0) ),
m_adjustment_value( Gtk::Adjustment::create(0.0, -10000.0, 10000.0, 0.5, ←
100.0, 0.0) ),
m_adjustment_digits( Gtk::Adjustment::create(2.0, 1.0, 5.0, 1.0, 1.0, ←
0.0) ),
m_SpinButton_Day(m_adjustment_day),
m_SpinButton_Month(m_adjustment_month),
m_SpinButton_Year(m_adjustment_year),
m_SpinButton_Value(m_adjustment_value, 1.0, 2),
m_SpinButton_Digits(m_adjustment_digits),
m_CheckButton_Snap("Snap to 0.5-ticks"),
m_CheckButton_Numeric("Numeric only input mode"),
m_Button_Int("Value as Int"),
m_Button_Float("Value as Float"),
m_Button_Close("Close")
{
    set_title("SpinButton");

    m_VBox_Main.set_border_width(10);
    add(m_VBox_Main);

    m_VBox_Main.pack_start(m_Frame_NotAccelerated);

    m_VBox.set_border_width(5);
    m_Frame_NotAccelerated.add(m_VBox);

    /* Day, month, year spinners */

    m_VBox.pack_start(m_HBox_NotAccelerated, Gtk::PACK_EXPAND_WIDGET, 5);

    m_VBox_Day.pack_start(m_Label_Day);

    m_SpinButton_Day.set_wrap();

```

```
m_VBox_Day.pack_start(m_SpinButton_Day);

m_HBox_NotAccelerated.pack_start(m_VBox_Day, Gtk::PACK_EXPAND_WIDGET, 5) ←
;

m_VBox_Month.pack_start(m_Label_Month);

m_SpinButton_Month.set_wrap();
m_VBox_Month.pack_start(m_SpinButton_Month);

m_HBox_NotAccelerated.pack_start(m_VBox_Month, Gtk::PACK_EXPAND_WIDGET, ←
5);

m_VBox_Year.pack_start(m_Label_Year);

m_SpinButton_Year.set_wrap();
m_SpinButton_Year.set_size_request(55, -1);
m_VBox_Year.pack_start(m_SpinButton_Year);

m_HBox_NotAccelerated.pack_start(m_VBox_Year, Gtk::PACK_EXPAND_WIDGET, ←
5);

//Accelerated:
m_VBox_Main.pack_start(m_Frame_Accelerated);

m_VBox_Accelerated.set_border_width(5);
m_Frame_Accelerated.add(m_VBox_Accelerated);

m_VBox_Accelerated.pack_start(m_HBox_Accelerated, Gtk:: ←
PACK_EXPAND_WIDGET, 5);

m_HBox_Accelerated.pack_start(m_VBox_Value, Gtk::PACK_EXPAND_WIDGET, 5);

m_VBox_Value.pack_start(m_Label_Value);

m_SpinButton_Value.set_wrap();
m_SpinButton_Value.set_size_request(100, -1);
m_VBox_Value.pack_start(m_SpinButton_Value);

m_HBox_Accelerated.pack_start(m_VBox_Digits, Gtk::PACK_EXPAND_WIDGET, 5) ←
;

m_VBox_Digits.pack_start(m_Label_Digits);

m_SpinButton_Digits.set_wrap();
m_adjustment_digits->signal_value_changed().connect( sigc::mem_fun(*this ←
```

---

```

        &ExampleWindow::on_spinbutton_digits_changed) );

m_VBox_Digits.pack_start(m_SpinButton_Digits);

//CheckButtons:
m_VBox_Accelerated.pack_start(m_CheckButton_Snap);
m_CheckButton_Snap.set_active();
m_CheckButton_Snap.signal_clicked().connect( sigc::mem_fun(*this,
        &ExampleWindow::on_checkbutton_snap) );

m_VBox_Accelerated.pack_start(m_CheckButton_Numeric);
m_CheckButton_Numeric.set_active();
m_CheckButton_Numeric.signal_clicked().connect( sigc::mem_fun(*this,
        &ExampleWindow::on_checkbutton_numeric) );

//Buttons:
m_VBox_Accelerated.pack_start (m_HBox_Buttons, Gtk::PACK_SHRINK, 5);

m_Button_Int.signal_clicked().connect( sigc::bind( sigc::mem_fun(*this,
        &ExampleWindow::on_button_getvalue), VALUE_FORMAT_INT) ) ←
        ;
m_HBox_Buttons.pack_start(m_Button_Int, Gtk::PACK_EXPAND_WIDGET, 5);

m_Button_Float.signal_clicked().connect( sigc::bind( sigc::mem_fun(*this ←
        ,
        &ExampleWindow::on_button_getvalue), VALUE_FORMAT_FLOAT) ←
        );
m_HBox_Buttons.pack_start(m_Button_Float, Gtk::PACK_EXPAND_WIDGET, 5);

m_VBox_Accelerated.pack_start(m_Label_ShowValue);
m_Label_ShowValue.set_text ("0");

//Close button:
m_Button_Close.signal_clicked().connect( sigc::mem_fun(*this,
        &ExampleWindow::on_button_close) );
m_VBox_Main.pack_start(m_Button_Close, Gtk::PACK_SHRINK);

show_all_children();
}

ExampleWindow::~~ExampleWindow()
{
}

```

```
void ExampleWindow::on_button_close()
{
    hide();
}

void ExampleWindow::on_checkbutton_snap()
{
    m_SpinButton_Value.set_snap_to_ticks( m_CheckButton_Snap.get_active() );
}

void ExampleWindow::on_checkbutton_numeric()
{
    m_SpinButton_Value.set_numeric( m_CheckButton_Numeric.get_active() );
}

void ExampleWindow::on_spinbutton_digits_changed()
{
    m_SpinButton_Value.set_digits( m_SpinButton_Digits.get_value_as_int() );
}

void ExampleWindow::on_button_getvalue(enumValueFormats display)
{
    gchar buf[32];

    if (display == VALUE_FORMAT_INT)
        sprintf (buf, "%d", m_SpinButton_Value.get_value_as_int());
    else
        sprintf (buf, "%0.*f", m_SpinButton_Value.get_digits(),
                 m_SpinButton_Value.get_value());

    m_Label_ShowValue.set_text (buf);
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

```
}
```

## 7.4 ProgressBar

Progress bars are used to show the status of an ongoing operation. For instance, a `ProgressBar` can show how much of a task has been completed.

To change the value shown, use the `set_fraction()` method, passing a double between 0.0 and 1.0 to provide the new percentage.

A `ProgressBar` is horizontal and left-to-right by default, but you can change it to a vertical progress bar by using the `set_orientation()` method.

### Reference

#### 7.4.1 Activity Mode

Besides indicating the amount of progress that has occurred, the progress bar can also be used to indicate that there is some activity; this is done by placing the progress bar in *activity mode*. In this mode, the progress bar displays a small rectangle which moves back and forth. Activity mode is useful in situations where the progress of an operation cannot be calculated as a value range (e.g., receiving a file of unknown length).

To do this, you need to call the `pulse()` method at regular intervals. You can also choose the step size, with the `set_pulse_step()` method.

The progress bar can also display a configurable text string within its trough, using the `set_text()` method.

---



### 7.4.2 Example




Figure 7.7: ProgressBar

#### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_checkbutton_text();
    void on_checkbutton_activity();
    void on_checkbutton_inverted();

    bool on_timeout();
};
```

```

void on_button_close();

//Child widgets:
Gtk::Box m_VBox;
Gtk::Grid m_Grid;
Gtk::ProgressBar m_ProgressBar;
Gtk::Separator m_Separator;
Gtk::CheckButton m_CheckButton_Text, m_CheckButton_Activity, ↔
    m_CheckButton_Inverted;
Gtk::Button m_Button_Close;

sigc::connection m_connection_timeout;
bool m_bActivityMode;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

File: examplewindow.cc (For use with gtkmm 3)

```

#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL, 5),
  m_CheckButton_Text("Show text"),
  m_CheckButton_Activity("Activity mode"),
  m_CheckButton_Inverted("Right to Left"),
  m_Button_Close("Close"),
  m_bActivityMode(false)
{
    set_resizable();
    set_title("Gtk::ProgressBar");

    m_VBox.set_border_width(10);
    add(m_VBox);

    m_VBox.pack_start(m_ProgressBar, Gtk::PACK_SHRINK, 5);
    m_ProgressBar.set_halign(Gtk::ALIGN_CENTER);
    m_ProgressBar.set_valign(Gtk::ALIGN_CENTER);
    m_ProgressBar.set_text("some text");
    m_ProgressBar.set_show_text(false);

    //Add a timer callback to update the value of the progress bar:
    m_connection_timeout = Glib::signal_timeout().connect(sigc::mem_fun(* ↔
        this,
        &ExampleWindow::on_timeout), 50 );

    m_VBox.pack_start(m_Separator, Gtk::PACK_SHRINK);

```

```
m_VBox.pack_start(m_Grid);
m_Grid.set_row_homogeneous(true);

//Add a check button to select displaying of the trough text:
m_Grid.attach(m_CheckButton_Text, 0, 0, 1, 1);
m_CheckButton_Text.property_margin() = 5;
m_CheckButton_Text.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_checkbutton_text) );

//Add a check button to toggle activity mode:
m_Grid.attach(m_CheckButton_Activity, 0, 1, 1, 1);
m_CheckButton_Activity.property_margin() = 5;
m_CheckButton_Activity.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_checkbutton_activity) );

//Add a check button to select growth from left to right or from right ←
    to left:
m_Grid.attach(m_CheckButton_Inverted, 0, 2, 1, 1);
m_CheckButton_Inverted.property_margin() = 5;
m_CheckButton_Inverted.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_checkbutton_inverted) );

//Add a button to exit the program.
m_VBox.pack_start(m_Button_Close, Gtk::PACK_SHRINK);
m_Button_Close.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_button_close) );
m_Button_Close.set_can_default();
m_Button_Close.grab_default();

show_all_children();
}

ExampleWindow::~~ExampleWindow()
{
}

void ExampleWindow::on_checkbutton_text()
{
    const bool show_text = m_CheckButton_Text.get_active();
    m_ProgressBar.set_show_text(show_text);
}

void ExampleWindow::on_checkbutton_activity()
{
    m_bActivityMode = m_CheckButton_Activity.get_active();

    if(m_bActivityMode)
```

---

```
        m_ProgressBar.pulse();
    else
        m_ProgressBar.set_fraction(0.0);
}

void ExampleWindow::on_checkbutton_inverted()
{
    const bool inverted = m_CheckButton_Inverted.get_active();
    m_ProgressBar.set_inverted(inverted);
}

void ExampleWindow::on_button_close()
{
    hide();
}

/* Update the value of the progress bar so that we get
 * some movement */
bool ExampleWindow::on_timeout()
{
    if(m_bActivityMode)
        m_ProgressBar.pulse();
    else
    {
        double new_val = m_ProgressBar.get_fraction() + 0.01;

        if(new_val > 1.0)
            new_val = 0.0;

        //Set the new value:
        m_ProgressBar.set_fraction(new_val);
    }

    //As this is a timeout function, return true so that it
    //continues to get called
    return true;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;
```

```
//Shows the window and returns when it is closed.  
return app->run(window);  
}
```

## 7.5 InfoBar

An `InfoBar` may show small items of information or ask brief questions. Unlike a `Dialog`, it appears at the top of the current window instead of opening a new window. Its API is very similar to the `Gtk::Dialog` API.

[Reference](#)

### 7.5.1 Example




Figure 7.8: InfoBar

[Source Code](#)

File: `examplewindow.h` (For use with `gtkmm 3`)

---

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_infobar_response(int response);
    void on_button_quit();
    void on_button_clear();
    void on_textbuffer_changed();

    //Child widgets:
    Gtk::Box m_VBox;

    Gtk::ScrolledWindow m_ScrolledWindow;
    Gtk::TextView m_TextView;

    Glib::RefPtr<Gtk::TextBuffer> m_refTextBuffer;

    Gtk::InfoBar m_InfoBar;
    Gtk::Label m_Message_Label;

    Gtk::ButtonBox m_ButtonBox;
    Gtk::Button m_Button_Quit, m_Button_Clear;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

**File:** examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL, 6),
  m_Button_Quit("_Quit", true),
  m_Button_Clear("_Clear", true)
{
    set_title("Gtk::InfoBar example");
    set_border_width(6);
    set_default_size(400, 200);
```

```
add(m_VBox);

// Add the message label to the InfoBar:
auto infoBarContainer =
    dynamic_cast<Gtk::Container*>(m_InfoBar.get_content_area());
if (infoBarContainer)
    infoBarContainer->add(m_Message_Label);

// Add an ok button to the InfoBar:
m_InfoBar.add_button("_OK", 0);

// Add the InfoBar to the vbox:
m_VBox.pack_start(m_InfoBar, Gtk::PACK_SHRINK);

// Create the buffer and set it for the TextView:
m_refTextBuffer = Gtk::TextBuffer::create();
m_TextView.set_buffer(m_refTextBuffer);

// Add the TreeView, inside a ScrolledWindow:
m_ScrolledWindow.add(m_TextView);

// Show the scrollbars only when they are necessary:
m_ScrolledWindow.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC ↵
    );

m_VBox.pack_start(m_ScrolledWindow);

// Add button box:
m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);

m_ButtonBox.pack_start(m_Button_Clear, Gtk::PACK_SHRINK);
m_ButtonBox.pack_start(m_Button_Quit, Gtk::PACK_SHRINK);
m_ButtonBox.set_spacing(6);
m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);

// Connect signals:
m_InfoBar.signal_response().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_infobar_response) );
m_Button_Quit.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_button_quit) );
m_Button_Clear.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_button_clear) );
m_refTextBuffer->signal_changed().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_textbuffer_changed) );

show_all();
```

---

```
// Keep the InfoBar hidden until a message needs to be shown:
m_InfoBar.hide();

// Make the clear button insensitive until text is typed in the buffer. ↵
// When
// the button is sensitive and it is pressed, the InfoBar is displayed ↵
// with a
// message.
m_Button_Clear.set_sensitive(false);
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_infobar_response(int)
{
    // Clear the message and hide the info bar:
    m_Message_Label.set_text("");
    m_InfoBar.hide();
}

void ExampleWindow::on_button_quit()
{
    hide();
}

void ExampleWindow::on_button_clear()
{
    m_refTextBuffer->set_text("");
    m_Message_Label.set_text("Cleared the text.");
    m_InfoBar.set_message_type(Gtk::MESSAGE_INFO);
    m_InfoBar.show();
}

void ExampleWindow::on_textbuffer_changed()
{
    m_Button_Clear.set_sensitive(m_refTextBuffer->size() > 0);
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
```



```
auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

ExampleWindow window;
//Shows the window and returns when it is closed.
return app->run(window);
}
```

## 7.6 Tooltips

Tooltips are the little information windows that pop up when you leave your pointer over a widget for a few seconds. Use `set_tooltip_text()` to set a text string as a tooltip on any `Widget`. `Gtk::ToolItems` are not `Widgets`, but have the same method for convenience. `Gtk::Tooltip` is used for more advanced tooltip usage, such as showing an image as well as text.

[Widget Reference](#)

[Tooltip Reference](#)

### 7.6.1 Example




Figure 7.9: Tooltip

[Source Code](#)

File: examplewindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:

    ExampleWindow();
    virtual ~ExampleWindow();

protected:

    //Methods:
    void prepare_textview();
    void connect_signals();

    //Signal handlers:
    void on_markup_checkbutton_click();
    bool on_textview_query_tooltip(int x, int y, bool keyboard_tooltip, ↵
        const Glib::RefPtr<Gtk::Tooltip>& tooltip);
    bool on_button_query_tooltip(int x, int y, bool keyboard_tooltip, const ↵
        Glib::RefPtr<Gtk::Tooltip>& tooltip);

    //Child widgets:
    Gtk::Box m_vbox;

    Gtk::CheckButton m_checkbutton;
    Gtk::Label m_label;

    Gtk::ScrolledWindow m_scrolled_window;
    Gtk::TextView m_text_view;
    Glib::RefPtr<Gtk::TextBuffer> m_ref_text_buffer;
    Glib::RefPtr<Gtk::TextTag> m_ref_bold_tag;

    Gtk::Button m_button;
    Gtk::Window m_button_tooltip_window;

};

#endif // GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

---

```
#include "examplewindow.h"

#include <vector>

const Glib::ustring app_title = "gtkmm tooltips example";
const Glib::ustring non_markedup_tip = "A tooltip without markup.";
const Glib::ustring markedup_tip = "<i>Markup</i> in a tooltip.";

ExampleWindow::ExampleWindow()
:
  m_vbox(Gtk::ORIENTATION_VERTICAL, 3),
  m_checkbutton("Click to alternate markup in tooltip"),
  m_label("A label"),
  m_button("Custom widget in tooltip window"),
  m_button_tooltip_window(Gtk::WINDOW_POPUP)
{
  //Set up window and the top-level container:
  set_title(app_title);
  set_border_width(10);

  add(m_vbox);

  //Check button with markup in tooltip:
  m_checkbutton.set_tooltip_text(non_markedup_tip);
  m_vbox.pack_start(m_checkbutton, Gtk::PACK_SHRINK);

  //Label:
  m_label.set_tooltip_text("Another tooltip");
  m_vbox.pack_start(m_label, Gtk::PACK_SHRINK);

  //Textview:
  prepare_textview();

  //Button:
  // set_tooltip_window(), like set_tooltip_text(),
  // will call set_has_tooltip() for us.
  m_button.set_tooltip_window(m_button_tooltip_window);
  m_vbox.pack_start(m_button, Gtk::PACK_SHRINK);

  //Button's custom tooltip window:
  m_button_tooltip_window.set_default_size(250, 30);
  Gtk::Label* label =
    Gtk::make_managed<Gtk::Label>("A label in a custom tooltip window");
  label->show();
  m_button_tooltip_window.add(*label);

  connect_signals();
}
```

---

```
    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::prepare_textview()
{
    Gtk::TextIter iter;
    std::vector< Glib::RefPtr<Gtk::TextTag> > tags;

    //Set up a scrolled window:
    m_scrolled_window.add(m_text_view);
    m_scrolled_window.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC);
    m_vbox.pack_start(m_scrolled_window);

    //Create a text buffer with some text:
    m_ref_text_buffer = Gtk::TextBuffer::create();

    iter = m_ref_text_buffer->end();
    m_ref_text_buffer->insert(iter, "Hover over the text ");

    //Insert some text with a tag.
    //In the tooltip signal handler below, we will show a tooltip
    //when mouse pointer is above this tagged text.
    m_ref_bold_tag = m_ref_text_buffer->create_tag("bold");
    m_ref_bold_tag->set_property("weight", Pango::WEIGHT_BOLD);

    tags.push_back(m_ref_bold_tag);

    iter = m_ref_text_buffer->end();
    m_ref_text_buffer->insert_with_tags(iter, "in bold", tags);

    iter = m_ref_text_buffer->end();
    m_ref_text_buffer->insert(iter, " to see its tooltip");

    m_text_view.set_buffer(m_ref_text_buffer);

    m_text_view.set_size_request(320, 50);

    //When only connecting to the query-tooltip signal, and not using any
    //of set_tooltip_text(), set_tooltip_markup() or set_tooltip_window(),
    //we need to explicitly tell GTK+ that the widget has a tooltip which
    //we'll show.
```

---

```
m_text_view.set_has_tooltip();
}

void ExampleWindow::connect_signals()
{
    m_checkbutton.signal_clicked().connect(
        sigc::mem_fun(*this, &ExampleWindow::on_markup_checkbutton_click));

    m_text_view.signal_query_tooltip().connect(
        sigc::mem_fun(*this, &ExampleWindow::on_textview_query_tooltip));

    m_button.signal_query_tooltip().connect(
        sigc::mem_fun(*this, &ExampleWindow::on_button_query_tooltip));
}

void ExampleWindow::on_markup_checkbutton_click()
{
    if (m_checkbutton.get_active() == true)
    {
        m_checkbutton.set_tooltip_markup(markedup_tip);
    }
    else
    {
        m_checkbutton.set_tooltip_markup(non_markedup_tip);
    }
}

bool ExampleWindow::on_textview_query_tooltip(int x, int y, bool ←
    keyboard_tooltip, const Glib::RefPtr<Gtk::Tooltip>& tooltip)
{
    Gtk::TextIter iter;

    if (keyboard_tooltip)
    {
        int offset = m_ref_text_buffer->property_cursor_position().get_value() ←
            ;
        iter = m_ref_text_buffer->get_iter_at_offset(offset);
    }
    else
    {
        int mouse_x, mouse_y, trailing;
        m_text_view.window_to_buffer_coords(Gtk::TEXT_WINDOW_TEXT,
            x, y, mouse_x, mouse_y);
        m_text_view.get_iter_at_position(iter, trailing, mouse_x, mouse_y);
    }

    //Show a tooltip if the cursor or mouse pointer is over the text
```

```
//with the specific tag:
if (iter.has_tag(m_ref_bold_tag))
{
    tooltip->set_markup("<b>Information</b> attached to a text tag");
    tooltip->set_icon_from_icon_name("dialog-information", Gtk::←
        ICON_SIZE_MENU);
}
else
{
    return false;
}

return true;
}

bool ExampleWindow::on_button_query_tooltip(int, int, bool, const Glib::←
    RefPtr<Gtk::Tooltip>&)
{
    //We already have a custom window ready, just return true to show it:
    return true;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## Chapter 8

# Container Widgets

All container widgets derive from `Gtk::Container`, not always directly. Some container widgets, such as `Gtk::Grid` can hold many child widgets, so these typically have more complex interfaces. Others, such as `Gtk::Frame` contain only one child widget.

### 8.1 Single-item Containers

The single-item container widgets derive from `Gtk::Bin`, which provides the `add()` and `remove()` methods for the child widget. Note that `Gtk::Button` and `Gtk::Window` are technically single-item containers, but we have discussed them already elsewhere.

We also discuss the `Gtk::Paned` widget, which allows you to divide a window into two separate "panes". This widget actually contains two child widgets, but the number is fixed so it seems appropriate.

#### 8.1.1 Frame

Frames can enclose one or a group of widgets within a box, optionally with a title. For instance, you might place a group of `RadioButtons` or `CheckButtons` in a `Frame`.

[Reference](#)

---

### 8.1.1.1 Example



Figure 8.1: Frame

#### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
```



```
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Child widgets:
    Gtk::Frame m_Frame;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
{
    /* Set some window properties */
    set_title("Frame Example");
    set_size_request(300, 300);

    /* Sets the border width of the window. */
    set_border_width(10);

    add(m_Frame);

    /* Set the frames label */
    m_Frame.set_label("Gtk::Frame Widget");

    /* Align the label at the right of the frame */
    //m_Frame.set_label_align(Gtk::ALIGN_END, Gtk::ALIGN_START);

    /* Set the style of the frame */
    m_Frame.set_shadow_type(Gtk::SHADOW_ETCHED_OUT);

    show_all_children();
}

ExampleWindow::~~ExampleWindow()
{
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>
```

---

```
int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

### 8.1.2 Paned

Panes divide a widget into two halves, separated by a moveable divider. The two halves (panes) can be oriented either horizontally (side by side) or vertically (one above the other).

Unlike the other widgets in this section, pane widgets contain not one but two child widgets, one in each pane. Therefore, you should use `add1()` and `add2()` instead of the `add()` method.

You can adjust the position of the divider using the `set_position()` method, and you will probably need to do so.

[Reference](#)

### 8.1.2.1 Example




Figure 8.2: Paned

#### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
```

```
#define GTKMM_EXAMPLEWINDOW_H

#include "messageslist.h"
#include "messagetext.h"
#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:

    //Child widgets:
    Gtk::Paned m_VPaned;
    MessagesList m_MessagesList;
    MessageText m_MessageText;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

**File: messageslist.h (For use with gtkmm 3)**

```
#ifndef GTKMM_EXAMPLE_MESSAGESLIST_H
#define GTKMM_EXAMPLE_MESSAGESLIST_H

#include <gtkmm.h>

class MessagesList: public Gtk::ScrolledWindow
{
public:
    MessagesList();
    virtual ~MessagesList();

    class ModelColumns : public Gtk::TreeModel::ColumnRecord
    {
    public:

        ModelColumns()
        { add(m_col_text); }

        Gtk::TreeModelColumn<Glib::ustring> m_col_text;
    };

    ModelColumns m_Columns;

protected:
```

```
Glib::RefPtr<Gtk::ListStore> m_refListStore; //The Tree Model.
Gtk::TreeView m_TreeView; //The Tree View.
};
#endif //GTKMM_EXAMPLE_MESSAGESLIST_H
```

File: messagetext.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_MESSAGETEXT_H
#define GTKMM_EXAMPLE_MESSAGETEXT_H

#include <gtkmm.h>

class MessageText : public Gtk::ScrolledWindow
{
public:
    MessageText();
    virtual ~MessageText();

    void insert_text();

protected:
    Gtk::TextView m_TextView;
};

#endif //GTKMM_EXAMPLE_MESSAGETEXT_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_VPaned(Gtk::ORIENTATION_VERTICAL)
{
    set_title ("Paned Windows");
    set_border_width(10);
    set_default_size(450, 400);

    /* Add a vpaned widget to our toplevel window */
    add(m_VPaned);

    /* Now add the contents of the two halves of the window */
    m_VPaned.add1(m_MessagesList);
    m_VPaned.add2(m_MessageText);

    show_all_children();
}

ExampleWindow::~~ExampleWindow()
```

```
{  
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"  
#include <gtkmm/application.h>  
  
int main(int argc, char *argv[])  
{  
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");  
  
    ExampleWindow window;  
  
    //Shows the window and returns when it is closed.  
    return app->run(window);  
}
```

**File: messageslist.cc (For use with gtkmm 3)**

```
#include "messageslist.h"  
#include <sstream>  
  
MessagesList::MessagesList()  
{  
    /* Create a new scrolled window, with scrollbars only if needed */  
    set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC);  
  
    add(m_TreeView);  
  
    /* create list store */  
    m_refListStore = Gtk::ListStore::create(m_Columns);  
  
    m_TreeView.set_model(m_refListStore);  
  
    /* Add some messages to the window */  
    for(int i = 0; i < 10; ++i)  
    {  
        std::ostringstream text;  
        text << "message #" << i;  
  
        Gtk::TreeModel::Row row = *(m_refListStore->append());  
        row[m_Columns.m_col_text] = text.str();  
    }  
  
    //Add the Model's column to the View's columns:  
    m_TreeView.append_column("Messages", m_Columns.m_col_text);  
}
```

```
    show_all_children();
}

MessagesList::~MessagesList()
{
}
```

File: messagetext.cc (For use with gtkmm 3)

```
#include "messagetext.h"

MessageText::MessageText()
{
    set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC);

    add(m_TextView);
    insert_text();

    show_all_children();
}

MessageText::~MessageText()
{
}

void MessageText::insert_text()
{
    auto refTextBuffer = m_TextView.get_buffer();

    Gtk::TextBuffer::iterator iter = refTextBuffer->get_iter_at_offset(0);
    refTextBuffer->insert(iter,
        "From: pathfinder@nasa.gov\n"
        "To: mom@nasa.gov\n"
        "Subject: Made it!\n"
        "\n"
        "We just got in this morning. The weather has been\n"
        "great - clear but cold, and there are lots of fun sights.\n"
        "Sojourner says hi. See you soon.\n"
        "-Path\n");
}
```

### 8.1.3 ScrolledWindow

ScrolledWindow widgets create a scrollable area. You can insert any type of widget into a ScrolledWindow window, and it will be accessible regardless of its size by using the scrollbars. Note that ScrolledWindow is not a `Gtk::Window` despite the slightly misleading name.

---

Scrolled windows have *scrollbar policies* which determine whether the `Scrollbar`s will be displayed. The policies can be set with the `set_policy()` method. The policy may be one of `Gtk::POLICY_AUTOMATIC` or `Gtk::POLICY_ALWAYS`. `Gtk::POLICY_AUTOMATIC` will cause the scrolled window to display the scrollbar only if the contained widget is larger than the visible area. `Gtk::POLICY_ALWAYS` will cause the scrollbar to be displayed always.

#### Reference

##### 8.1.3.1 Example

Here is a simple example that packs 100 toggle buttons into a `ScrolledWindow`. Try resizing the window to see the scrollbars react.



Figure 8.3: ScrolledWindow



## Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Dialog
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_dialog_response(int response_id);

    //Child widgets:
    Gtk::ScrolledWindow m_ScrolledWindow;
    Gtk::Grid m_Grid;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: `examplewindow.cc` (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
{
    set_title("Gtk::ScrolledWindow example");
    set_border_width(0);
    set_size_request(300, 300);

    m_ScrolledWindow.set_border_width(10);

    /* the policy is one of Gtk::POLICY_AUTOMATIC, or Gtk::POLICY_ALWAYS.
     * Gtk::POLICY_AUTOMATIC will automatically decide whether you need
     * scrollbars, whereas Gtk::POLICY_ALWAYS will always leave the ↵
     *   scrollbars
     * there. The first one is the horizontal scrollbar, the second,
     * the vertical. */
    m_ScrolledWindow.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_ALWAYS);

    get_content_area()->pack_start(m_ScrolledWindow);
```

```
/* set the spacing to 10 on x and 10 on y */
m_Grid.set_row_spacing(10);
m_Grid.set_column_spacing(10);

/* pack the grid into the scrolled window */
m_ScrolledWindow.add(m_Grid);

/* this simply creates a grid of toggle buttons
 * to demonstrate the scrolled window. */
for(int i = 0; i < 10; i++)
{
    for(int j = 0; j < 10; j++)
    {
        char buffer[32];
        sprintf(buffer, "button (%d,%d)\n", i, j);
        auto pButton = Gtk::make_managed<Gtk::ToggleButton>(buffer);
        m_Grid.attach(*pButton, i, j);
    }
}

/* Add a "close" button to the bottom of the dialog */
add_button("_Close", Gtk::RESPONSE_CLOSE);
signal_response().connect(sigc::mem_fun(*this, &ExampleWindow::↵
    on_dialog_response));

/* This makes it so the button is the default.
 * Simply hitting the "Enter" key will cause this button to activate. */
set_default_response(Gtk::RESPONSE_CLOSE);

show_all_children();
}

ExampleWindow::~~ExampleWindow()
{
}

void ExampleWindow::on_dialog_response(int response_id)
{
    switch (response_id)
    {
        case Gtk::RESPONSE_CLOSE:
        case Gtk::RESPONSE_DELETE_EVENT:
            hide();
            break;
        default:
            std::cout << "Unexpected response_id=" << response_id << std::endl;
```

---

```
        break;
    }
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

### 8.1.4 AspectFrame

The `AspectFrame` widget looks like a `Frame` widget, but it also enforces the *aspect ratio* (the ratio of the width to the height) of the child widget, adding extra space if necessary. For instance, this would allow you to display a photograph without allowing the user to distort it horizontally or vertically while resizing.

#### Reference

#### 8.1.4.1 Example

The following program uses a `Gtk::AspectFrame` to present a drawing area whose aspect ratio will always be 2:1, no matter how the user resizes the top-level window.




Figure 8.4: AspectFrame

### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Child widgets:
    Gtk::AspectFrame m_AspectFrame;
    Gtk::DrawingArea m_DrawingArea;
```

```
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

**File: examplewindow.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_AspectFrame("2x1", /* label */
  Gtk::ALIGN_CENTER, /* center x */
  Gtk::ALIGN_CENTER, /* center y */
  2.0, /* xsize/ysize = 2 */
  false /* ignore child's aspect */)
{
  set_title("Aspect Frame");
  set_border_width(10);

  // Add a child widget to the aspect frame */
  // Ask for a 200x200 window, but the AspectFrame will give us a 200x100
  // window since we are forcing a 2x1 aspect ratio */
  m_DrawingArea.set_size_request(200, 200);
  m_AspectFrame.add(m_DrawingArea);

  // Add the aspect frame to our toplevel window:
  add(m_AspectFrame);

  show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
  auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

  ExampleWindow window;

  //Shows the window and returns when it is closed.
  return app->run(window);
}
```

---

```
}
```

## 8.1.5 Alignment

The `Alignment` widget allows you to place a widget at a position and size relative to the size of the `Alignment` widget itself. For instance, it might be used to center a widget.

The `Alignment` widget is deprecated from gtkmm version 3.14 and should not be used in newly-written code. Use `Gtk::Widget`'s alignment and margin methods instead.

### 8.1.5.1 Example

This example right-aligns a button in a window by using `Gtk::Widget::set_halign()`.



Figure 8.5: Alignment

### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_clicked();
};
```

```
//Child widgets:
Gtk::Button m_Button;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

**File: examplewindow.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_Button("_Close", /* mnemonic= */ true)
{
    set_title("Alignment");
    set_border_width(10);
    set_default_size(200, 50);

    m_Button.set_halign(Gtk::ALIGN_END);
    m_Button.set_valign(Gtk::ALIGN_CENTER);
    add(m_Button);

    m_Button.signal_clicked().connect( sigc::mem_fun(*this,
        &ExampleWindow::on_button_clicked) );

    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_clicked()
{
    hide();
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;
```

```
//Shows the window and returns when it is closed.  
return app->run(window);  
}
```

See the [ProgressBar](#) section for another example that uses `set_halign()`.

## 8.2 Multiple-item widgets

Multiple-item widgets inherit from `Gtk::Container`; just as with `Gtk::Bin`, you use the `add()` and `remove()` methods to add and remove contained widgets. Unlike `Gtk::Bin::remove()`, however, the `remove()` method for `Gtk::Container` takes an argument, specifying which widget to remove.

### 8.2.1 Packing

You've probably noticed that gtkmm windows seem "elastic" - they can usually be stretched in many different ways. This is due to the *widget packing* system.

Many GUI toolkits require you to precisely place widgets in a window, using absolute positioning, often using a visual editor. This leads to several problems:

- The widgets don't rearrange themselves when the window is resized. Some widgets are hidden when the window is made smaller, and lots of useless space appears when the window is made larger.
- It's impossible to predict the amount of space necessary for text after it has been translated to other languages, or displayed in a different font. On Unix it is also impossible to anticipate the effects of every theme and window manager.
- Changing the layout of a window "on the fly", to make some extra widgets appear, for instance, is complex. It requires tedious recalculation of every widget's position.

gtkmm uses the packing system to solve these problems. Rather than specifying the position and size of each widget in the window, you can arrange your widgets in rows, columns, and/or grids. gtkmm can size your window automatically, based on the sizes of the widgets it contains. And the sizes of the widgets are, in turn, determined by the amount of text they contain, or the minimum and maximum sizes that you specify, and/or how you have requested that the available space should be shared between sets of widgets. You can perfect your layout by specifying padding distance and centering values for each of your widgets. gtkmm then uses all this information to resize and reposition everything sensibly and smoothly when the user manipulates the window.

gtkmm arranges widgets hierarchically, using *containers*. A Container widget contains other widgets. Most gtkmm widgets are containers. Windows, Notebook tabs, and Buttons are all container widgets.

---



There are two flavours of containers: single-child containers, which are all descendants of `Gtk::Bin`, and multiple-child containers, which are descendants of `Gtk::Container`. Most widgets in `gtkmm` are descendants of `Gtk::Bin`, including `Gtk::Window`.

Yes, that's correct: a `Window` can contain at most one widget. How, then, can we use a window for anything useful? By placing a multiple-child container in the window. The most useful container widgets are `Gtk::Grid` and `Gtk::Box`.

- `Gtk::Grid` arranges its child widgets in rows and columns. Use `attach()`, `attach_next_to()` and `add()` to insert child widgets.
- `Gtk::Box` arranges its child widgets vertically or horizontally. Use `pack_start()` and `pack_end()` to insert child widgets.

There are several other containers, which we will also discuss.

If you've never used a packing toolkit before, it can take some getting used to. You'll probably find, however, that you don't need to rely on visual form editors quite as much as you might with other toolkits.

## 8.2.2 An improved Hello World

Let's take a look at a slightly improved `helloworld`, showing what we've learnt.



Figure 8.6: Hello World 2

### Source Code

File: `helloworld.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLE_HELLOWORLD_H
#define GTKMM_EXAMPLE_HELLOWORLD_H

#include <gtkmm/box.h>
#include <gtkmm/button.h>
#include <gtkmm/window.h>

class HelloWorld : public Gtk::Window
```

```
{
public:
    HelloWorld();
    virtual ~HelloWorld();

protected:

    // Signal handlers:
    // Our new improved on_button_clicked(). (see below)
    void on_button_clicked(Glib::ustring data);

    // Child widgets:
    Gtk::Box m_box1;
    Gtk::Button m_button1, m_button2;
};

#endif // GTKMM_EXAMPLE_HELLOWORLD_H
```

File: helloworld.cc (For use with gtkmm 3)

```
#include "helloworld.h"
#include <iostream>

HelloWorld::HelloWorld()
: m_button1("Button 1"),
  m_button2("Button 2")
{
    // This just sets the title of our new window.
    set_title("Hello Buttons!");

    // sets the border width of the window.
    set_border_width(10);

    // put the box into the main window.
    add(m_box1);

    // Now when the button is clicked, we call the "on_button_clicked" ↵
    function
    // with a pointer to "button 1" as it's argument
    m_button1.signal_clicked().connect(sigc::bind<Glib::ustring>(
        sigc::mem_fun(*this, &HelloWorld::on_button_clicked), " ↵
        button 1"));

    // instead of gtk_container_add, we pack this button into the invisible
    // box, which has been packed into the window.
    // note that the pack_start default arguments are Gtk::EXPAND | Gtk:: ↵
    FILL, 0
    m_box1.pack_start(m_button1);
```

```
// always remember this step, this tells GTK that our preparation
// for this button is complete, and it can be displayed now.
m_button1.show();

// call the same signal handler with a different argument,
// passing a pointer to "button 2" instead.
m_button2.signal_clicked().connect(sigc::bind<-1, Glib::ustring>(
    sigc::mem_fun(*this, &HelloWorld::on_button_clicked), " ↵
    button 2"));

m_box1.pack_start(m_button2);

// Show the widgets.
// They will not really be shown until this Window is shown.
m_button2.show();
m_box1.show();
}

HelloWorld::~HelloWorld()
{
}

// Our new improved signal handler. The data passed to this method is
// printed to stdout.
void HelloWorld::on_button_clicked(Glib::ustring data)
{
    std::cout << "Hello World - " << data << " was pressed" << std::endl;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "helloworld.h"
#include <gtkmm/application.h>

int main (int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    HelloWorld helloworld;

    //Shows the window and returns when it is closed.
    return app->run(helloworld);
}
```

After building and running this program, try resizing the window to see the behaviour. Also, try playing with the options to `pack_start()` while reading the [Boxes](#) section.

---

### 8.2.3 Boxes

Most packing uses boxes as in the above example. These are invisible containers into which we can pack our widgets. When packing widgets into a horizontal box, the objects are inserted horizontally from left to right or right to left depending on whether `pack_start()` or `pack_end()` is used. In a vertical box, widgets are packed from top to bottom or vice versa. You may use any combination of boxes inside or beside other boxes to create the desired effect.

#### 8.2.3.1 Adding widgets

##### 8.2.3.1.1 Per-child packing options

The `pack_start()` and `pack_end()` methods place widgets inside these containers. The `pack_start()` method will start at the top and work its way down in a Box with vertical orientation, or pack left to right in a Box with horizontal orientation. `pack_end()` will do the opposite, packing from bottom to top or from right to left. Using these methods allows us to right justify or left justify our widgets. We will use `pack_start()` in most of our examples.

There are several options governing how widgets are to be packed, and this can be confusing at first. If you have difficulties then it is sometimes a good idea to play with the glade GUI designer to see what is possible. You might even decide to use the `Gtk::Builder` API to load your GUI at runtime.

There are basically five different styles, as shown in this picture:




Figure 8.7: Box Packing 1

Each line contains one horizontal Box with several buttons. Each of the buttons on a line is packed into the Box with the same arguments to the `pack_start()` method.

This is the declaration of the `pack_start()` method:

```
void pack_start(Gtk::Widget& child,
               Gtk::PackOptions options = Gtk::PACK_EXPAND_WIDGET,
               guint padding = 0);
```

The first argument is the widget you're packing. In our example these are all `Buttons`.

The *options* argument can take one of these three options:

- `Gtk::PACK_SHRINK`: Space is contracted to the child widget size. The widget will take up just-enough space and never expand.
- `Gtk::PACK_EXPAND_PADDING`: Extra space is filled with padding. The widgets will be spaced out evenly, but their sizes won't change - there will be empty space between the widgets instead.
- `Gtk::PACK_EXPAND_WIDGET`: Extra space is taken up by increasing the child widget size, without changing the amount of space between widgets.

The *padding* argument specifies the width of an extra border area to leave around the packed widget.

#### Reference

##### 8.2.3.1.2 Per-container packing options

Here's the constructor for the `Box` widget, and methods that set per-container packing options:

```
Gtk::Box(Gtk::Orientation orientation = Gtk::ORIENTATION_HORIZONTAL, int ←  
         spacing = 0);  
void set_spacing(int spacing);  
void set_homogeneous(bool homogeneous = true);
```

Passing `true` to `set_homogeneous()` will cause all of the contained widgets to be the same size. *spacing* is a (minimum) number of pixels to leave between each widget.

What's the difference between *spacing* (set when the box is created) and *padding* (set when elements are packed)? *Spacing* is added between objects, and *padding* is added on either side of a widget. The following figure should make it clearer:

---




Figure 8.8: Box Packing 2

### 8.2.3.2 Gtk::Application and command-line options

The following example program requires a command-line option. The source code shows two ways of handling command-line options in combination with `Gtk::Application`.

- Handle the options in `main()` and hide them from `Gtk::Application` by setting `argc = 1` in the call to `Gtk::Application::create()`.
- Give all command-line options to `Gtk::Application::create()` and add the flag `Gio::APPLICATION_HANDLES_COMMAND_LINE`. Connect a signal handler to the `command_line` signal, and handle the command-line options in the signal handler.

You must set the optional parameter `after = false` in the call to `signal_command_line().connect()`, because your signal handler must be called before the default signal handler. You must also call `Gio::Application::activate()` in the signal handler, unless you want your application to exit without showing its main window. (`Gio::Application` is a base class of `Gtk::Application`.)

### 8.2.3.3 Example

Here is the source code for the example that produced the screenshots above. When you run this example, provide a number between 1 and 3 as a command-line option, to see different packing options in use.

## Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow(int which);
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_quit_clicked();

    //Child widgets:
    Gtk::Button m_button;
    Gtk::Box m_box1;
    Gtk::Box m_boxQuit;
    Gtk::Button m_buttonQuit;

    Gtk::Label m_Label1, m_Label2;

    Gtk::Separator m_separator1, m_separator2;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: `packbox.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_PACKBOX_H
#define GTKMM_EXAMPLE_PACKBOX_H

#include <gtkmm.h>

class PackBox : public Gtk::Box
{
public:
    PackBox(bool homogeneous, int spacing, Gtk::PackOptions options, int ←
        padding = 0);
    virtual ~PackBox();

protected:
    Gtk::Button m_button1, m_button2, m_button3;
```

```
    Gtk::Button* m_pbutton4;
};

#endif //GTKMM_EXAMPLE_PACKBOX_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include <iostream>
#include "examplewindow.h"
#include "packbox.h"

ExampleWindow::ExampleWindow(int which)
: m_box1(Gtk::ORIENTATION_VERTICAL),
  m_buttonQuit("Quit")
{
    set_title("Gtk::Box example");

    PackBox *pPackBox1, *pPackBox2, *pPackBox3, *pPackBox4, *pPackBox5;

    switch(which)
    {
        case 1:
        {
            m_Label1.set_text("Gtk::Box (Gtk::ORIENTATION_HORIZONTAL); ←
                set_homogeneous(false);");

            // Align the label to the left side.
            m_Label1.set_halign(Gtk::ALIGN_START);
            m_Label1.set_valign(Gtk::ALIGN_START);

            // Pack the label into the vertical box (vbox box1). Remember that
            // widgets added to a vbox will be packed one on top of the other in
            // order.
            m_box1.pack_start(m_Label1, Gtk::PACK_SHRINK);

            // Create a PackBox - homogeneous = false, spacing = 0,
            // options = Gtk::PACK_SHRINK, padding = 0
            pPackBox1 = Gtk::make_managed<PackBox>(false, 0, Gtk::PACK_SHRINK);
            m_box1.pack_start(*pPackBox1, Gtk::PACK_SHRINK);

            // Create a PackBox - homogeneous = false, spacing = 0,
            // options = Gtk::PACK_EXPAND_PADDING, padding = 0
            pPackBox2 = Gtk::make_managed<PackBox>(false, 0, Gtk::←
                PACK_EXPAND_PADDING);
            m_box1.pack_start(*pPackBox2, Gtk::PACK_SHRINK);

            // Create a PackBox - homogeneous = false, spacing = 0,
            // options = Gtk::PACK_EXPAND_WIDGET, padding = 0
```



```
pPackBox3 = Gtk::make_managed<PackBox>(false, 0, Gtk::←
    PACK_EXPAND_WIDGET);
m_box1.pack_start(*pPackBox3, Gtk::PACK_SHRINK);

// pack the separator into the vbox. Remember each of these
// widgets are being packed into a vbox, so they'll be stacked
// vertically.
m_box1.pack_start(m_separator1, Gtk::PACK_SHRINK, 5);

// create another new label, and show it.
m_Label2.set_text("Gtk::Box(Gtk::ORIENTATION_HORIZONTAL); ←
    set_homogeneous(true);");
m_Label2.set_halign(Gtk::ALIGN_START);
m_Label2.set_valign(Gtk::ALIGN_START);
m_box1.pack_start(m_Label2, Gtk::PACK_SHRINK);

// Args are: homogeneous, spacing, options, padding
pPackBox4 = Gtk::make_managed<PackBox>(true, 0, Gtk::←
    PACK_EXPAND_PADDING);
m_box1.pack_start(*pPackBox4, Gtk::PACK_SHRINK);

// Args are: homogeneous, spacing, options, padding
pPackBox5 = Gtk::make_managed<PackBox>(true, 0, Gtk::←
    PACK_EXPAND_WIDGET);
m_box1.pack_start(*pPackBox5, Gtk::PACK_SHRINK);

m_box1.pack_start(m_separator2, Gtk::PACK_SHRINK, 5);

break;
}

case 2:
{

    m_Label1.set_text("Gtk::Box(Gtk::ORIENTATION_HORIZONTAL, 10); ←
        set_homogeneous(false);");
    m_Label1.set_halign(Gtk::ALIGN_START);
    m_Label1.set_valign(Gtk::ALIGN_START);
    m_box1.pack_start(m_Label1, Gtk::PACK_SHRINK);

    pPackBox1 = Gtk::make_managed<PackBox>(false, 10, Gtk::←
        PACK_EXPAND_PADDING);
    m_box1.pack_start(*pPackBox1, Gtk::PACK_SHRINK);

    pPackBox2 = Gtk::make_managed<PackBox>(false, 10, Gtk::←
        PACK_EXPAND_WIDGET);
    m_box1.pack_start(*pPackBox2, Gtk::PACK_SHRINK);
```

---

```
m_box1.pack_start(m_separator1, Gtk::PACK_SHRINK, 5);

m_Label2.set_text("Gtk::Box(Gtk::ORIENTATION_HORIZONTAL); ←
    set_homogeneous(false);");
m_Label2.set_halign(Gtk::ALIGN_START);
m_Label2.set_valign(Gtk::ALIGN_START);
m_box1.pack_start(m_Label2, Gtk::PACK_SHRINK);

pPackBox3 = Gtk::make_managed<PackBox>(false, 0, Gtk::PACK_SHRINK, ←
    10);
m_box1.pack_start(*pPackBox3, Gtk::PACK_SHRINK);

pPackBox4 = Gtk::make_managed<PackBox>(false, 0, Gtk:: ←
    PACK_EXPAND_WIDGET, 10);
m_box1.pack_start(*pPackBox4, Gtk::PACK_SHRINK);

m_box1.pack_start(m_separator2, Gtk::PACK_SHRINK, 5);

break;
}

case 3:
{
    // This demonstrates the ability to use Gtk::Box::pack_end() to
    // right justify widgets. First, we create a new box as before.
    pPackBox1 = Gtk::make_managed<PackBox>(false, 0, Gtk::PACK_SHRINK);

    // create the label that will be put at the end.
    m_Label1.set_text("end");

    // pack it using pack_end(), so it is put on the right side
    // of the PackBox.
    pPackBox1->pack_end(m_Label1, Gtk::PACK_SHRINK);

    m_box1.pack_start(*pPackBox1, Gtk::PACK_SHRINK);

    // this explicitly sets the separator to 500 pixels wide by 5 pixels
    // high. This is so the hbox we created will also be 500 pixels ←
    // wide,
    // and the "end" label will be separated from the other labels in ←
    // the
    // hbox. Otherwise, all the widgets in the hbox would be packed as
    // close together as possible.
    m_separator1.set_size_request(500, 5);

    // pack the separator into the vbox.
```

---

```

        m_box1.pack_start(m_separator1, Gtk::PACK_SHRINK, 5);

        break;
    }

    default:
    {
        std::cerr << "Unexpected command-line option." << std::endl;
        break;
    }
}

// Connect the signal to hide the window:
m_buttonQuit.signal_clicked().connect( sigc::mem_fun(*this,
        &ExampleWindow::on_button_quit_clicked) );

// pack the button into the quitbox.
// The last 2 arguments to Box::pack_start are: options, padding.
m_boxQuit.pack_start(m_buttonQuit, Gtk::PACK_EXPAND_PADDING);
m_box1.pack_start(m_boxQuit, Gtk::PACK_SHRINK);

// pack the vbox (box1) which now contains all our widgets, into the
// main window.
add(m_box1);

show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_quit_clicked()
{
    hide();
}

```

**File: main.cc (For use with gtkmm 3)**

```

#include "examplewindow.h"
#include <gtkmm/application.h>
#include <iostream>
#include <cstdlib>

#define GTK_APPLICATION_RECEIVES_COMMAND_LINE_ARGUMENTS 0

#if GTK_APPLICATION_RECEIVES_COMMAND_LINE_ARGUMENTS
namespace

```

---

```

{
int on_command_line(const Glib::RefPtr<Gio::ApplicationCommandLine>& ↵
    command_line,
                        Glib::RefPtr<Gtk::Application>& app)
{
    int argc = 0;
    char** argv = command_line->get_arguments(argc);

    for (int i = 0; i < argc; ++i)
        std::cout << "argv[" << i << "] = " << argv[i] << std::endl;

    app->activate(); // Without activate() the window won't be shown.
    return EXIT_SUCCESS;
}
} // anonymous namespace
#endif

int main(int argc, char *argv[])
{
    if (argc != 2)
    {
        std::cerr << "Usage: example <num>, where <num> is 1, 2, or 3." << std::↵
            ::endl;
        return EXIT_FAILURE;
    }

#ifdef GTK_APPLICATION_RECEIVES_COMMAND_LINE_ARGUMENTS
    // The command line arguments must be checked before Gtk::Application:: ↵
    run()
    // is called. The Gio::APPLICATION_HANDLES_COMMAND_LINE flag and the
    // on_command_line() signal handler are not necessary. This program is ↵
    simpler
    // without them, and with argc = 1 in the call to Gtk::Application:: ↵
    create().
    // They are included to show a program with Gio:: ↵
    APPLICATION_HANDLES_COMMAND_LINE.
    // Gio::APPLICATION_NON_UNIQUE makes it possible to run several ↵
    instances of
    // this application simultaneously.
    auto app = Gtk::Application::create(argc, argv,
        "org.gtkmm.example", Gio::APPLICATION_HANDLES_COMMAND_LINE | Gio:: ↵
        APPLICATION_NON_UNIQUE);

    // Note after = false.
    // Only one signal handler is invoked. This signal handler must run ↵
    before

```

---

```

// the default signal handler, or else it won't run at all.
app->signal_command_line().connect(sigc::bind(sigc::ptr_fun(& ↵
    on_command_line), app), false);
#else
// Gio::APPLICATION_NON_UNIQUE makes it possible to run several ↵
    instances of
// this application simultaneously.
int argc1 = 1; // Don't give the command line arguments to Gtk:: ↵
    Application.
auto app = Gtk::Application::create(argc1, argv,
    "org.gtkmm.example", Gio::APPLICATION_NON_UNIQUE);
#endif

ExampleWindow window(std::atoi(argv[1]));
return app->run(window); //Shows the window and returns when it is ↵
    closed.
}

```

File: packbox.cc (For use with gtkmm 3)

```

#include "packbox.h"

PackBox::PackBox(bool homogeneous, int spacing, Gtk::PackOptions options,
    int padding)
: Gtk::Box(Gtk::ORIENTATION_HORIZONTAL, spacing),
  m_button1("box.pack_start("),
  m_button2("button,"),
  m_button3((options == Gtk::PACK_SHRINK) ? "Gtk::PACK_SHRINK" :
    ((options == Gtk::PACK_EXPAND_PADDING) ?
      "Gtk::PACK_EXPAND_PADDING" : "Gtk::PACK_EXPAND_WIDGET"))
{
    set_homogeneous(homogeneous);

    pack_start(m_button1, options, padding);
    pack_start(m_button2, options, padding);
    pack_start(m_button3, options, padding);

    m_pbutton4 = new Gtk::Button(Glib::ustring::format(padding) + ");");
    pack_start(*m_pbutton4, options, padding);
}

PackBox::~~PackBox()
{
    delete m_pbutton4;
}

```

### 8.2.4 ButtonBoxes

Button boxes are a convenient way to quickly arrange a group of buttons. Their orientation can be either horizontal or vertical.

`ButtonBoxes` help to make applications appear consistent because they use standard settings, such as inter-button spacing and packing.

Buttons are added to a `ButtonBox` with the `add()` method.

Button boxes support several layout styles. The style can be retrieved and changed using `get_layout()` and `set_layout()`.

[Reference](#)

### 8.2.4.1 Example




Figure 8.9: ButtonBox

## Source Code

File: examplebuttonbox.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_BUTTONBOX_H
#define GTKMM_EXAMPLE_BUTTONBOX_H

#include <gtkmm.h>

class ExampleButtonBox : public Gtk::Frame
{
public:
    ExampleButtonBox(bool horizontal,
                     const Glib::ustring& title,
                     gint spacing,
                     Gtk::ButtonBoxStyle layout);

protected:
    Gtk::Button m_Button_OK, m_Button_Cancel, m_Button_Help;
};

#endif //GTKMM_EXAMPLE_BUTTONBOX_H
```

File: examplewindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_clicked();

    //Child widgets:
    Gtk::Box m_VBox_Main, m_VBox;
    Gtk::Box m_HBox;
    Gtk::Frame m_Frame_Horizontal, m_Frame_Vertical;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```



File: examplebuttonbox.cc (For use with gtkmm 3)

```
#include "examplebuttonbox.h"

ExampleButtonBox::ExampleButtonBox(bool horizontal,
    const Glib::ustring& title,
    gint spacing,
    Gtk::ButtonBoxStyle layout)
: Gtk::Frame(title),
  m_Button_OK("OK"),
  m_Button_Cancel("Cancel"),
  m_Button_Help("Help")
{
    Gtk::ButtonBox* bbox = nullptr;

    if(horizontal)
        bbox = Gtk::make_managed<Gtk::ButtonBox>(Gtk::ORIENTATION_HORIZONTAL);
    else
        bbox = Gtk::make_managed<Gtk::ButtonBox>(Gtk::ORIENTATION_VERTICAL);

    bbox->set_border_width(5);

    add(*bbox);

    /* Set the appearance of the Button Box */
    bbox->set_layout(layout);
    bbox->set_spacing(spacing);

    bbox->add(m_Button_OK);
    bbox->add(m_Button_Cancel);
    bbox->add(m_Button_Help);
}
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include "examplebuttonbox.h"

ExampleWindow::ExampleWindow()
: m_VBox_Main(Gtk::ORIENTATION_VERTICAL),
  m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Frame_Horizontal("Horizontal Button Boxes"),
  m_Frame_Vertical("Vertical Button Boxes")
{
    set_title("Gtk::ButtonBox");
    add(m_VBox_Main);
}
```

```
m_VBox_Main.pack_start(m_Frame_Horizontal, Gtk::PACK_EXPAND_WIDGET, 10);

//The horizontal ButtonBoxes:
m_VBox.set_border_width(10);
m_Frame_Horizontal.add(m_VBox);

m_VBox.pack_start(*Gtk::make_managed<ExampleButtonBox>
    (true, "Spread (spacing 40)", 40, Gtk::BUTTONBOX_SPREAD),
    Gtk::PACK_EXPAND_WIDGET);

m_VBox.pack_start(*Gtk::make_managed<ExampleButtonBox>
    (true, "Edge (spacing 30)", 30, Gtk::BUTTONBOX_EDGE),
    Gtk::PACK_EXPAND_WIDGET, 5);

m_VBox.pack_start(*Gtk::make_managed<ExampleButtonBox>
    (true, "Start (spacing 20)", 20, Gtk::BUTTONBOX_START),
    Gtk::PACK_EXPAND_WIDGET, 5);

m_VBox.pack_start(*Gtk::make_managed<ExampleButtonBox>
    (true, "End (spacing 10)", 10, Gtk::BUTTONBOX_END),
    Gtk::PACK_EXPAND_WIDGET, 5);

//The vertical ButtonBoxes:
m_VBox_Main.pack_start(m_Frame_Vertical, Gtk::PACK_EXPAND_WIDGET, 10);

m_HBox.set_border_width(10);
m_Frame_Vertical.add(m_HBox);

m_HBox.pack_start(*Gtk::make_managed<ExampleButtonBox>
    (false, "Spread (spacing 5)", 5, Gtk::BUTTONBOX_SPREAD),
    Gtk::PACK_EXPAND_WIDGET);

m_HBox.pack_start(*Gtk::make_managed<ExampleButtonBox>
    (false, "Edge (spacing 30)", 30, Gtk::BUTTONBOX_EDGE),
    Gtk::PACK_EXPAND_WIDGET, 5);

m_HBox.pack_start(*Gtk::make_managed<ExampleButtonBox>
    (false, "Start (spacing 20)", 20, Gtk::BUTTONBOX_START),
    Gtk::PACK_EXPAND_WIDGET, 5);

m_HBox.pack_start(*Gtk::make_managed<ExampleButtonBox>
    (false, "End (spacing 10)", 10, Gtk::BUTTONBOX_END),
    Gtk::PACK_EXPAND_WIDGET, 5);

show_all_children();
}
```

```
ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_clicked()
{
    hide();
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## 8.2.5 Grid

A *Grid* dynamically lays out child widgets in rows and columns. The dimensions of the grid do not need to be specified in the constructor.

Child widgets can span multiple rows or columns, using `attach()`, or added next to an existing widget inside the grid with `attach_next_to()`. Individual rows and columns of the grid can be set to have uniform height or width with `set_row_homogeneous()` and `set_column_homogeneous()`.

You can set the *margin* and *expand* properties of the child *Widgets* to control their spacing and their behaviour when the *Grid* is resized.

### Reference

#### 8.2.5.1 Example

This example creates a window with three buttons in a grid. The first two buttons are in the upper row, from left to right. A third button is attached underneath the first button, in a new lower row, spanning two columns.

---



Figure 8.10: Grid

### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

private:
    // Signal handlers:
    void on_button_quit();
    void on_button_numbered(const Glib::ustring& data);

    // Child widgets:
    Gtk::Grid m_grid;
    Gtk::Button m_button_1, m_button_2, m_button_quit;
};

#endif /* GTKMM_EXAMPLEWINDOW_H */
```

File: `examplewindow.cc` (For use with gtkmm 3)

```
#include <iostream>
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_button_1("button 1"),
```

```
m_button_2("button 2"),
m_button_quit("Quit")
{
    set_title("Gtk::Grid");
    set_border_width(12);

    add(m_grid);

    m_grid.add(m_button_1);
    m_grid.add(m_button_2);
    m_grid.attach_next_to(m_button_quit, m_button_1, Gtk::POS_BOTTOM, 2, 1);

    m_button_1.signal_clicked().connect(
        sigc::bind<Glib::ustring>( sigc::mem_fun(*this,
            &ExampleWindow::on_button_numbered), "button 1") );
    m_button_2.signal_clicked().connect(
        sigc::bind<Glib::ustring>( sigc::mem_fun(*this,
            &ExampleWindow::on_button_numbered), "button 2") );

    m_button_quit.signal_clicked().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_button_quit) );

    show_all_children();
}

ExampleWindow::~~ExampleWindow()
{
}

void ExampleWindow::on_button_quit()
{
    hide();
}

void
ExampleWindow::on_button_numbered(const Glib::ustring& data)
{
    std::cout << data << " was pressed" << std::endl;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");
```

```
ExampleWindow window;  
  
// Shows the window and returns when it is closed.  
return app->run(window);  
}
```

### 8.2.6 Table

`Gtk::Table` allows us to place widgets in a grid, similar to `Gtk::Grid`.

`Gtk::Table` is deprecated from gtkmm version 3.4 and should not be used in newly-written code. Use `Gtk::Grid` instead.

### 8.2.7 Notebook

A Notebook has a set of stacked pages, each of which contains widgets. Labelled tabs allow the user to select the pages. Notebooks allow several sets of widgets to be placed in a small space, by only showing one page at a time. For instance, they are often used in preferences dialogs.

Use the `append_page()`, `prepend_page()` and `insert_page()` methods to add tabbed pages to the Notebook, supplying the child widget and the name for the tab.

To discover the currently visible page, use the `get_current_page()` method. This returns the page number, and then calling `get_nth_page()` with that number will give you a pointer to the actual child widget.

To programmatically change the selected page, use the `set_current_page()` method.

[Reference](#)

### 8.2.7.1 Example




Figure 8.11: Notebook

#### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_quit();
    void on_notebook_switch_page(Gtk::Widget* page, guint page_num);
```

```
//Child widgets:
Gtk::Box m_VBox;
Gtk::Notebook m_Notebook;
Gtk::Label m_Label1, m_Label2;

Gtk::ButtonBox m_ButtonBox;
Gtk::Button m_Button_Quit;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include <iostream>
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Label1("Contents of tab 1"),
  m_Label2("Contents of tab 2"),
  m_Button_Quit("Quit")
{
  set_title("Gtk::Notebook example");
  set_border_width(10);
  set_default_size(400, 200);

  add(m_VBox);

  //Add the Notebook, with the button underneath:
  m_Notebook.set_border_width(10);
  m_VBox.pack_start(m_Notebook);
  m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);

  m_ButtonBox.pack_start(m_Button_Quit, Gtk::PACK_SHRINK);
  m_Button_Quit.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_button_quit) );

  //Add the Notebook pages:
  m_Notebook.append_page(m_Label1, "First");
  m_Notebook.append_page(m_Label2, "Second");

  m_Notebook.signal_switch_page().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_notebook_switch_page) );

  show_all_children();
}
```



```
ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_quit()
{
    hide();
}

void ExampleWindow::on_notebook_switch_page(Gtk::Widget* /* page */, guint ←
    page_num)
{
    std::cout << "Switched to tab with index " << page_num << std::endl;

    //You can also use m_Notebook.get_current_page() to get this index.
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

### 8.2.8 Assistant

An Assistant splits a complex operation into steps. Each step is a page, containing a header, a child widget and an action area. The Assistant's action area has navigation buttons which update automatically depending on the type of the page, set with `set_page_type()`.

Use the `append_page()`, `prepend_page` and `insert_page()` methods to add pages to the Assistant, supplying the child widget for each page.

To determine the currently-visible page, use the `get_current_page()` method, and pass the result to `get_nth_page()`, which returns a pointer to the actual widget. To programmatically change the current page, use the `set_current_page()` method.

To set the title of a page, use the `set_page_title()` method. The header and side images of a page can be set with the `set_page_header_image()` and `set_page_side_image()` methods.

---

To add widgets to the action area, use the `add_action_widget()` method. They will be packed alongside the default buttons. Use the `remove_action_widget()` method to remove widgets.

#### Reference

##### 8.2.8.1 Example




Figure 8.12: Assistant

#### Source Code

File: `exampleassistant.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEASSISTANT_H
#define GTKMM_EXAMPLEASSISTANT_H

#include <gtkmm.h>

class ExampleAssistant : public Gtk::Assistant
```

```
{
public:
    ExampleAssistant();
    virtual ~ExampleAssistant();

    void get_result(bool& check_state, Glib::ustring& entry_text);

private:
    // Signal handlers:
    void on_assistant_apply();
    void on_assistant_cancel();
    void on_assistant_close();
    void on_assistant_prepare(Gtk::Widget* widget);
    void on_entry_changed();

    // Member functions:
    void print_status();

    // Child widgets:
    Gtk::Box m_box;
    Gtk::Label m_label1, m_label2;
    Gtk::CheckButton m_check;
    Gtk::Entry m_entry;
};

#endif /* GTKMM_EXAMPLEASSISTANT_H */
```

**File: examplewindow.h (For use with gtkmm 3)**

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include "exampleassistant.h"
#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

private:
    // Signal handlers:
    void on_button_clicked();
    void on_assistant_apply();

    // Child widgets:
    Gtk::Grid m_grid;
```

```
    Gtk::Button m_button;  
    Gtk::Label m_label1, m_label2;  
    Gtk::CheckButton m_check;  
    Gtk::Entry m_entry;  
    ExampleAssistant m_assistant;  
};  
  
#endif /* GTKMM_EXAMPLEWINDOW_H */
```

**File:** exampleassistant.cc (For use with gtkmm 3)

```
#include <iostream>  
#include "exampleassistant.h"  
  
ExampleAssistant::ExampleAssistant()  
: m_box(Gtk::ORIENTATION_HORIZONTAL, 12),  
  m_label1("Type text to allow the assistant to continue:"),  
  m_label2("Confirmation page"),  
  m_check("Optional extra information")  
{  
    set_title("Gtk::Assistant example");  
    set_border_width(12);  
    set_default_size(400, 300);  
  
    m_box.pack_start(m_label1);  
    m_box.pack_start(m_entry);  
  
    append_page(m_box);  
    append_page(m_check);  
    append_page(m_label2);  
  
    set_page_title(*get_nth_page(0), "Page 1");  
    set_page_title(*get_nth_page(1), "Page 2");  
    set_page_title(*get_nth_page(2), "Confirmation");  
  
    set_page_complete(m_check, true);  
    set_page_complete(m_label2, true);  
  
    set_page_type(m_box, Gtk::ASSISTANT_PAGE_INTRO);  
    set_page_type(m_label2, Gtk::ASSISTANT_PAGE_CONFIRM);  
  
    signal_apply().connect(sigc::mem_fun(*this,  
        &ExampleAssistant::on_assistant_apply));  
    signal_cancel().connect(sigc::mem_fun(*this,  
        &ExampleAssistant::on_assistant_cancel));  
    signal_close().connect(sigc::mem_fun(*this,  
        &ExampleAssistant::on_assistant_close));  
    signal_prepare().connect(sigc::mem_fun(*this,
```

```
        &ExampleAssistant::on_assistant_prepare));

    m_entry.signal_changed().connect(sigc::mem_fun(*this,
        &ExampleAssistant::on_entry_changed));

    show_all_children();
}

ExampleAssistant::~ExampleAssistant()
{
}

void ExampleAssistant::get_result(bool& check_state, Glib::ustring& ↵
    entry_text)
{
    check_state = m_check.get_active();
    entry_text = m_entry.get_text();
}

void ExampleAssistant::on_assistant_apply()
{
    std::cout << "Apply was clicked";
    print_status();
}

void ExampleAssistant::on_assistant_cancel()
{
    std::cout << "Cancel was clicked";
    print_status();
    hide();
}

void ExampleAssistant::on_assistant_close()
{
    std::cout << "Assistant was closed";
    print_status();
    hide();
}

void ExampleAssistant::on_assistant_prepare(Gtk::Widget* /* widget */)
{
    set_title(Glib::ustring::compose("Gtk::Assistant example (Page %1 of %2) ↵
        ",
        get_current_page() + 1, get_n_pages()));
}

void ExampleAssistant::on_entry_changed()
```

---

```
{
    // The page is only complete if the entry contains text.
    if(m_entry.get_text_length())
        set_page_complete(m_box, true);
    else
        set_page_complete(m_box, false);
}

void ExampleAssistant::print_status()
{
    std::cout << ", entry contents: \"" << m_entry.get_text()
        << "\", checkbox status: " << m_check.get_active() << std::endl;
}
```

**File:** examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include "exampleassistant.h"

ExampleWindow::ExampleWindow()
: m_button("Show the assistant"),
  m_label1("State of assistant checkbox:", Gtk::ALIGN_START, Gtk::↵
    ALIGN_CENTER),
  m_label2("Contents of assistant entry:", Gtk::ALIGN_START, Gtk::↵
    ALIGN_CENTER)
{
    set_title("Gtk::Assistant example");
    set_border_width(12);

    m_grid.set_row_homogeneous(true);

    m_grid.attach(m_button, 0, 0, 2, 1);
    m_button.set_hexpand(true);
    m_button.set_valign(Gtk::ALIGN_CENTER);

    m_grid.attach(m_label1, 0, 1, 1, 1);

    m_grid.attach(m_label2, 0, 2, 1, 1);

    m_grid.attach(m_check, 1, 1, 1, 1);
    m_check.set_halign(Gtk::ALIGN_START);

    m_grid.attach(m_entry, 1, 2, 1, 1);
    m_entry.set_hexpand(true);

    add(m_grid);

    m_button.signal_clicked().connect(sigc::mem_fun(*this,
```

```
        &ExampleWindow::on_button_clicked));
    m_assistant.signal_apply().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_assistant_apply));

    m_check.set_sensitive(false);
    m_entry.set_sensitive(false);

    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_assistant_apply()
{
    bool check_state;
    Glib::ustring entry_text;

    m_assistant.get_result(check_state, entry_text);
    m_check.set_active(check_state);
    m_entry.set_text(entry_text);
}

void ExampleWindow::on_button_clicked()
{
    m_assistant.show();
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    // Shows the window and returns when it is closed.
    return app->run(window);
}
```

## Chapter 9

# The `TreeView` widget

The `Gtk::TreeView` widget can contain lists or trees of data, in columns.

### 9.1 The Model

Each `Gtk::TreeView` has an associated `Gtk::TreeModel`, which contains the data displayed by the `TreeView`. Each `Gtk::TreeModel` can be used by more than one `Gtk::TreeView`. For instance, this allows the same underlying data to be displayed and edited in 2 different ways at the same time. Or the 2 Views might display different columns from the same Model data, in the same way that 2 SQL queries (or "views") might show different fields from the same database table.

Although you can theoretically implement your own Model, you will normally use either the `ListStore` or `TreeStore` model classes.

#### Reference

#### 9.1.1 `ListStore`, for rows

The `ListStore` contains simple rows of data, and each row has no children.

---






Figure 9.1: TreeView - ListStore

## Reference

### 9.1.2 TreeStore, for a hierarchy

The `TreeStore` contains rows of data, and each row may have child rows.



Figure 9.2: TreeView - TreeStore

## Reference

### 9.1.3 Model Columns

The `TreeModelColumnRecord` class is used to keep track of the columns and their data types. You add `TreeModelColumn` instances to the `ColumnRecord` and then use those `TreeModelColumns` when getting and setting the data in model rows. You will probably find it convenient to derive a new `TreeModelColumnRecord` which has your `TreeModelColumn` instances as member data.

```
class ModelColumns : public Gtk::TreeModelColumnRecord
{
public:

    ModelColumns()
    { add(m_col_text); add(m_col_number); }

    Gtk::TreeModelColumn<Glib::ustring> m_col_text;
    Gtk::TreeModelColumn<int> m_col_number;
};
```

```
ModelColumns m_Columns;
```

You specify the `ColumnRecord` when creating the `Model`, like so:

```
Glib::RefPtr<Gtk::ListStore> refListStore =  
    Gtk::ListStore::create(m_Columns);
```

As a `TreeModelColumnRecord` describes structure, not data, it can be shared among multiple models, and this is preferable for efficiency. However, the instance (such as `m_Columns` here) should usually not be static, because it often needs to be instantiated after `glibmm` has been initialized. The best solution is to make it a lazily instantiated singleton, so that it will be constructed on-demand, whenever the first model accesses it.

### 9.1.4 Adding Rows

Add rows to the model with the `append()`, `prepend()`, or `insert()` methods.

```
Gtk::TreeModel::iterator iter = m_refListStore->append();
```

You can dereference the iterator to get the `Row`:

```
Gtk::TreeModel::Row row = *iter;
```

#### 9.1.4.1 Adding child rows

`Gtk::TreeStore` models can have child items. Add them with the `append()`, `prepend()`, or `insert()` methods, like so:

```
Gtk::TreeModel::iterator iter_child =  
    m_refTreeStore->append(row.children());
```

### 9.1.5 Setting values

You can use the `operator[]` override to set the data for a particular column in the row, specifying the `TreeModelColumn` used to create the model.

```
row[m_Columns.m_col_text] = "sometext";
```

---

### 9.1.6 Getting values

You can use the `operator[]` override to get the data in a particular column in a row, specifying the `TreeModelColumn` used to create the model.

```
Glib::ustring strText = row[m_Columns.m_col_text];  
int number = row[m_Columns.m_col_number];
```

The compiler will complain if you use an inappropriate type. For instance, this would generate a compiler error:

```
//compiler error - no conversion from ustring to int.  
int number = row[m_Columns.m_col_text];
```

### 9.1.7 "Hidden" Columns

You might want to associate extra data with each row. If so, just add it as a `Model` column, but don't add it to the `View`.

## 9.2 The View

The `View` is the actual widget (`Gtk::TreeView`) that displays the model (`Gtk::TreeModel`) data and allows the user to interact with it. The `View` can show all of the model's columns, or just some, and it can show them in various ways.

### Reference

### 9.2.1 Using a Model

You can specify a `Gtk::TreeModel` when constructing the `Gtk::TreeView`, or you can use the `set_model()` method, like so:

```
m_TreeView.set_model(m_refListStore);
```

### 9.2.2 Adding View Columns

You can use the `append_column()` method to tell the `View` that it should display certain `Model` columns, in a certain order, with a certain column title.

```
m_TreeView.append_column("Messages", m_Columns.m_col_text);
```

---

When using this simple `append_column()` override, the `TreeView` will display the model data with an appropriate `CellRenderer`. For instance, strings and numbers are shown in a simple `Gtk::Entry` widget, and booleans are shown in a `Gtk::CheckBox`. This is usually what you need. For other column types you must either connect a callback that converts your type into a string representation, with `TreeViewColumn::set_cell_data_func()`, or derive a custom `CellRenderer`. Note that (unsigned) short is not supported by default - You could use (unsigned) int or (unsigned) long as the column type instead.

### 9.2.3 More than one Model Column per View Column

To render more than one model column in a view column, you need to create the `TreeView::Column` widget manually, and use `pack_start()` to add the model columns to it.

Then use `append_column()` to add the view `Column` to the `View`. Notice that `Gtk::TreeView::append_column()` is overridden to accept either a prebuilt `Gtk::TreeView::Column` widget, or just the `TreeModelColumn` from which it generates an appropriate `Gtk::TreeView::Column` widget.

Here is some example code from `gtkmm/demos/gtk-demo/example_icontheme.cc`, which has a `pixbuf` icon and a text name in the same column:

```
Gtk::TreeView::Column* pColumn =
    Gtk::make_managed<Gtk::TreeView::Column>("Icon Name");

// m_columns.icon and m_columns.iconname are columns in the model.
// pColumn is the column in the TreeView:
pColumn->pack_start(m_columns.icon, /* expand= */ false);
pColumn->pack_start(m_columns.iconname);

m_TreeView.append_column(*pColumn);
```

### 9.2.4 Specifying CellRenderer details

The default `CellRenderers` and their default behaviour will normally suffice, but you might occasionally need finer control. For instance, this example code from `gtkmm/demos/gtk-demo/example_treeview_treestore.cc`, appends a `Gtk::CellRenderer` widget and instructs it to render the data from various model columns through various aspects of its appearance.

```
int cols_count = m_TreeView.append_column_editable("Alex", m_columns.alex) <-
    ;
Gtk::TreeViewColumn* pColumn = m_TreeView.get_column(cols_count-1);
if(pColumn)
{
    Gtk::CellRendererToggle* pRenderer =
        static_cast<Gtk::CellRendererToggle*>(pColumn->get_first_cell());
```

```
pColumn->add_attribute(pRenderer->property_visible(), m_columns.visible) ↔
;
pColumn->add_attribute(pRenderer->property_activatable(), m_columns. ↔
world);
```

You can also connect to `CellRenderer` signals to detect user actions. For instance:

```
Gtk::CellRendererToggle* pRenderer =
    Gtk::make_managed<Gtk::CellRendererToggle>();
pRenderer->signal_toggled().connect(
    sigc::bind( sigc::mem_fun(*this,
        &Example_TreeView_TreeStore::on_cell_toggled), m_columns.dave)
);
```

## 9.2.5 Editable Cells

### 9.2.5.1 Automatically-stored editable cells.

Cells in a `TreeView` can be edited in-place by the user. To allow this, use the `Gtk::TreeView` `insert_column_editable()` and `append_column_editable()` methods instead of `insert_column()` and `append_column()`. When these cells are edited the new values will be stored immediately in the Model. Note that these methods are templates which can only be instantiated for simple column types such as `Glib::ustring`, `int`, and `long`.

### 9.2.5.2 Implementing custom logic for editable cells.

However, you might not want the new values to be stored immediately. For instance, maybe you want to restrict the input to certain characters or ranges of values.

To achieve this, you should use the normal `Gtk::TreeView` `insert_column()` and `append_column()` methods, then use `get_column_cell_renderer()` to get the `Gtk::CellRenderer` used by that column.

You should then cast that `Gtk::CellRenderer*` to the specific `CellRenderer` that you expect, so you can use specific API.

For instance, for a `CellRendererText`, you would set the cell's *editable* property to true, like so:

```
cell.property_editable() = true;
```

For a `CellRendererToggle`, you would set the *activatable* property instead.

You can then connect to the appropriate "edited" signal. For instance, connect to `Gtk::CellRendererText::signal_edited()` or `Gtk::CellRendererToggle::signal_toggled()`. If the column contains more than one

`CellRenderer` then you will need to use `Gtk::TreeView::get_column()` and then call `get_cell_renderers()` on that view `Column`.

In your signal handler, you should examine the new value and then store it in the `Model` if that is appropriate for your application.

## 9.3 Iterating over Model Rows

`Gtk::TreeModel` provides a C++ Standard Library-style container of its children, via the `children()` method. You can use the familiar `begin()` and `end()` methods iterator incrementing, like so:

```
typedef Gtk::TreeModel::Children type_children; //minimise code length.
type_children children = refModel->children();
for(type_children::iterator iter = children.begin();
    iter != children.end(); ++iter)
{
    Gtk::TreeModel::Row row = *iter;
    //Do something with the row - see above for set/get.
}
```

### 9.3.1 Row children

When using a `Gtk::TreeStore`, the rows can have child rows, which can have their own children in turn. Use `Gtk::TreeModel::Row::children()` to get the container of child Rows:

```
Gtk::TreeModel::Children children = row.children();
```

## 9.4 The Selection

To find out what rows the user has selected, get the `Gtk::TreeView::Selection` object from the `TreeView`, like so:

```
Glib::RefPtr<Gtk::TreeSelection> refTreeSelection =
    m_TreeView.get_selection();
```

### 9.4.1 Single or multiple selection

By default, only single rows can be selected, but you can allow multiple selection by setting the mode, like so:

```
refTreeSelection->set_mode(Gtk::SELECTION_MULTIPLE);
```

---

### 9.4.2 The selected rows

For single-selection, you can just call `get_selected()`, like so:

```
TreeModel::iterator iter = refTreeSelection->get_selected();
if(iter) //If anything is selected
{
    TreeModel::Row row = *iter;
    //Do something with the row.
}
```

For multiple-selection, you need to define a callback, and give it to `selected_foreach()`, `selected_foreach_path()` or `selected_foreach_iter()`, like so:

```
refTreeSelection->selected_foreach_iter(
    sigc::mem_fun(*this, &TheClass::selected_row_callback) );

void TheClass::selected_row_callback(
    const Gtk::TreeModel::iterator& iter)
{
    TreeModel::Row row = *iter;
    //Do something with the row.
}
```

### 9.4.3 The "changed" signal

To respond to the user clicking on a row or range of rows, connect to the signal like so:

```
refTreeSelection->signal_changed().connect(
    sigc::mem_fun(*this, &Example_IconTheme::on_selection_changed)
);
```

### 9.4.4 Preventing row selection

Maybe the user should not be able to select every item in your list or tree. For instance, in the `gtk-demo`, you can select a demo to see the source code, but it doesn't make any sense to select a demo category.

To control which rows can be selected, use the `set_select_function()` method, providing a `sigc::slot` callback. For instance:

```
m_refTreeSelection->set_select_function( sigc::mem_fun(*this,
    &DemoWindow::select_function) );
```

and then

---



```
bool DemoWindow::select_function(  
    const Glib::RefPtr<Gtk::TreeModel>& model,  
    const Gtk::TreeModel::Path& path, bool)  
{  
    const Gtk::TreeModel::iterator iter = model->get_iter(path);  
    return iter->children().empty(); // only allow leaf nodes to be selected  
}
```

### 9.4.5 Changing the selection

To change the selection, specify a `Gtk::TreeModel::iterator` or `Gtk::TreeModel::Row`, like so:

```
Gtk::TreeModel::Row row = m_refModel->children()[5]; //The fifth row.  
if(row)  
    refTreeSelection->select(row);
```

or

```
Gtk::TreeModel::iterator iter = m_refModel->children().begin()  
if(iter)  
    refTreeSelection->select(iter);
```

## 9.5 Sorting

The standard tree models (`TreeStore` and `ListStore`) derive from `TreeSortable`, so they offer sorting functionality. For instance, call `set_sort_column()`, to sort the model by the specified column. Or supply a callback function to `set_sort_func()` to implement a more complicated sorting algorithm.

[TreeSortable Reference](#)

### 9.5.1 Sorting by clicking on columns

So that a user can click on a `TreeView`'s column header to sort the `TreeView`'s contents, call `Gtk::TreeView::Column::set_sort_column()`, supplying the model column on which model should be sorted when the header is clicked. For instance:

```
Gtk::TreeView::Column* pColumn = treeview.get_column(0);  
if(pColumn)  
    pColumn->set_sort_column(m_columns.m_col_id);
```

---

### 9.5.2 Independently sorted views of the same model

The `TreeView` already allows you to show the same `TreeModel` in two `TreeView` widgets. If you need one of these `TreeView`s to sort the model differently than the other then you should use a `TreeModelSort` instead of just, for instance, `Gtk::TreeViewModel::set_sort_column()`. `TreeModelSort` is a model that contains another model, presenting a sorted version of that model. For instance, you might add a sorted version of a model to a `TreeView` like so:

```
Glib::RefPtr<Gtk::TreeModelSort> sorted_model =
    Gtk::TreeModelSort::create(model);
sorted_model->set_sort_column(columns.m_col_name, Gtk::SORT_ASCENDING);
treeview.set_model(sorted_model);
```

Note, however, that the `TreeView` will provide iterators to the sorted model. You must convert them to iterators to the underlying child model in order to perform actions on that model. For instance:

```
void ExampleWindow::on_button_delete()
{
    Glib::RefPtr<Gtk::TreeSelection> refTreeSelection =
        m_treeview.get_selection();
    if(refTreeSelection)
    {
        Gtk::TreeModel::iterator sorted_iter =
            m_refTreeSelection->get_selected();
        if(sorted_iter)
        {
            Gtk::TreeModel::iterator iter =
                m_refModelSort->convert_iter_to_child_iter(sorted_iter);
            m_refModel->erase(iter);
        }
    }
}
```

[TreeModelSort Reference](#)

## 9.6 Drag and Drop

`Gtk::TreeView` already implements simple drag-and-drop when used with the `Gtk::ListStore` or `Gtk::TreeStore` models. If necessary, it also allows you to implement more complex behaviour when items are dragged and dropped, using the normal [Drag and Drop API](#).

### 9.6.1 Reorderable rows

If you call `Gtk::TreeView::set_reorderable()` then your `TreeView`'s items can be moved within the `treeview` itself. This is demonstrated in the `TreeStore` example.

---

However, this does not allow you any control of which items can be dragged, and where they can be dropped. If you need that extra control then you might create a derived `Gtk::TreeModel` from `Gtk::TreeStore` or `Gtk::ListStore` and override the `Gtk::TreeDragSource::row_draggable()` and `Gdk::TreeDragDest::row_drop_possible()` virtual methods. You can examine the `Gtk::TreeModel::Pat` provided and allow or disallow dragging or dropping by returning `true` or `false`.

This is demonstrated in the `drag_and_drop` example.

## 9.7 Popup Context Menu

Lots of people need to implement right-click context menus for `TreeView`'s so we will explain how to do that here to save you some time. Apart from one or two points, it's much the same as a normal context menu, as described in the [menus chapter](#).

### 9.7.1 Handling `button_press_event`

To detect a click of the right mouse button, you need to handle the `button_press_event` signal, and check exactly which button was pressed. Because the `TreeView` normally handles this signal completely, you need to either override the default signal handler in a derived `TreeView` class, or use `connect_notify()` instead of `connect()`. You probably also want to call the default handler before doing anything else, so that the right-click will cause the row to be selected first.

This is demonstrated in the `Popup Context Menu` example.

## 9.8 Examples

Some `TreeView` examples are shown here. There are more examples in the [treeview directory](#) in `gtkmm-documentation`'s examples.

If neither `ListStore` nor `TreeStore` is suitable for your application, look at the [custom TreeModel](#) example. It shows how you can make your own implementation of the `TreeModel` interface.

### 9.8.1 ListStore

This example has a `Gtk::TreeView` widget, with a `Gtk::ListStore` model.




Figure 9.3: TreeView - ListStore

### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_quit();

    //Tree model columns:
    class ModelColumns : public Gtk::TreeModel::ColumnRecord
    {
    public:
```

```

ModelColumns()
{ add(m_col_id); add(m_col_name); add(m_col_number); add( ↵
  m_col_percentage); }

Gtk::TreeModelColumn<unsigned int> m_col_id;
Gtk::TreeModelColumn<Glib::ustring> m_col_name;
Gtk::TreeModelColumn<short> m_col_number;
Gtk::TreeModelColumn<int> m_col_percentage;
};

ModelColumns m_Columns;

//Child widgets:
Gtk::Box m_VBox;

Gtk::ScrolledWindow m_ScrolledWindow;
Gtk::TreeView m_TreeView;
Glib::RefPtr<Gtk::ListStore> m_refTreeModel;

Gtk::ButtonBox m_ButtonBox;
Gtk::Button m_Button_Quit;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

**File:** examplewindow.cc (For use with gtkmm 3)

```

#include <iostream>
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_Quit("Quit")
{
  set_title("Gtk::TreeView (ListStore) example");
  set_border_width(5);
  set_default_size(400, 200);

  add(m_VBox);

  //Add the TreeView, inside a ScrolledWindow, with the button underneath:
  m_ScrolledWindow.add(m_TreeView);

  //Only show the scrollbars when they are necessary:
  m_ScrolledWindow.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC ↵
  );
}

```

```
m_VBox.pack_start(m_ScrolledWindow);
m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);

m_ButtonBox.pack_start(m_Button_Quit, Gtk::PACK_SHRINK);
m_ButtonBox.set_border_width(5);
m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);
m_Button_Quit.signal_clicked().connect( sigc::mem_fun(*this,
    &ExampleWindow::on_button_quit) );

//Create the Tree model:
m_refTreeModel = Gtk::ListStore::create(m_Columns);
m_TreeView.set_model(m_refTreeModel);

//Fill the TreeView's model
Gtk::TreeModel::Row row = *(m_refTreeModel->append());
row[m_Columns.m_col_id] = 1;
row[m_Columns.m_col_name] = "Billy Bob";
row[m_Columns.m_col_number] = 10;
row[m_Columns.m_col_percentage] = 15;

row = *(m_refTreeModel->append());
row[m_Columns.m_col_id] = 2;
row[m_Columns.m_col_name] = "Joey Jojo";
row[m_Columns.m_col_number] = 20;
row[m_Columns.m_col_percentage] = 40;

row = *(m_refTreeModel->append());
row[m_Columns.m_col_id] = 3;
row[m_Columns.m_col_name] = "Rob McRoberts";
row[m_Columns.m_col_number] = 30;
row[m_Columns.m_col_percentage] = 70;

//Add the TreeView's view columns:
//This number will be shown with the default numeric formatting.
m_TreeView.append_column("ID", m_Columns.m_col_id);
m_TreeView.append_column("Name", m_Columns.m_col_name);

m_TreeView.append_column_numeric("Formatted number", m_Columns.m_col_number,
    "%010d" /* 10 digits, using leading zeroes. */);

//Display a progress bar instead of a decimal number:
auto cell = Gtk::make_managed<Gtk::CellRendererProgress>();
int cols_count = m_TreeView.append_column("Some percentage", *cell);
auto pColumn = m_TreeView.get_column(cols_count - 1);
if(pColumn)
{
```

```

        pColumn->add_attribute(cell->property_value(), m_Columns. ←
            m_col_percentage);
    }

    //Make all the columns reorderable:
    //This is not necessary, but it's nice to show the feature.
    //You can use TreeView::set_column_drag_function() to more
    //finely control column drag and drop.
    for(guint i = 0; i < 2; i++)
    {
        auto column = m_TreeView.get_column(i);
        column->set_reorderable();
    }

    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_quit()
{
    hide();
}

```

File: main.cc (For use with gtkmm 3)

```

#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}

```

### 9.8.2 TreeStore

This example is very similar to the `ListStore` example, but uses a `Gtk::TreeStore` model instead, and adds children to the rows.




Figure 9.4: TreeView - TreeStore

### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_quit();
    void on_treeview_row_activated(const Gtk::TreeModel::Path& path, Gtk::↵
        TreeViewColumn* column);
};
```



```

//Tree model columns:
class ModelColumns : public Gtk::TreeModel::ColumnRecord
{
public:

    ModelColumns()
    { add(m_col_id); add(m_col_name); }

    Gtk::TreeModelColumn<int> m_col_id;
    Gtk::TreeModelColumn<Glib::ustring> m_col_name;
};

ModelColumns m_Columns;

//Child widgets:
Gtk::Box m_VBox;

Gtk::ScrolledWindow m_ScrolledWindow;
Gtk::TreeView m_TreeView;
Glib::RefPtr<Gtk::TreeStore> m_refTreeModel;

Gtk::ButtonBox m_ButtonBox;
Gtk::Button m_Button_Quit;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

File: examplewindow.cc (For use with gtkmm 3)

```

#include <iostream>
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_Quit("Quit")
{
    set_title("Gtk::TreeView (TreeStore) example");
    set_border_width(5);
    set_default_size(400, 200);

    add(m_VBox);

    //Add the TreeView, inside a ScrolledWindow, with the button underneath:
    m_ScrolledWindow.add(m_TreeView);

    //Only show the scrollbars when they are necessary:
    m_ScrolledWindow.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC ↵
    );
}

```

```
m_VBox.pack_start(m_ScrolledWindow);
m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);

m_ButtonBox.pack_start(m_Button_Quit, Gtk::PACK_SHRINK);
m_ButtonBox.set_border_width(5);
m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);
m_Button_Quit.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_button_quit) );

//Create the Tree model:
m_refTreeModel = Gtk::TreeStore::create(m_Columns);
m_TreeView.set_model(m_refTreeModel);

//All the items to be reordered with drag-and-drop:
m_TreeView.set_reorderable();

//Fill the TreeView's model
Gtk::TreeModel::Row row = *(m_refTreeModel->append());
row[m_Columns.m_col_id] = 1;
row[m_Columns.m_col_name] = "Billy Bob";

Gtk::TreeModel::Row childrow = *(m_refTreeModel->append(row.children())) ←
;
childrow[m_Columns.m_col_id] = 11;
childrow[m_Columns.m_col_name] = "Billy Bob Junior";

childrow = *(m_refTreeModel->append(row.children()));
childrow[m_Columns.m_col_id] = 12;
childrow[m_Columns.m_col_name] = "Sue Bob";

row = *(m_refTreeModel->append());
row[m_Columns.m_col_id] = 2;
row[m_Columns.m_col_name] = "Joey Jojo";

row = *(m_refTreeModel->append());
row[m_Columns.m_col_id] = 3;
row[m_Columns.m_col_name] = "Rob McRoberts";

childrow = *(m_refTreeModel->append(row.children()));
childrow[m_Columns.m_col_id] = 31;
childrow[m_Columns.m_col_name] = "Xavier McRoberts";

//Add the TreeView's view columns:
m_TreeView.append_column("ID", m_Columns.m_col_id);
m_TreeView.append_column("Name", m_Columns.m_col_name);
```

---

```

//Connect signal:
m_TreeView.signal_row_activated().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_treeview_row_activated) );

show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_quit()
{
    hide();
}

void ExampleWindow::on_treeview_row_activated(const Gtk::TreeModel::Path& ←
    path,
    Gtk::TreeViewColumn* /* column */)
{
    Gtk::TreeModel::iterator iter = m_refTreeModel->get_iter(path);
    if(iter)
    {
        Gtk::TreeModel::Row row = *iter;
        std::cout << "Row activated: ID=" << row[m_Columns.m_col_id] << ", ←
            Name="
            << row[m_Columns.m_col_name] << std::endl;
    }
}

```

**File: main.cc (For use with gtkmm 3)**

```

#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}

```

### 9.8.3 Editable Cells

This example is identical to the `ListStore` example, but it uses `TreeView::append_column_editable()` instead of `TreeView::append_column()`.




Figure 9.5: TreeView - Editable Cells

#### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_quit();

    void treeviewcolumn_validated_on_cell_data(Gtk::CellRenderer* renderer, ↵
        const Gtk::TreeModel::iterator& iter);
    void cellrenderer_validated_on_editing_started(Gtk::CellEditable* ↵
        cell_editable, const Glib::ustring& path);
};
```

```

void cellrendered_validated_on_edited(const Glib::ustring& path_string, ↵
    const Glib::ustring& new_text);

//Tree model columns:
class ModelColumns : public Gtk::TreeModel::ColumnRecord
{
public:

    ModelColumns()
    { add(m_col_id); add(m_col_name); add(m_col_foo); add(m_col_number); ↵
      add(m_col_number_validated); }

    Gtk::TreeModelColumn<unsigned int> m_col_id;
    Gtk::TreeModelColumn<Glib::ustring> m_col_name;
    Gtk::TreeModelColumn<bool> m_col_foo;
    Gtk::TreeModelColumn<int> m_col_number;
    Gtk::TreeModelColumn<int> m_col_number_validated;
};

ModelColumns m_Columns;

//Child widgets:
Gtk::Box m_VBox;

Gtk::ScrolledWindow m_ScrolledWindow;
Gtk::TreeView m_TreeView;
Glib::RefPtr<Gtk::ListStore> m_refTreeModel;

Gtk::ButtonBox m_ButtonBox;
Gtk::Button m_Button_Quit;

//For the validated column:
//You could also use a CellRendererSpin or a CellRendererProgress:
Gtk::CellRendererText m_cellrendered_validated;
Gtk::TreeView::Column m_treeviewcolumn_validated;
bool m_validate_retry;
Glib::ustring m_invalid_text_for_retry;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

**File:** examplewindow.cc (For use with gtkmm 3)

```

#include <iostream>
#include <cstdio>
#include <cstdlib>
#include "examplewindow.h"

```

```
using std::sprintf;
using std::strtol;

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_Quit("Quit"),
  m_validate_retry(false)
{
    set_title("Gtk::TreeView Editable Cells example");
    set_border_width(5);
    set_default_size(400, 200);

    add(m_VBox);

    //Add the TreeView, inside a ScrolledWindow, with the button underneath:
    m_ScrolledWindow.add(m_TreeView);

    //Only show the scrollbars when they are necessary:
    m_ScrolledWindow.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC ↔
    );

    m_VBox.pack_start(m_ScrolledWindow);
    m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);

    m_ButtonBox.pack_start(m_Button_Quit, Gtk::PACK_SHRINK);
    m_ButtonBox.set_border_width(5);
    m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);
    m_Button_Quit.signal_clicked().connect( sigc::mem_fun(*this,
        &ExampleWindow::on_button_quit) );

    //Create the Tree model:
    m_refTreeModel = Gtk::ListStore::create(m_Columns);
    m_TreeView.set_model(m_refTreeModel);

    //Fill the TreeView's model
    Gtk::TreeModel::Row row = *(m_refTreeModel->append());
    row[m_Columns.m_col_id] = 1;
    row[m_Columns.m_col_name] = "Billy Bob";
    row[m_Columns.m_col_foo] = true;
    row[m_Columns.m_col_number] = 10;

    row = *(m_refTreeModel->append());
    row[m_Columns.m_col_id] = 2;
    row[m_Columns.m_col_name] = "Joey Jojo";
    row[m_Columns.m_col_foo] = true;
    row[m_Columns.m_col_number] = 20;
```

---

```
row = *(m_refTreeModel->append());

row[m_Columns.m_col_id] = 3;
row[m_Columns.m_col_name] = "Rob McRoberts";
row[m_Columns.m_col_foo] = false;
row[m_Columns.m_col_number] = 30;

//Add the TreeView's view columns:
//We use the *_editable convenience methods for most of these,
//because the default functionality is enough:
m_TreeView.append_column_editable("ID", m_Columns.m_col_id);
m_TreeView.append_column_editable("Name", m_Columns.m_col_name);
m_TreeView.append_column_editable("foo", m_Columns.m_col_foo);
m_TreeView.append_column_numeric_editable("Number", m_Columns.m_col_number,
    "%010d");

//For this column, we create the CellRenderer ourselves, and connect our own
//signal handlers, so that we can validate the data that the user enters, and
//control how it is displayed.
m_treeviewcolumn_validated.set_title("validated (<10)");
m_treeviewcolumn_validated.pack_start(m_cellrenderer_validated);
m_TreeView.append_column(m_treeviewcolumn_validated);

//Tell the view column how to render the model values:
m_treeviewcolumn_validated.set_cell_data_func(m_cellrenderer_validated,
    sigc::mem_fun(*this,
        &ExampleWindow::treeviewcolumn_validated_on_cell_data) );

//Make the CellRenderer editable, and handle its editing signals:
m_cellrenderer_validated.property_editable() = true;

m_cellrenderer_validated.signal_editing_started().connect(
    sigc::mem_fun(*this,
        &ExampleWindow::cellrenderer_validated_on_editing_started) );

m_cellrenderer_validated.signal_edited().connect( sigc::mem_fun(*this,
    &ExampleWindow::cellrenderer_validated_on_edited) );

//If this was a CellRendererSpin then you would have to set the adjustment:
//m_cellrenderer_validated.property_adjustment() = m_spin_adjustment;

show_all_children();
```

---

```
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_quit()
{
    hide();
}

void ExampleWindow::treeviewcolumn_validated_on_cell_data(
    Gtk::CellRenderer* /* renderer */,
    const Gtk::TreeModel::iterator& iter)
{
    //Get the value from the model and show it appropriately in the view:
    if(iter)
    {
        Gtk::TreeModel::Row row = *iter;
        int model_value = row[m_Columns.m_col_number_validated];

        //This is just an example.
        //In this case, it would be easier to use append_column_editable() or
        //append_column_numeric_editable()
        char buffer[32];
        sprintf(buffer, "%d", model_value);

        Glib::ustring view_text = buffer;
        m_cellrenderer_validated.property_text() = view_text;
    }
}

void ExampleWindow::cellrenderer_validated_on_editing_started(
    Gtk::CellEditable* cell_editable, const Glib::ustring& /* path */)
{
    //Start editing with previously-entered (but invalid) text,
    //if we are allowing the user to correct some invalid data.
    if(m_validate_retry)
    {
        //This is the CellEditable inside the CellRenderer.
        auto celleditable_validated = cell_editable;

        //It's usually an Entry, at least for a CellRendererText:
        auto pEntry = dynamic_cast<Gtk::Entry*>(celleditable_validated);
        if(pEntry)
        {
            pEntry->set_text(m_invalid_text_for_retry);
        }
    }
}
```

---



```
        m_validate_retry = false;
        m_invalid_text_for_retry.clear();
    }
}

void ExampleWindow::cellrenderer_validated_on_edited(
    const Glib::ustring& path_string,
    const Glib::ustring& new_text)
{
    Gtk::TreePath path(path_string);

    //Convert the inputted text to an integer, as needed by our model column:
    char* pchEnd = nullptr;
    int new_value = strtol(new_text.c_str(), &pchEnd, 10);

    if(new_value > 10)
    {
        //Prevent entry of numbers higher than 10.

        //Tell the user:
        Gtk::MessageDialog dialog(*this,
            "The number must be less than 10. Please try again.",
            false, Gtk::MESSAGE_ERROR);
        dialog.run();

        //Start editing again, with the bad text, so that the user can correct ←
        it.
        //A real application should probably allow the user to revert to the
        //previous text.

        //Set the text to be used in the start_editing signal handler:
        m_invalid_text_for_retry = new_text;
        m_validate_retry = true;

        //Start editing again:
        m_TreeView.set_cursor(path, m_treeviewcolumn_validated,
            m_cellrenderer_validated, true /* start_editing */);
    }
    else
    {
        //Get the row from the path:
        Gtk::TreeModel::iterator iter = m_refTreeModel->get_iter(path);
        if(iter)
        {
            Gtk::TreeModel::Row row = *iter;
```

---

```
        //Put the new value in the model:
        row[m_Columns.m_col_number_validated] = new_value;
    }
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

### 9.8.4 Drag and Drop

This example is much like the `TreeStore` example, but has 2 extra columns to indicate whether the row can be dragged, and whether it can receive drag-and-dropped rows. It uses a derived `Gtk::TreeStore` which overrides the virtual functions as described in the [TreeView Drag and Drop](#) section.




Figure 9.6: TreeView - Drag And Drop

### Source Code

File: examplewindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>
#include "treemodel_dnd.h"

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_quit();

    //Child widgets:
    Gtk::Box m_VBox;

    Gtk::ScrolledWindow m_ScrolledWindow;
    Gtk::TreeView m_TreeView;
    Glib::RefPtr<TreeModel_Dnd> m_refTreeModel;
};
```

```

    Gtk::ButtonBox m_ButtonBox;
    Gtk::Button m_Button_Quit;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

**File:** treemodel\_dnd.h (For use with gtkmm 3)

```

#ifndef GTKMM_EXAMPLE_TREEMODEL_DND_H
#define GTKMM_EXAMPLE_TREEMODEL_DND_H

#include <gtkmm.h>

class TreeModel_Dnd : public Gtk::TreeStore
{
protected:
    TreeModel_Dnd();

public:

    //Tree model columns:
    class ModelColumns : public Gtk::TreeModel::ColumnRecord
    {
    public:

        ModelColumns()
        { add(m_col_id); add(m_col_name); add(m_col_draggable); add( ←
          m_col_receivesdrags); }

        Gtk::TreeModelColumn<int> m_col_id;
        Gtk::TreeModelColumn<Glib::ustring> m_col_name;
        Gtk::TreeModelColumn<bool> m_col_draggable;
        Gtk::TreeModelColumn<bool> m_col_receivesdrags;
    };

    ModelColumns m_Columns;

    static Glib::RefPtr<TreeModel_Dnd> create();

protected:
    //Overridden virtual functions:
    bool row_draggable_vfunc(const Gtk::TreeModel::Path& path) const ←
        override;
    bool row_drop_possible_vfunc(const Gtk::TreeModel::Path& dest, const Gtk ←
        ::SelectionData& selection_data) const override;
};

```

```
#endif //GTKMM_EXAMPLE_TREEMODEL_DND_H
```

**File: examplewindow.cc (For use with gtkmm 3)**

```
#include <iostream>
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_Quit("_Quit", true)
{
    set_title("Gtk::TreeView (Drag and Drop) example");
    set_border_width(5);
    set_default_size(400, 200);

    add(m_VBox);

    //Add the TreeView, inside a ScrolledWindow, with the button underneath:
    m_ScrolledWindow.add(m_TreeView);

    //Only show the scrollbars when they are necessary:
    m_ScrolledWindow.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC ↵
    );

    m_VBox.pack_start(m_ScrolledWindow);
    m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);

    m_ButtonBox.pack_start(m_Button_Quit, Gtk::PACK_SHRINK);
    m_ButtonBox.set_border_width(5);
    m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);
    m_Button_Quit.signal_clicked().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_button_quit) );

    //Create the Tree model:
    //Use our derived model, which overrides some Gtk::TreeDragDest and
    //Gtk::TreeDragSource virtual functions:
    //The columns are declared in the overridden TreeModel.
    m_refTreeModel = TreeModel_Dnd::create();
    m_TreeView.set_model(m_refTreeModel);

    //Enable Drag-and-Drop of TreeView rows:
    //See also the derived TreeModel's *_vfunc overrides.
    m_TreeView.enable_model_drag_source();
    m_TreeView.enable_model_drag_dest();

    //Fill the TreeView's model
    Gtk::TreeModel::Row row = *(m_refTreeModel->append());
```

---

```

row[m_refTreeModel->m_Columns.m_col_id] = 1;
row[m_refTreeModel->m_Columns.m_col_name] = "Billy Bob";
row[m_refTreeModel->m_Columns.m_col_draggable] = true;
row[m_refTreeModel->m_Columns.m_col_receivesdrags] = true;

Gtk::TreeModel::Row childrow = *(m_refTreeModel->append(row.children())) ←
;
childrow[m_refTreeModel->m_Columns.m_col_id] = 11;
childrow[m_refTreeModel->m_Columns.m_col_name] = "Billy Bob Junior";
childrow[m_refTreeModel->m_Columns.m_col_draggable] = true;
childrow[m_refTreeModel->m_Columns.m_col_receivesdrags] = true;

childrow = *(m_refTreeModel->append(row.children()));
childrow[m_refTreeModel->m_Columns.m_col_id] = 12;
childrow[m_refTreeModel->m_Columns.m_col_name] = "Sue Bob";
childrow[m_refTreeModel->m_Columns.m_col_draggable] = true;
childrow[m_refTreeModel->m_Columns.m_col_receivesdrags] = true;

row = *(m_refTreeModel->append());
row[m_refTreeModel->m_Columns.m_col_id] = 2;
row[m_refTreeModel->m_Columns.m_col_name] = "Joey Jojo";
row[m_refTreeModel->m_Columns.m_col_draggable] = true;
row[m_refTreeModel->m_Columns.m_col_receivesdrags] = true;

row = *(m_refTreeModel->append());
row[m_refTreeModel->m_Columns.m_col_id] = 3;
row[m_refTreeModel->m_Columns.m_col_name] = "Rob McRoberts";
row[m_refTreeModel->m_Columns.m_col_draggable] = true;
row[m_refTreeModel->m_Columns.m_col_receivesdrags] = true;

childrow = *(m_refTreeModel->append(row.children()));
childrow[m_refTreeModel->m_Columns.m_col_id] = 31;
childrow[m_refTreeModel->m_Columns.m_col_name] = "Xavier McRoberts";
childrow[m_refTreeModel->m_Columns.m_col_draggable] = true;
childrow[m_refTreeModel->m_Columns.m_col_receivesdrags] = true;

//Add the TreeView's view columns:
m_TreeView.append_column("ID", m_refTreeModel->m_Columns.m_col_id);
m_TreeView.append_column("Name", m_refTreeModel->m_Columns.m_col_name);
m_TreeView.append_column_editable("Draggable",
    m_refTreeModel->m_Columns.m_col_draggable);
m_TreeView.append_column_editable("Receives Drags",
    m_refTreeModel->m_Columns.m_col_receivesdrags);

show_all_children();
}

```

---

```
ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_quit()
{
    hide();
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

**File: treemodel\_dnd.cc (For use with gtkmm 3)**

```
#include "treemodel_dnd.h"
#include <iostream>

TreeModel_Dnd::TreeModel_Dnd()
{
    //We can't just call Gtk::TreeModel(m_Columns) in the initializer list
    //because m_Columns does not exist when the base class constructor runs.
    //And we can't have a static m_Columns instance, because that would be
    //instantiated before the gtkmm type system.
    //So, we use this method, which should only be used just after creation:
    set_column_types(m_Columns);
}

Glib::RefPtr<TreeModel_Dnd> TreeModel_Dnd::create()
{
    return Glib::RefPtr<TreeModel_Dnd>( new TreeModel_Dnd() );
}

bool
TreeModel_Dnd::row_draggable_vfunc(const Gtk::TreeModel::Path& path) const
{
}
```

---

```

// Make the value of the "draggable" column determine whether this row ↵
// can
// be dragged:

//TODO: Add a const version of get_iter to TreeModel:
auto unconstThis = const_cast<TreeModel_Dnd*>(this);
const_iterator iter = unconstThis->get_iter(path);
//const_iterator iter = get_iter(path);
if(iter)
{
    Row row = *iter;
    bool is_draggable = row[m_Columns.m_col_draggable];
    return is_draggable;
}

return Gtk::TreeStore::row_draggable_vfunc(path);
}

bool
TreeModel_Dnd::row_drop_possible_vfunc(const Gtk::TreeModel::Path& dest,
    const Gtk::SelectionData& selection_data) const
{
    //Make the value of the "receives drags" column determine whether a row ↵
    // can be
    //dragged into it:

    //dest is the path that the row would have after it has been dropped:
    //But in this case we are more interested in the parent row:
    Gtk::TreeModel::Path dest_parent = dest;
    bool dest_is_not_top_level = dest_parent.up();
    if(!dest_is_not_top_level || dest_parent.empty())
    {
        //The user wants to move something to the top-level.
        //Let's always allow that.
    }
    else
    {
        //Get an iterator for the row at this path:
        //We must unconst this. This should not be necessary with a future ↵
        // version
        //of gtkmm.
        //TODO: Add a const version of get_iter to TreeModel:
        auto unconstThis = const_cast<TreeModel_Dnd*>(this);
        const_iterator iter_dest_parent = unconstThis->get_iter(dest_parent);
        //const_iterator iter_dest_parent = get_iter(dest);
        if(iter_dest_parent)
        {

```

---



```
    Row row = *iter_dest_parent;
    bool receives_drag = row[m_Columns.m_col_receivesdrags];
    return receives_drag;
}

//You could also examine the row being dragged (via selection_data)
//if you must look at both rows to see whether a drop should be allowed.
//You could use
//TODO: Add const version of get_from_selection_data(): Glib::RefPtr< ↵
const
//Gtk::TreeModel> refThis = Glib::RefPtr<const Gtk::TreeModel>(this);
//
//auto refThis =
//Glib::RefPtr<Gtk::TreeModel>(const_cast<TreeModel_Dnd*>(this));
//refThis->reference(); //, true /* take_copy */
//Gtk::TreeModel::Path path_dragged_row;
//Gtk::TreeModel::Path::get_from_selection_data(selection_data, refThis,
//path_dragged_row);

return Gtk::TreeStore::row_drop_possible_vfunc(dest, selection_data);
}
```

### 9.8.5 Popup Context Menu

This example is much like the `ListStore` example, but derives a custom `TreeView` in order to override the `button_press_event`, and also to encapsulate the tree model code in our derived class. See the [TreeView Popup Context Menu](#) section.

---




Figure 9.7: TreeView - Popup Context Menu

### Source Code

File: examplewindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>
#include "treeview_withpopup.h"

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_quit();

    //Child widgets:
    Gtk::Box m_VBox;

    Gtk::ScrolledWindow m_ScrolledWindow;
    TreeView_WithPopup m_TreeView;
```

```
    Gtk::ButtonBox m_ButtonBox;  
    Gtk::Button m_Button_Quit;  
};  
  
#endif //GTKMM_EXAMPLEWINDOW_H
```

File: treeview\_withpopup.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_TREEVIEW_WITHPOPUP_H  
#define GTKMM_EXAMPLE_TREEVIEW_WITHPOPUP_H  
  
#include <gtkmm.h>  
  
class TreeView_WithPopup : public Gtk::TreeView  
{  
public:  
    TreeView_WithPopup();  
    virtual ~TreeView_WithPopup();  
  
protected:  
    // Override Signal handler:  
    // Alternatively, use signal_button_press_event().connect_notify()  
    bool on_button_press_event(GdkEventButton* button_event) override;  
  
    //Signal handler for popup menu items:  
    void on_menu_file_popup_generic();  
  
    //Tree model columns:  
    class ModelColumns : public Gtk::TreeModel::ColumnRecord  
    {  
    public:  
  
        ModelColumns()  
        { add(m_col_id); add(m_col_name); }  
  
        Gtk::TreeModelColumn<unsigned int> m_col_id;  
        Gtk::TreeModelColumn<Glib::ustring> m_col_name;  
    };  
  
    ModelColumns m_Columns;  
  
    //The Tree model:  
    Glib::RefPtr<Gtk::ListStore> m_refTreeModel;  
  
    Gtk::Menu m_Menu_Popup;  
};
```

```
#endif //GTKMM_EXAMPLE_TREEVIEW_WITHPOPUP_H
```

File: `examplewindow.cc` (For use with gtkmm 3)

```
#include <iostream>
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_Quit("Quit")
{
    set_title("Gtk::TreeView (ListStore) example");
    set_border_width(5);
    set_default_size(400, 200);

    add(m_VBox);

    //Add the TreeView, inside a ScrolledWindow, with the button underneath:
    m_ScrolledWindow.add(m_TreeView);

    //Only show the scrollbars when they are necessary:
    m_ScrolledWindow.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC ↵
    );

    m_VBox.pack_start(m_ScrolledWindow);
    m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);

    m_ButtonBox.pack_start(m_Button_Quit, Gtk::PACK_SHRINK);
    m_ButtonBox.set_border_width(5);
    m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);
    m_Button_Quit.signal_clicked().connect( sigc::mem_fun(*this,
        &ExampleWindow::on_button_quit) );

    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_quit()
{
    hide();
}
```

File: `main.cc` (For use with gtkmm 3)

---

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

**File:** treeview\_withpopup.cc (For use with gtkmm 3)

```
#include "treeview_withpopup.h"
#include <iostream>

TreeView_WithPopup::TreeView_WithPopup()
{
    //Create the Tree model:
    m_refTreeModel = Gtk::ListStore::create(m_Columns);
    set_model(m_refTreeModel);

    //Fill the TreeView's model
    Gtk::TreeModel::Row row = *(m_refTreeModel->append());
    row[m_Columns.m_col_id] = 1;
    row[m_Columns.m_col_name] = "right-click on this";

    row = *(m_refTreeModel->append());
    row[m_Columns.m_col_id] = 2;
    row[m_Columns.m_col_name] = "or this";

    row = *(m_refTreeModel->append());
    row[m_Columns.m_col_id] = 3;
    row[m_Columns.m_col_name] = "or this, for a popup context menu";

    //Add the TreeView's view columns:
    append_column("ID", m_Columns.m_col_id);
    append_column("Name", m_Columns.m_col_name);

    //Fill popup menu:
    auto item = Gtk::make_managed<Gtk::MenuItem>("_Edit", true);
    item->signal_activate().connect(
        sigc::mem_fun(*this, &TreeView_WithPopup::on_menu_file_popup_generic) ↔
    );
    m_Menu_Popup.append(*item);
}
```

```

item = Gtk::make_managed<Gtk::MenuItem>("_Process", true);
item->signal_activate().connect(
    sigc::mem_fun(*this, &TreeView_WithPopup::on_menu_file_popup_generic) ←
);
m_Menu_Popup.append(*item);

item = Gtk::make_managed<Gtk::MenuItem>("_Remove", true);
item->signal_activate().connect(
    sigc::mem_fun(*this, &TreeView_WithPopup::on_menu_file_popup_generic) ←
);
m_Menu_Popup.append(*item);

m_Menu_Popup.accelerate(*this);
m_Menu_Popup.show_all(); //Show all menu items when the menu pops up
}

TreeView_WithPopup::~TreeView_WithPopup()
{
}

bool TreeView_WithPopup::on_button_press_event(GdkEventButton* ←
    button_event)
{
    bool return_value = false;

    //Call base class, to allow normal handling,
    //such as allowing the row to be selected by the right-click:
    return_value = TreeView::on_button_press_event(button_event);

    //Then do our custom stuff:
    if( (button_event->type == GDK_BUTTON_PRESS) && (button_event->button == ←
        3) )
    {
        m_Menu_Popup.popup_at_pointer((GdkEvent*)button_event);

        // Menu::popup_at_pointer() is new in gtkmm 3.22.
        // If you have an older revision, try this:
        //m_Menu_Popup.popup(button_event->button, button_event->time);
    }

    return return_value;
}

void TreeView_WithPopup::on_menu_file_popup_generic()
{
    std::cout << "A popup menu item was selected." << std::endl;
}

```

---

```
auto refSelection = get_selection();
if(refSelection)
{
    Gtk::TreeModel::iterator iter = refSelection->get_selected();
    if(iter)
    {
        int id = (*iter)[m_Columns.m_col_id];
        std::cout << "    Selected ID=" << id << std::endl;
    }
}
}
```

## Chapter 10

# Combo Boxes

The `ComboBox` widget offers a list (or tree) of choices in a dropdown menu. If appropriate, it can show extra information about each item, such as text, a picture, a checkbox, or a progress bar. The `ComboBox` widget usually restricts the user to the available choices, but it can optionally have an `Entry`, allowing the user to enter arbitrary text if none of the available choices are suitable.

The list is provided via a `TreeModel`, and columns from this model are added to the `ComboBox`'s view with the `ComboBox::pack_start()` method. This provides flexibility and compile-time type-safety, but the `ComboBoxText` class provides a simpler text-based specialization in case that flexibility is not required.

### Reference

## 10.1 The model

The model for a `ComboBox` can be defined and filled exactly as for a `TreeView`. For instance, you might derive a `ComboBox` class with one integer and one text column, like so:

```
ModelColumns()
{ add(m_col_id); add(m_col_name); }

Gtk::TreeModelColumn<int> m_col_id;
Gtk::TreeModelColumn<Glib::ustring> m_col_name;
};

ModelColumns m_columns;
```



After appending rows to this model, you should provide the model to the `ComboBox` with the `set_model()` method. Then use the `pack_start()` or `pack_end()` methods to specify what columns will be displayed in the `ComboBox`. As with the `TreeView` you may either use the default cell renderer by passing the `TreeModelColumn` to the pack methods, or you may instantiate a specific `CellRenderer` and specify a particular mapping with either `add_attribute()` or `set_cell_data_func()`. Note that these methods are in the `CellLayout` base class.

## 10.2 The chosen item

To discover what item, if any, the user has chosen from the `ComboBox`, call `ComboBox::get_active()`. This returns a `TreeModel::iterator` that you can dereference to a `Row` in order to read the values in your columns. For instance, you might read an integer ID value from the model, even though you have chosen only to show the human-readable description in the `ComboBox`. For instance:

```
Gtk::TreeModel::iterator iter = m_Combo.get_active();
if(iter)
{
    Gtk::TreeModel::Row row = *iter;

    //Get the data for the selected row, using our knowledge
    //of the tree model:
    int id = row[m_Columns.m_col_id];
    set_something_id_chosen(id); //Your own function.
}
else
    set_nothing_chosen(); //Your own function.
```

## 10.3 Responding to changes

You might need to react to every change of selection in the `ComboBox`, for instance to update other widgets. To do so, you should handle the `changed` signal. For instance:

```
m_combo.signal_changed().connect( sigc::mem_fun(*this,
    &ExampleWindow::on_combo_changed) );
```

## 10.4 Full Example



Figure 10.1: ComboBox

### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm/window.h>
#include <gtkmm/comboboxtext.h>
#include <gtkmm/liststore.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    void on_cell_data_extra(const Gtk::TreeModel::const_iterator& iter);

    //Signal handlers:
    void on_combo_changed();

    //Tree model columns:
    class ModelColumns : public Gtk::TreeModel::ColumnRecord
    {
    public:

        ModelColumns()
        { add(m_col_id); add(m_col_name); add(m_col_extra); }

        Gtk::TreeModelColumn<int> m_col_id;
        Gtk::TreeModelColumn<Glib::ustring> m_col_name;
        Gtk::TreeModelColumn<Glib::ustring> m_col_extra;
    };
};
```

```
};

ModelColumns m_Columns;

//Child widgets:
Gtk::ComboBox m_Combo;
Gtk::CellRendererText m_cell;
Glib::RefPtr<Gtk::ListStore> m_refTreeModel;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
{
    set_title("ComboBox example");

    //Create the Tree model:
    //m_refTreeModel = Gtk::TreeStore::create(m_Columns);
    m_refTreeModel = Gtk::ListStore::create(m_Columns);
    m_Combo.set_model(m_refTreeModel);

    //Fill the ComboBox's Tree Model:
    Gtk::TreeModel::Row row = *(m_refTreeModel->append());
    row[m_Columns.m_col_id] = 1;
    row[m_Columns.m_col_name] = "Billy Bob";
    row[m_Columns.m_col_extra] = "something";
    m_Combo.set_active(row);
    /*
    Gtk::TreeModel::Row childrow = *(m_refTreeModel->append(row.children())) ←
    ;
    childrow[m_Columns.m_col_id] = 11;
    childrow[m_Columns.m_col_name] = "Billy Bob Junior";

    childrow = *(m_refTreeModel->append(row.children()));
    childrow[m_Columns.m_col_id] = 12;
    childrow[m_Columns.m_col_name] = "Sue Bob";
    */

    row = *(m_refTreeModel->append());
    row[m_Columns.m_col_id] = 2;
    row[m_Columns.m_col_name] = "Joey Jojo";
    row[m_Columns.m_col_extra] = "yadda";
```

```
row = *(m_refTreeModel->append());
row[m_Columns.m_col_id] = 3;
row[m_Columns.m_col_name] = "Rob McRoberts";
row[m_Columns.m_col_extra] = "";

/*
childrow = *(m_refTreeModel->append(row.children()));
childrow[m_Columns.m_col_id] = 31;
childrow[m_Columns.m_col_name] = "Xavier McRoberts";
*/

//Add the model columns to the Combo (which is a kind of view),
//rendering them in the default way:
m_Combo.pack_start(m_Columns.m_col_id);
m_Combo.pack_start(m_Columns.m_col_name);

//An example of adding a cell renderer manually,
//instead of using pack_start(model_column)
//so we have more control:
m_Combo.set_cell_data_func(m_cell,
    sigc::mem_fun(*this, &ExampleWindow::on_cell_data_extra));
m_Combo.pack_start(m_cell);

//Add the ComboBox to the window.
add(m_Combo);

//Connect signal handler:
m_Combo.signal_changed().connect( sigc::mem_fun(*this, &ExampleWindow:: ←
    on_combo_changed) );

    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_cell_data_extra(const Gtk::TreeModel:: ←
    const_iterator& iter)
{
    auto row = *iter;
    const Glib::ustring extra = row[m_Columns.m_col_extra];

    //Some arbitrary logic just to show that this is where you can do such ←
    things:
```

---

```
//Transform the value, deciding how to represent it as text:
if(extra.empty())
    m_cell.property_text() = "(none)";
else
    m_cell.property_text() = "-" + extra + "-";

//Change other cell renderer properties too:
m_cell.property_foreground() = (extra == "yadda" ? "red" : "green");
}

void ExampleWindow::on_combo_changed()
{
    Gtk::TreeModel::iterator iter = m_Combo.get_active();
    if(iter)
    {
        Gtk::TreeModel::Row row = *iter;
        if(row)
        {
            //Get the data for the selected row, using our knowledge of the tree
            //model:
            int id = row[m_Columns.m_col_id];
            Glib::ustring name = row[m_Columns.m_col_name];

            std::cout << " ID=" << id << ", name=" << name << std::endl;
        }
    }
    else
        std::cout << "invalid iter" << std::endl;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## 10.5 Simple Text Example




Figure 10.2: ComboBoxText

### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm/window.h>
#include <gtkmm/comboboxtext.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_combo_changed();

    //Child widgets:
    Gtk::ComboBoxText m_Combo;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: `examplewindow.cc` (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
{
    set_title("ComboBoxText example");
```

```
//Fill the combo:
m_Combo.append("something");
m_Combo.append("something else");
m_Combo.append("something or other");
m_Combo.set_active(1);

add(m_Combo);

//Connect signal handler:
m_Combo.signal_changed().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_combo_changed) );

show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_combo_changed()
{
    Glib::ustring text = m_Combo.get_active_text();
    if(!text.empty())
        std::cout << "Combo changed: " << text << std::endl;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## 10.6 ComboBox with an Entry

A `ComboBox` may contain an `Entry` widget for entering of arbitrary text, by specifying `true` for the constructor's `has_entry` parameter.

### 10.6.1 The text column

So that the `Entry` can interact with the drop-down list of choices, you must specify which of your model columns is the text column, with `set_entry_text_column()`. For instance:

```
m_combo.set_entry_text_column(m_columns.m_col_name);
```

When you select a choice from the drop-down menu, the value from this column will be placed in the `Entry`.

### 10.6.2 The entry

Because the user may enter arbitrary text, an active model row isn't enough to tell us what text the user has entered. Therefore, you should retrieve the `Entry` widget with the `ComboBox::get_entry()` method and call `get_text()` on that.

### 10.6.3 Responding to changes

When the user enters arbitrary text, it may not be enough to connect to the `changed` signal, which is emitted for every typed character. It is not emitted when the user presses the Enter key. Pressing the Enter key or moving the keyboard focus to another widget may signal that the user has finished entering text. To be notified of these events, connect to the `Entry`'s `activate` and `focus_out_event` signals, like so

```
Gtk::Entry* entry = m_Combo.get_entry();
if (entry)
{
    // The Entry shall receive focus-out events.
    entry->add_events(Gdk::FOCUS_CHANGE_MASK);

    // Alternatively you can connect to m_Combo.signal_changed().
    entry->signal_changed().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_entry_changed) );

    entry->signal_activate().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_entry_activate) );
}
```



```
entry->signal_focus_out_event().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_entry_focus_out_event) );
}
```

The changed signals of `ComboBox` and `Entry` are both emitted for every change. It doesn't matter which one you connect to. But only `Entry`'s `focus_out_event` signal is useful here.

X events are described in more detail in the [X Event signals](#) section in the appendix.

### 10.6.4 Full Example




Figure 10.3: `ComboBox` with `Entry`

#### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm/window.h>
#include <gtkmm/combobox.h>
#include <gtkmm/liststore.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_entry_changed();
    void on_entry_activate();
    bool on_entry_focus_out_event(GdkEventFocus* event);

    //Signal connection:
    sigc::connection m_ConnectionFocusOut;

    //Tree model columns:
```

```

class ModelColumns : public Gtk::TreeModel::ColumnRecord
{
public:

    ModelColumns()
    { add(m_col_id); add(m_col_name); }

    Gtk::TreeModelColumn<Glib::ustring> m_col_id; //The data to choose - ↔
        this must be text.
    Gtk::TreeModelColumn<Glib::ustring> m_col_name;
};

ModelColumns m_Columns;

//Child widgets:
Gtk::ComboBox m_Combo;
Glib::RefPtr<Gtk::ListStore> m_refTreeModel;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

File: examplewindow.cc (For use with gtkmm 3)

```

#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: m_Combo(true /* has_entry */)
{
    set_title("ComboBox example");

    //Create the Tree model:
    //m_refTreeModel = Gtk::TreeStore::create(m_Columns);
    m_refTreeModel = Gtk::ListStore::create(m_Columns);
    m_Combo.set_model(m_refTreeModel);

    //Fill the ComboBox's Tree Model:
    Gtk::TreeModel::Row row = *(m_refTreeModel->append());
    row[m_Columns.m_col_id] = "1";
    row[m_Columns.m_col_name] = "Billy Bob";
    /*
    Gtk::TreeModel::Row childrow = *(m_refTreeModel->append(row.children())) ↔
        ;
    childrow[m_Columns.m_col_id] = 11;
    childrow[m_Columns.m_col_name] = "Billy Bob Junior";

    childrow = *(m_refTreeModel->append(row.children()));
    childrow[m_Columns.m_col_id] = 12;

```

```
childrow[m_Columns.m_col_name] = "Sue Bob";
*/

row = *(m_refTreeModel->append());
row[m_Columns.m_col_id] = "2";
row[m_Columns.m_col_name] = "Joey Jojo";

row = *(m_refTreeModel->append());
row[m_Columns.m_col_id] = "3";
row[m_Columns.m_col_name] = "Rob McRoberts";

/*
childrow = *(m_refTreeModel->append(row.children()));
childrow[m_Columns.m_col_id] = 31;
childrow[m_Columns.m_col_name] = "Xavier McRoberts";
*/

//Add the model columns to the Combo (which is a kind of view),
//rendering them in the default way:
//This is automatically rendered when we use set_entry_text_column().
//m_Combo.pack_start(m_Columns.m_col_id);
m_Combo.pack_start(m_Columns.m_col_name);

m_Combo.set_entry_text_column(m_Columns.m_col_id);
m_Combo.set_active(1);

//Add the ComboBox to the window.
add(m_Combo);

//Connect signal handlers:
auto entry = m_Combo.get_entry();
if (entry)
{
    // The Entry shall receive focus-out events.
    entry->add_events(Gdk::FOCUS_CHANGE_MASK);
    // Alternatively you can connect to m_Combo.signal_changed().
    entry->signal_changed().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_entry_changed) );
    entry->signal_activate().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_entry_activate) );
    m_ConnectionFocusOut = entry->signal_focus_out_event().
        connect(sigc::mem_fun(*this, &ExampleWindow::↵
            on_entry_focus_out_event) );
}
else
    std::cout << "No Entry ???< " << std::endl;
```

```
    show_all_children();
}

ExampleWindow::~~ExampleWindow()
{
    // The focus_out signal may be emitted while m_Combo is being destructed ↵
    // The signal handler can generate critical messages, if it's called ↵
    // when
    // m_Combo has been partly destructed.
    m_ConnectionFocusOut.disconnect();
}

void ExampleWindow::on_entry_changed()
{
    auto entry = m_Combo.get_entry();
    if (entry)
    {
        std::cout << "on_entry_changed(): Row=" << m_Combo. ↵
            get_active_row_number()
            << ", ID=" << entry->get_text() << std::endl;
    }
}

void ExampleWindow::on_entry_activate()
{
    auto entry = m_Combo.get_entry();
    if (entry)
    {
        std::cout << "on_entry_activate(): Row=" << m_Combo. ↵
            get_active_row_number()
            << ", ID=" << entry->get_text() << std::endl;
    }
}

bool ExampleWindow::on_entry_focus_out_event(GdkEventFocus* /* event */)
{
    auto entry = m_Combo.get_entry();
    if (entry)
    {
        std::cout << "on_entry_focus_out_event(): Row=" << m_Combo. ↵
            get_active_row_number()
            << ", ID=" << entry->get_text() << std::endl;
        return true;
    }
    return false;
}
```

---

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

### 10.6.5 Simple Text Example




Figure 10.4: ComboBoxText with Entry

#### Source Code

File: examplewindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm/window.h>
#include <gtkmm/comboboxtext.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_combo_changed();
    void on_entry_activate();
    bool on_entry_focus_out_event (GdkEventFocus* event);
}
```

```
//Signal connection:
sigc::connection m_ConnectionFocusOut;

//Child widgets:
Gtk::ComboBoxText m_Combo;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: m_Combo(true /* has_entry */)
{
    set_title("ComboBoxText example");

    //Fill the combo:
    m_Combo.append("something");
    m_Combo.append("something else");
    m_Combo.append("something or other");
    m_Combo.set_active(0);

    add(m_Combo);

    //Connect signal handlers:
    auto entry = m_Combo.get_entry();
    // Alternatively you can connect to entry->signal_changed().
    m_Combo.signal_changed().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_combo_changed) );
    if (entry)
    {
        // The Entry shall receive focus-out events.
        entry->add_events(Gdk::FOCUS_CHANGE_MASK);
        entry->signal_activate().connect(sigc::mem_fun(*this,
            &ExampleWindow::on_entry_activate) );
        m_ConnectionFocusOut = entry->signal_focus_out_event().
            connect(sigc::mem_fun(*this, &ExampleWindow::↵
                on_entry_focus_out_event) );
    }
    else
        std::cout << "No Entry ???" << std::endl;

    m_Combo.property_has_frame() = false;
    show_all_children();
}
```

```

}

ExampleWindow::~ExampleWindow()
{
    // The focus_out signal may be emitted while m_Combo is being destructed ←
    .
    // The signal handler can generate critical messages, if it's called ←
    when
    // m_Combo has been partly destructed.
    m_ConnectionFocusOut.disconnect();
}

void ExampleWindow::on_combo_changed()
{
    std::cout << "on_combo_changed(): Row=" << m_Combo.get_active_row_number() ←
    << ", Text=" << m_Combo.get_active_text() << std::endl;
}

void ExampleWindow::on_entry_activate()
{
    std::cout << "on_entry_activate(): Row=" << m_Combo.get_active_row_number() ←
    << ", Text=" << m_Combo.get_active_text() << std::endl;
}

bool ExampleWindow::on_entry_focus_out_event(GdkEventFocus* /* event */)
{
    std::cout << "on_entry_focus_out_event(): Row=" << m_Combo.get_active_row_number() ←
    << ", Text=" << m_Combo.get_active_text() << std::endl;
    return true;
}

```

**File: main.cc (For use with gtkmm 3)**

```

#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}

```

```
}
```

---



## Chapter 11

# TextView

The `TextView` widget can be used to display and edit large amounts of formatted text. Like the `TreeView`, it has a model/view design. In this case the `TextBuffer` is the model.

### 11.1 The Buffer

`Gtk::TextBuffer` is a model containing the data for the `Gtk::TextView`, like the `Gtk::TreeModel` used by `Gtk::TreeView`. This allows two or more `Gtk::TextViews` to share the same `TextBuffer`, and allows those `TextBuffers` to be displayed slightly differently. Or you could maintain several `Gtk::TextBuffers` and choose to display each one at different times in the same `Gtk::TextView` widget.

The `TextView` creates its own default `TextBuffer`, which you can access via the `get_buffer()` method.

#### Reference

#### 11.1.1 Iterators

#### 11.1.2 Tags and Formatting

##### 11.1.2.1 Tags

To specify that some text in the buffer should have specific formatting, you must define a tag to hold that formatting information, and then apply that tag to the region of text. For instance, to define the tag and its properties:

---

```
Glib::RefPtr<Gtk::TextBuffer::Tag> refTagMatch =  
    Gtk::TextBuffer::Tag::create();  
refTagMatch->property_background() = "orange";
```

You can specify a name for the Tag when using the `create()` method, but it is not necessary.

The Tag class has many other properties.

## Reference

### 11.1.2.2 TagTable

Each `Gtk::TextBuffer` uses a `Gtk::TextBuffer::TagTable`, which contains the Tags for that buffer. 2 or more `TextBuffers` may share the same `TagTable`. When you create Tags you should add them to the `TagTable`. For instance:

```
Glib::RefPtr<Gtk::TextBuffer::TagTable> refTagTable =  
    Gtk::TextBuffer::TagTable::create();  
refTagTable->add(refTagMatch);  
//Hopefully a future version of gtkmm will have a set_tag_table() method,  
//for use after creation of the buffer.  
Glib::RefPtr<Gtk::TextBuffer> refBuffer =  
    Gtk::TextBuffer::create(refTagTable);
```

You can also use `get_tag_table()` to get, and maybe modify, the `TextBuffer`'s default `TagTable` instead of creating one explicitly.

## Reference

### 11.1.2.3 Applying Tags

If you have created a Tag and added it to the `TagTable`, you may apply that tag to part of the `TextBuffer` so that some of the text is displayed with that formatting. You define the start and end of the range of text by specifying `Gtk::TextBuffer::iterators`. For instance:

```
refBuffer->apply_tag(refTagMatch, iterRangeStart, iterRangeStop);
```

Or you could specify the tag when first inserting the text:

```
refBuffer->insert_with_tag(iter, "Some text", refTagMatch);
```

You can apply more than one Tag to the same text, by using `apply_tag()` more than once, or by using `insert_with_tags()`. The Tags might specify different values for the same properties, but you can resolve these conflicts by using `Tag::set_priority()`.

---

### 11.1.3 Marks

`TextBuffer` iterators are generally invalidated when the text changes, but you can use a `Gtk::TextBuffer::Mark` to remember a position in these situations. For instance,

```
Glib::RefPtr<Gtk::TextBuffer::Mark> refMark =  
    refBuffer->create_mark(iter);
```

You can then use the `get_iter()` method later to create an iterator for the `Mark`'s new position.

There are two built-in Marks - `insert` and `selection_bound`, which you can access with `TextBuffer`'s `get_insert()` and `get_selection_bound()` methods.

[Reference](#)

### 11.1.4 The View

As mentioned above, each `TextView` has a `TextBuffer`, and one or more `TextView`s can share the same `TextBuffer`.

Like the `TreeView`, you should probably put your `TextView` inside a `ScrolledWindow` to allow the user to see and move around the whole text area with scrollbars.

[Reference](#)

#### 11.1.4.1 Default formatting

`TextView` has various methods which allow you to change the presentation of the buffer for this particular view. Some of these may be overridden by the `Gtk::TextTags` in the buffer, if they specify the same things. For instance, `set_left_margin()`, `set_right_margin()`, `set_indent()`, etc.

#### 11.1.4.2 Scrolling

`Gtk::TextView` has various `scroll_to_*`() methods. These allow you to ensure that a particular part of the text buffer is visible. For instance, your application's Find feature might use `Gtk::TextView::scroll_to_iter()` to show the found text.

## 11.2 Widgets and ChildAnchors

You can embed widgets, such as `Gtk::Buttons`, in the text. Each such child widget needs a `ChildAnchor`. `ChildAnchors` are associated with iterators. For instance, to create a child anchor at a particular position, use `Gtk::TextBuffer::create_child_anchor()`:

---

```
Glib::RefPtr<Gtk::TextChildAnchor> refAnchor =  
    refBuffer->create_child_anchor(iter);
```

Then, to add a widget at that position, use `Gtk::TextView::add_child_at_anchor()`:

```
m_TextView.add_child_at_anchor(m_Button, refAnchor);
```

#### Reference

## 11.3 Examples

### 11.3.1 Simple Example




Figure 11.1: TextView

#### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:

    void fill_buffers();

    //Signal handlers:
    void on_button_quit();
    void on_button_buffer1();
    void on_button_buffer2();

    //Child widgets:
    Gtk::Box m_VBox;

    Gtk::ScrolledWindow m_ScrolledWindow;
    Gtk::TextView m_TextView;

    Glib::RefPtr<Gtk::TextBuffer> m_refTextBuffer1, m_refTextBuffer2;

    Gtk::ButtonBox m_ButtonBox;
    Gtk::Button m_Button_Quit, m_Button_Buffer1, m_Button_Buffer2;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_Quit("_Quit", true),
  m_Button_Buffer1("Use buffer 1"),
  m_Button_Buffer2("Use buffer 2")
{
    set_title("Gtk::TextView example");
    set_border_width(5);
    set_default_size(400, 200);
```

```
add(m_VBox);

//Add the TreeView, inside a ScrolledWindow, with the button underneath:
m_ScrolledWindow.add(m_TextView);

//Only show the scrollbars when they are necessary:
m_ScrolledWindow.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC ↵
);

m_VBox.pack_start(m_ScrolledWindow);

//Add buttons:
m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);

m_ButtonBox.pack_start(m_Button_Buffer1, Gtk::PACK_SHRINK);
m_ButtonBox.pack_start(m_Button_Buffer2, Gtk::PACK_SHRINK);
m_ButtonBox.pack_start(m_Button_Quit, Gtk::PACK_SHRINK);
m_ButtonBox.set_border_width(5);
m_ButtonBox.set_spacing(5);
m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);

//Connect signals:
m_Button_Quit.signal_clicked().connect(sigc::mem_fun(*this,
&ExampleWindow::on_button_quit) );
m_Button_Buffer1.signal_clicked().connect(sigc::mem_fun(*this,
&ExampleWindow::on_button_buffer1) );
m_Button_Buffer2.signal_clicked().connect(sigc::mem_fun(*this,
&ExampleWindow::on_button_buffer2) );

fill_buffers();
on_button_buffer1();

show_all_children();
}

void ExampleWindow::fill_buffers()
{
    m_refTextBuffer1 = Gtk::TextBuffer::create();
    m_refTextBuffer1->set_text("This is the text from TextBuffer #1.");

    m_refTextBuffer2 = Gtk::TextBuffer::create();
    m_refTextBuffer2->set_text(
        "This is some alternative text, from TextBuffer #2.");
}
```

---

```
ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_quit()
{
    hide();
}

void ExampleWindow::on_button_buffer1()
{
    m_TextView.set_buffer(m_refTextBuffer1);
}

void ExampleWindow::on_button_buffer2()
{
    m_TextView.set_buffer(m_refTextBuffer2);
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## Chapter 12

# Menus and Toolbars

There are specific APIs for menus and toolbars, but you should usually deal with them together, creating `Gio::SimpleActions` that you can refer to in both menus and toolbars. In this way you can handle activation of the action instead of responding to the menu and toolbar items separately. And you can enable or disable both the menu and toolbar item via the action. `Gtk::Builder` can create menus and toolbars.

This involves the use of the `Gio::SimpleActionGroup`, `Gio::SimpleAction` and `Gtk::Builder` classes, all of which should be instantiated via their `create()` methods, which return `RefPtrs`.

`Gtk::ActionGroup`, `Gtk::Action` with its subclasses and `Gtk::UIManager` has been an alternative. These classes are deprecated from gtkmm version 3.22 and should not be used in newly-written code.

### 12.1 Actions

First create the `Gio::SimpleActions` and add them to a `Gio::SimpleActionGroup`, with `Gio::ActionMap::add` (`Gio::ActionMap` is a base class of `Gio::SimpleActionGroup`.) Then add the action group to your window with `Gtk::Widget::insert_action_group()`.

The arguments to `add_action()` specify the action's name, which is used in the menu items and toolbar buttons. You can also specify a signal handler when calling `add_action()`. This signal handler will be called when the action is activated via either a menu item or a toolbar button.

For instance:

```
m_refActionGroup = Gio::SimpleActionGroup::create();  
  
m_refActionGroup->add_action("new", sigc::mem_fun(*this, &ExampleWindow::↵  
    on_action_file_new));
```

---



```
m_refActionGroup->add_action("open", sigc::mem_fun(*this, &ExampleWindow:: ↵
    on_action_file_open));
m_refActionGroup->add_action("quit", sigc::mem_fun(*this, &ExampleWindow:: ↵
    on_action_file_quit));

insert_action_group("example", m_refActionGroup);
```

If you use an `Gtk::ApplicationWindow`, you don't have to create your own action group. `Gio::ActionGroup` and `Gio::ActionMap` are base classes of `Gtk::ApplicationWindow`.

## 12.2 Menubar and Toolbar

Next you should create a `Gtk::Builder`. At this point is also a good idea to tell the application to respond to keyboard shortcuts, by using `Gtk::Application::set_accel_for_action()`.

For instance,

```
Glib::RefPtr<Gtk::Builder> m_refBuilder = Gtk::Builder::create();

app->set_accel_for_action("example.new", "<Primary>n");
app->set_accel_for_action("example.quit", "<Primary>q");
app->set_accel_for_action("example.copy", "<Primary>c");
app->set_accel_for_action("example.paste", "<Primary>v");
```

If your main window is derived from `ApplicationWindow` and you instantiate your menubar with `Gtk::Application::set_menubar()`, then you don't have to call `set_accel_for_action()`. See [Application Menu and Main Menu example](#) for an example.

Then, you can define the actual visible layout of the menus and toolbars, and add the UI layout to the `Builder`. This "ui string" uses an XML format, in which you should mention the names of the actions that you have already created. For instance:

```
const char* ui_info =
    "<interface>"
    "  <menu id='menubar'>"
    "    <submenu>"
    "      <attribute name='label' translatable='yes'>_File</attribute>"
    "      <section>"
    "        <item>"
    "          <attribute name='label' translatable='yes'>_New</attribute>"
    "          <attribute name='action'>example.new</attribute>"
    "          <attribute name='accel'>&lt;Primary&gt;n</attribute>"
    "        </item>"
    "      </section>"
    "    <section>"
    "      <item>"
```

```

"      <attribute name='label' translatable='yes'>_Quit</attribute>"
"      <attribute name='action'>example.quit</attribute>"
"      <attribute name='accel'>&lt;Primary&gt;q</attribute>"
"    </item>"
"  </section>"
" </submenu>"
" <submenu>"
"   <attribute name='label' translatable='yes'>_Edit</attribute>"
"   <item>"
"     <attribute name='label' translatable='yes'>_Copy</attribute>"
"     <attribute name='action'>example.copy</attribute>"
"     <attribute name='accel'>&lt;Primary&gt;c</attribute>"
"   </item>"
"   <item>"
"     <attribute name='label' translatable='yes'>_Paste</attribute>"
"     <attribute name='action'>example.paste</attribute>"
"     <attribute name='accel'>&lt;Primary&gt;v</attribute>"
"   </item>"
" </submenu>"
" </menu>"
"</interface>";

m_refBuilder->add_from_string(ui_info);
m_refBuilder->add_from_resource("/toolbar/toolbar.glade");

```

This is where we specify the names of the menu items as they will be seen by users in the menu. Therefore, this is where you should make strings translatable, by adding `translatable='yes'`.

To instantiate a `Gtk::MenuBar` and `Gtk::Toolbar` which you can actually show, you should use the `Builder::get_object()` and `Builder::get_widget()` methods, and then add the widgets to a container. For instance:

```

Glib::RefPtr<Glib::Object> object = m_refBuilder->get_object("menubar");
Glib::RefPtr<Gio::Menu> gmenu = Glib::RefPtr<Gio::Menu>::cast_dynamic( ←
    object);
Gtk::MenuBar* pMenuBar = Gtk::make_managed<Gtk::MenuBar>(gmenu);
m_Box.pack_start(*pMenuBar, Gtk::PACK_SHRINK);

Gtk::Toolbar* toolbar = nullptr;
m_refBuilder->get_widget("toolbar", toolbar);
m_Box.pack_start(*toolbar, Gtk::PACK_SHRINK);

```

## 12.3 Popup Menus

Menus are normally just added to a window, but they can also be displayed temporarily as the result of a mouse button click. For instance, a context menu might be displayed when the user clicks their right mouse button.

For instance:

```
Glib::ustring ui_info =
    "<interface>"
    "  <menu id='menu-examplepopup'>"
    "    <section>"
    "      <item>"
    "        <attribute name='label' translatable='yes'>Edit</attribute>"
    "        <attribute name='action'>examplepopup.edit</attribute>"
    "      </item>"
    "      <item>"
    "        <attribute name='label' translatable='yes'>Process</attribute>"
    "        <attribute name='action'>examplepopup.process</attribute>"
    "      </item>"
    "      <item>"
    "        <attribute name='label' translatable='yes'>Remove</attribute>"
    "        <attribute name='action'>examplepopup.remove</attribute>"
    "      </item>"
    "    </section>"
    "  </menu>"
    "</interface>";

m_refBuilder->add_from_string(ui_info);

Glib::RefPtr<Glib::Object> object = m_refBuilder->get_object("menu- ↵
    examplepopup");
Glib::RefPtr<Gio::Menu> gmenu = Glib::RefPtr<Gio::Menu>::cast_dynamic( ↵
    object);
m_pMenuPopup = std::make_unique<Gtk::Menu>(gmenu);
```

To show the popup menu, use `Gtk::Menu`'s `popup()` method, providing the button identifier and the time of activation, as provided by the `button_press_event` signal, which you will need to handle anyway. For instance:

```
bool ExampleWindow::on_button_press_event(GdkEventButton* event)
{
    if( (event->type == GDK_BUTTON_PRESS) && (event->button == 3) )
    {
        if(!m_pMenuPopup->get_attach_widget())
            m_pMenuPopup->attach_to_widget(*this);
    }
}
```

```
m_pMenuPopup->popup(event->button, event->time);
return true; //It has been handled.
}
else
    return false;
}
```

## 12.4 Gio::Resource and glib-compile-resources

Applications and libraries often contain binary or textual data that is really part of the application, rather than user data. For instance `Gtk::Builder` .glade files, splashscreen images, `Gio::Menu` markup xml, CSS files, icons, etc. These are often shipped as files in `$datadir/appname`, or manually included as literal strings in the code.

The `Gio::Resource` API and the `glib-compile-resources` program provide a convenient and efficient alternative to this, which has some nice properties. You maintain the files as normal files, so it's easy to edit them, but during the build the files are combined into a binary bundle that is linked into the executable. This means that loading the resource files is efficient (as they are already in memory, shared with other instances) and simple (no need to check for things like I/O errors or locate the files in the filesystem). It also makes it easier to create relocatable applications.

Resource bundles are created by the `glib-compile-resources` program which takes an xml file that describes the bundle, and a set of files that the xml references. These are combined into a binary resource bundle.

### Gio::Resource Reference

An example:

```
<?xml version="1.0" encoding="UTF-8"?>
<gresources>
  <gresource prefix="/toolbar">
    <file preprocess="xml-stripblanks">toolbar.glade</file>
    <file>rain.png</file>
  </gresource>
</gresources>
```

This will create a resource bundle with the files

- /toolbar/toolbar.glade
- /toolbar/rain.png

You can then use `glib-compile-resources` to compile the xml to a binary bundle that you can load with `Gio::Resource::create_from_file()`. However, it's more common to use the `--generate-source` argument to create a C source file to link directly into your application. E.g.

```
$ glib-compile-resources --target=resources.c --generate-source toolbar. ↵  
  gresource.xml
```

Once a `Gio::Resource` has been created and registered all the data in it can be accessed globally in the process by using API calls like `Gio::Resource::open_stream_from_global_resources()` to stream the data or `Gio::Resource::lookup_data_in_global_resources()` to get a direct pointer to the data. You can also use URIs like `resource:///toolbar/rain.png` with `Gio::File` to access the resource data.

Often you don't need a `Gio::Resource` instance, because resource data can be loaded with methods such as `Gdk::Pixbuf::create_from_resource()`, `Gtk::Builder::add_from_resource()` and `Gtk::Image::set_from_resource()`.

## 12.5 Examples

### 12.5.1 Application Menu and Main Menu example

This program contains an application menu, a menubar and a toolbar. Classes are derived from `Gtk::Application` and `Gtk::ApplicationWindow`.




Figure 12.1: App and Main Menu

#### Source Code

File: `exampleapplication.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEAPPLICATION_H  
#define GTKMM_EXAMPLEAPPLICATION_H  
  
#include <gtkmm.h>
```

```
class ExampleApplication : public Gtk::Application
{
protected:
    ExampleApplication();

public:
    static Glib::RefPtr<ExampleApplication> create();

protected:
    //Overrides of default signal handlers:
    void on_startup() override;
    void on_activate() override;

private:
    void create_window();

    void on_window_hide(Gtk::Window* window);
    void on_menu_file_new_generic();
    void on_menu_file_quit();
    void on_menu_help_about();

    Glib::RefPtr<Gtk::Builder> m_refBuilder;
};

#endif /* GTKMM_EXAMPLEAPPLICATION_H */
```

**File: examplewindow.h (For use with gtkmm 3)**

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::ApplicationWindow
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_menu_others();

    void on_menu_choices(const Glib::ustring& parameter);
    void on_menu_choices_other(int parameter);
    void on_menu_toggle();

    //Child widgets:
```

```
Gtk::Box m_Box;

Glib::RefPtr<Gtk::Builder> m_refBuilder;

//Two sets of choices:
Glib::RefPtr<Gio::SimpleAction> m_refChoice;
Glib::RefPtr<Gio::SimpleAction> m_refChoiceOther;

Glib::RefPtr<Gio::SimpleAction> m_refToggle;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: exampleapplication.cc (For use with gtkmm 3)

```
#include "exampleapplication.h"
#include "examplewindow.h"
#include <iostream>

ExampleApplication::ExampleApplication()
: Gtk::Application("org.gtkmm.example.main_menu")
{
    Glib::set_application_name("Main Menu Example");
}

Glib::RefPtr<ExampleApplication> ExampleApplication::create()
{
    return Glib::RefPtr<ExampleApplication>(new ExampleApplication());
}

void ExampleApplication::on_startup()
{
    //Call the base class's implementation:
    Gtk::Application::on_startup();

    //Create actions for menus and toolbars.
    //We can use add_action() because Gtk::Application derives from Gio:: ←
    ActionMap.

    //File|New sub menu:
    add_action("newstandard",
        sigc::mem_fun(*this, &ExampleApplication::on_menu_file_new_generic));

    add_action("newfoo",
        sigc::mem_fun(*this, &ExampleApplication::on_menu_file_new_generic));

    add_action("newgoo",
        sigc::mem_fun(*this, &ExampleApplication::on_menu_file_new_generic));
```

```
//File menu:
add_action("quit", sigc::mem_fun(*this, &ExampleApplication::↵
    on_menu_file_quit));

//Help menu:
add_action("about", sigc::mem_fun(*this, &ExampleApplication::↵
    on_menu_help_about));

m_refBuilder = Gtk::Builder::create();

//Layout the actions in a menubar and an application menu:
Glib::ustring ui_info =
    "<interface>"
    "  <!-- menubar -->"
    "  <menu id='menu-example'>"
    "    <submenu>"
    "      <attribute name='label' translatable='yes'>_File</attribute>"
    "      <section>"
    "        <item>"
    "          <attribute name='label' translatable='yes'>New _Standard</↵
attribute>"
    "          <attribute name='action'>app.newstandard</attribute>"
    "          <attribute name='accel'>&lt;Primary&gt;n</attribute>"
    "        </item>"
    "        <item>"
    "          <attribute name='label' translatable='yes'>New _Foo</↵
attribute>"
    "          <attribute name='action'>app.newfoo</attribute>"
    "        </item>"
    "        <item>"
    "          <attribute name='label' translatable='yes'>New _Goo</↵
attribute>"
    "          <attribute name='action'>app.newgoo</attribute>"
    "        </item>"
    "      </section>"
    "      <section>"
    "        <item>"
    "          <attribute name='label' translatable='yes'>_Quit</attribute↵
>"
    "          <attribute name='action'>app.quit</attribute>"
    "          <attribute name='accel'>&lt;Primary&gt;q</attribute>"
    "        </item>"
    "      </section>"
    "    </submenu>"
    "    <submenu>"
    "      <attribute name='label' translatable='yes'>_Edit</attribute>"
```

---



```

"      <section>"
"      <item>"
"      <attribute name='label' translatable='yes'>_Copy</attribute <↵
">"
"      <attribute name='action'>win.copy</attribute>"
"      <attribute name='accel'>&lt;Primary&gt;c</attribute>"
"      </item>"
"      <item>"
"      <attribute name='label' translatable='yes'>_Paste</ <↵
"attribute>"
"      <attribute name='action'>win.paste</attribute>"
"      <attribute name='accel'>&lt;Primary&gt;v</attribute>"
"      </item>"
"      <item>"
"      <attribute name='label' translatable='yes'>_Something</ <↵
"attribute>"
"      <attribute name='action'>win.something</attribute>"
"      </item>"
"    </section>"
"  </submenu>"
"  <submenu>"
"    <attribute name='label' translatable='yes'>_Choices</attribute <↵
">"
"    <section>"
"    <item>"
"    <attribute name='label' translatable='yes'>Choice _A</ <↵
"attribute>"
"    <attribute name='action'>win.choice</attribute>"
"    <attribute name='target'>a</attribute>"
"    </item>"
"    <item>"
"    <attribute name='label' translatable='yes'>Choice _B</ <↵
"attribute>"
"    <attribute name='action'>win.choice</attribute>"
"    <attribute name='target'>b</attribute>"
"    </item>"
"    </section>"
"  </submenu>"
"  <submenu>"
"    <attribute name='label' translatable='yes'>_Other Choices</ <↵
"attribute>"
"    <section>"
"    <item>"
"    <attribute name='label' translatable='yes'>Choice 1</ <↵
"attribute>"
"    <attribute name='action'>win.choiceother</attribute>"
"    <attribute name='target' type='i'>1</attribute>"

```

---

```

"      </item>"
"      <item>"
"      <attribute name='label' translatable='yes'>Choice 2</ ↵
attribute>"
"      <attribute name='action'>win.choiceother</attribute>"
"      <attribute name='target' type='i'>2</attribute>"
"      </item>"
"    </section>"
"    <section>"
"      <item>"
"      <attribute name='label' translatable='yes'>Some Toggle</ ↵
attribute>"
"      <attribute name='action'>win.sometoggle</attribute>"
"      </item>"
"    </section>"
"  </submenu>"
"  <submenu>"
"    <attribute name='label' translatable='yes'>_Help</attribute>"
"    <section>"
"      <item>"
"      <attribute name='label' translatable='yes'>_About</ ↵
attribute>"
"      <attribute name='action'>win.about</attribute>"
"      </item>"
"    </section>"
"  </submenu>"
"</menu>"
""
" <!-- application menu -->"
" <menu id='appmenu'>"
"   <submenu>"
"     <attribute name='label' translatable='yes'>_File</attribute>"
"     <section>"
"       <item>"
"       <attribute name='label' translatable='yes'>New _Standard</ ↵
attribute>"
"       <attribute name='action'>app.newstandard</attribute>"
"       <attribute name='accel'>&lt;Primary&gt;n</attribute>"
"       </item>"
"       <item>"
"       <attribute name='label' translatable='yes'>New _Foo</ ↵
attribute>"
"       <attribute name='action'>app.newfoo</attribute>"
"       </item>"
"       <item>"
"       <attribute name='label' translatable='yes'>New _Goo</ ↵
attribute>"

```

---

```

"      <attribute name='action'>app.newgoo</attribute>"
"    </item>"
"  </section>"
"  <section>"
"    <item>"
"      <attribute name='label' translatable='yes'>_Quit</attribute <
"    >"
"      <attribute name='action'>app.quit</attribute>"
"      <attribute name='accel'>&lt;Primary&gt;q</attribute>"
"    </item>"
"  </section>"
" </submenu>"
" <submenu>"
"   <attribute name='label' translatable='yes'>_Help</attribute>"
"   <section>"
"     <item>"
"       <attribute name='label' translatable='yes'>_About</ <
"     attribute>"
"       <attribute name='action'>app.about</attribute>"
"     </item>"
"   </section>"
" </submenu>"
" </menu>"
"</interface>";

try
{
  m_refBuilder->add_from_string(ui_info);
}
catch (const Glib::Error& ex)
{
  std::cerr << "Building menus failed: " << ex.what();
}

//Get the menubar and the app menu, and add them to the application:
auto object = m_refBuilder->get_object("menu-example");
auto gmenu = Glib::RefPtr<Gio::Menu>::cast_dynamic(object);
object = m_refBuilder->get_object("appmenu");
auto appMenu = Glib::RefPtr<Gio::Menu>::cast_dynamic(object);
if (!(gmenu && appMenu)) {
  g_warning("GMenu or AppMenu not found");
}
else
{
  set_app_menu(appMenu);
  set_menubar(gmenu);
}

```

---

```
}

void ExampleApplication::on_activate()
{
    //std::cout << "debug1: " << G_STRFUNC << std::endl;
    // The application has been started, so let's show a window.
    // A real application might want to reuse this window in on_open(),
    // when asked to open a file, if no changes have been made yet.
    create_window();
}

void ExampleApplication::create_window()
{
    auto win = new ExampleWindow();

    //Make sure that the application runs for as long this window is still ←
    open:
    add_window(*win);

    //Delete the window when it is hidden.
    //That's enough for this simple example.
    win->signal_hide().connect(sigc::bind<Gtk::Window*>(
        sigc::mem_fun(*this, &ExampleApplication::on_window_hide), win));

    win->show_all();
}

void ExampleApplication::on_window_hide(Gtk::Window* window)
{
    delete window;
}

void ExampleApplication::on_menu_file_new_generic()
{
    std::cout << "A File|New menu item was selected." << std::endl;
}

void ExampleApplication::on_menu_file_quit()
{
    std::cout << G_STRFUNC << std::endl;
    quit(); // Not really necessary, when Gtk::Widget::hide() is called.

    // Gio::Application::quit() will make Gio::Application::run() return,
    // but it's a crude way of ending the program. The window is not removed
    // from the application. Neither the window's nor the application's
    // destructors will be called, because there will be remaining reference
    // counts in both of them. If we want the destructors to be called, we
```

---

```

// must remove the window from the application. One way of doing this
// is to hide the window.
std::vector<Gtk::Window*> windows = get_windows();
if (windows.size() > 0)
    windows[0]->hide(); // In this simple case, we know there is only one ↵
    window.
}

void ExampleApplication::on_menu_help_about()
{
    std::cout << "App|Help|About was selected." << std::endl;
}

```

File: examplewindow.cc (For use with gtkmm 3)

```

#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: Gtk::ApplicationWindow(),
  m_Box(Gtk::ORIENTATION_VERTICAL)
{
    set_title("Main menu example");
    set_default_size(300, 100);

    // ExampleApplication displays the menubar. Other stuff, such as a ↵
    toolbar,
    // is put into the box.
    add(m_Box);

    // Create actions for menus and toolbars.
    // We can use add_action() because Gtk::ApplicationWindow derives from ↵
    Gio::ActionMap.
    // This Action Map uses a "win." prefix for the actions.
    // Therefore, for instance, "win.copy", is used in ExampleApplication:: ↵
    on_startup()
    // to layout the menu.

    //Edit menu:
    add_action("copy", sigc::mem_fun(*this, &ExampleWindow::on_menu_others)) ↵
    ;
    add_action("paste", sigc::mem_fun(*this, &ExampleWindow::on_menu_others) ↵
    );
    add_action("something", sigc::mem_fun(*this, &ExampleWindow:: ↵
    on_menu_others));

    //Choices menus, to demonstrate Radio items,
    //using our convenience methods for string and int radio values:

```

```

m_refChoice = add_action_radio_string("choice",
    sigc::mem_fun(*this, &ExampleWindow::on_menu_choices), "a");

m_refChoiceOther = add_action_radio_integer("choicether",
    sigc::mem_fun(*this, &ExampleWindow::on_menu_choices_other), 1);

m_refToggle = add_action_bool("sometoggle",
    sigc::mem_fun(*this, &ExampleWindow::on_menu_toggle), false);

//Help menu:
add_action("about", sigc::mem_fun(*this, &ExampleWindow::on_menu_others) ←
    );

//Create the toolbar and add it to a container widget:

m_refBuilder = Gtk::Builder::create();

Glib::ustring ui_info =
    "<!-- Generated with glade 3.18.3 -->"
    "<interface>"
    "  <requires lib='gtk+' version='3.4' />"
    "  <object class='GtkToolbar' id='toolbar'>"
    "    <property name='visible'>True</property>"
    "    <property name='can_focus'>False</property>"
    "    <child>"
    "      <object class='GtkToolButton' id='toolbutton_new'>"
    "        <property name='visible'>True</property>"
    "        <property name='can_focus'>False</property>"
    "        <property name='tooltip_text' translatable='yes'>New Standard ←
    </property>"
    "        <property name='action_name'>app.newstandard</property>"
    "        <property name='icon_name'>document-new</property>"
    "      </object>"
    "      <packing>"
    "        <property name='expand'>False</property>"
    "        <property name='homogeneous'>True</property>"
    "      </packing>"
    "    </child>"
    "    <child>"
    "      <object class='GtkToolButton' id='toolbutton_quit'>"
    "        <property name='visible'>True</property>"
    "        <property name='can_focus'>False</property>"
    "        <property name='tooltip_text' translatable='yes'>Quit</ ←
    property>"
    "        <property name='action_name'>app.quit</property>"
    "        <property name='icon_name'>application-exit</property>"
    "      </object>"

```

---

```
"      <packing>"
"      <property name='expand'>False</property>"
"      <property name='homogeneous'>True</property>"
"    </packing>"
"  </child>"
" </object>"
"</interface>";

try
{
  m_refBuilder->add_from_string(ui_info);
}
catch (const Glib::Error& ex)
{
  std::cerr << "Building toolbar failed: " << ex.what();
}

Gtk::Toolbar* toolbar = nullptr;
m_refBuilder->get_widget("toolbar", toolbar);
if (!toolbar)
  g_warning("GtkToolbar not found");
else
  m_Box.pack_start(*toolbar, Gtk::PACK_SHRINK);
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_menu_others()
{
  std::cout << "A menu item was selected." << std::endl;
}

void ExampleWindow::on_menu_choices(const Glib::ustring& parameter)
{
  //The radio action's state does not change automatically:
  m_refChoice->change_state(parameter);

  Glib::ustring message;
  if (parameter == "a")
    message = "Choice a was selected.";
  else
    message = "Choice b was selected.";

  std::cout << message << std::endl;
}
```

---

```
void ExampleWindow::on_menu_choices_other(int parameter)
{
    //The radio action's state does not change automatically:
    m_refChoiceOther->change_state(parameter);

    Glib::ustring message;
    if (parameter == 1)
        message = "Choice 1 was selected.";
    else
        message = "Choice 2 was selected.";

    std::cout << message << std::endl;
}

void ExampleWindow::on_menu_toggle()
{
    bool active = false;
    m_refToggle->get_state(active);

    //The toggle action's state does not change automatically:
    active = !active;
    m_refToggle->change_state(active);

    Glib::ustring message;
    if (active)
        message = "Toggle is active.";
    else
        message = "Toggle is not active.";

    std::cout << message << std::endl;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "exampleapplication.h"

int main(int argc, char* argv[])
{
    auto application = ExampleApplication::create();

    // Start the application, showing the initial window,
    // and opening extra windows for any files that it is asked to open,
    // for instance as a command-line parameter.
    // run() will return when the last window has been closed by the user.
    const int status = application->run(argc, argv);
    return status;
}
```



```
}
```

### 12.5.2 Main Menu example

This program contains a menubar and a toolbar. A class is derived from `Gtk::Window`.




Figure 12.2: Main Menu

#### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow(const Glib::RefPtr<Gtk::Application>& app);
    virtual ~ExampleWindow();
};
```

```
private:
    //Signal handlers:
    void on_action_file_new();
    void on_action_file_quit();
    void on_action_others();
    void on_action_toggle();

    //Child widgets:
    Gtk::Box m_Box;

    Glib::RefPtr<Gtk::Builder> m_refBuilder;
    Glib::RefPtr<Gio::SimpleActionGroup> m_refActionGroup;
    Glib::RefPtr<Gio::SimpleAction> m_refActionRain;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm.h>
#include <iostream>

ExampleWindow::ExampleWindow(const Glib::RefPtr<Gtk::Application>& app)
: m_Box(Gtk::ORIENTATION_VERTICAL)
{
    set_title("main_menu example");
    set_default_size(200, 200);

    add(m_Box); //We can put a MenuBar at the top of the box and other stuff ←
                below it.

    //Define the actions:
    m_refActionGroup = Gio::SimpleActionGroup::create();

    m_refActionGroup->add_action("new",
        sigc::mem_fun(*this, &ExampleWindow::on_action_file_new) );
    m_refActionGroup->add_action("open",
        sigc::mem_fun(*this, &ExampleWindow::on_action_others) );

    m_refActionRain = m_refActionGroup->add_action_bool("rain",
        sigc::mem_fun(*this, &ExampleWindow::on_action_toggle),
        false);

    m_refActionGroup->add_action("quit",
        sigc::mem_fun(*this, &ExampleWindow::on_action_file_quit) );
```

```

m_refActionGroup->add_action("cut",
    sigc::mem_fun(*this, &ExampleWindow::on_action_others) );
m_refActionGroup->add_action("copy",
    sigc::mem_fun(*this, &ExampleWindow::on_action_others) );
m_refActionGroup->add_action("paste",
    sigc::mem_fun(*this, &ExampleWindow::on_action_others) );

insert_action_group("example", m_refActionGroup);

//Define how the actions are presented in the menus and toolbars:
m_refBuilder = Gtk::Builder::create();

//Layout the actions in a menubar and toolbar:
const char* ui_info =
    "<interface>"
    "  <menu id='menubar'>"
    "    <submenu>"
    "      <attribute name='label' translatable='yes'>_File</attribute>"
    "      <section>"
    "        <item>"
    "          <attribute name='label' translatable='yes'>_New</attribute <↵
    >"
    "          <attribute name='action'>example.new</attribute>"
    "          <attribute name='accel'>&lt;Primary&gt;n</attribute>"
    "        </item>"
    "        <item>"
    "          <attribute name='label' translatable='yes'>_Open</attribute <↵
    >"
    "          <attribute name='action'>example.open</attribute>"
    "          <attribute name='accel'>&lt;Primary&gt;o</attribute>"
    "        </item>"
    "      </section>"
    "      <section>"
    "        <item>"
    "          <attribute name='label' translatable='yes'>Rain</attribute <↵
    >"
    "          <attribute name='action'>example.rain</attribute>"
    "        </item>"
    "      </section>"
    "      <section>"
    "        <item>"
    "          <attribute name='label' translatable='yes'>_Quit</attribute <↵
    >"
    "          <attribute name='action'>example.quit</attribute>"
    "          <attribute name='accel'>&lt;Primary&gt;q</attribute>"
    "        </item>"
    "      </section>"

```

---

```

"    </submenu>"
"    <submenu>"
"        <attribute name='label' translatable='yes'>_Edit</attribute>"
"        <item>"
"            <attribute name='label' translatable='yes'>_Cut</attribute>"
"            <attribute name='action'>example.cut</attribute>"
"            <attribute name='accel'>&lt;Primary&gt;x</attribute>"
"        </item>"
"        <item>"
"            <attribute name='label' translatable='yes'>_Copy</attribute>"
"            <attribute name='action'>example.copy</attribute>"
"            <attribute name='accel'>&lt;Primary&gt;c</attribute>"
"        </item>"
"        <item>"
"            <attribute name='label' translatable='yes'>_Paste</attribute <↵
">"
"            <attribute name='action'>example.paste</attribute>"
"            <attribute name='accel'>&lt;Primary&gt;v</attribute>"
"        </item>"
"    </submenu>"
" </menu>"
"</interface>";

// When the menubar is a child of a Gtk::Window, keyboard accelerators <↵
// are not
// automatically fetched from the Gio::Menu.
// See the examples/book/menus/main_menu example for an alternative way <↵
// of
// adding the menubar when using Gtk::ApplicationWindow.
// Gtk::Application::set_accel_for_action() is new in gtkmm 3.11.9.
app->set_accel_for_action("example.new", "<Primary>n");
app->set_accel_for_action("example.open", "<Primary>o");
app->set_accel_for_action("example.quit", "<Primary>q");
app->set_accel_for_action("example.cut", "<Primary>x");
app->set_accel_for_action("example.copy", "<Primary>c");
app->set_accel_for_action("example.paste", "<Primary>v");

try
{
    m_refBuilder->add_from_string(ui_info);
    m_refBuilder->add_from_resource("/toolbar/toolbar.glade");
}
catch(const Glib::Error& ex)
{
    std::cerr << "Building menus and toolbar failed: " << ex.what();
}

```

---

```
//Get the menubar:
auto object = m_refBuilder->get_object("menubar");
auto gmenu = Glib::RefPtr<Gio::Menu>::cast_dynamic(object);
if (!gmenu)
    g_warning("GMenu not found");
else
{
    auto pMenuBar = Gtk::make_managed<Gtk::MenuBar>(gmenu);

    //Add the MenuBar to the window:
    m_Box.pack_start(*pMenuBar, Gtk::PACK_SHRINK);
}

//Get the toolbar and add it to a container widget:
Gtk::Toolbar* toolbar = nullptr;
m_refBuilder->get_widget("toolbar", toolbar);
if (!toolbar)
    g_warning("GtkToolbar not found");
else
    m_Box.pack_start(*toolbar, Gtk::PACK_SHRINK);

show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_action_file_quit()
{
    hide(); //Closes the main window to stop the app->run().
}

void ExampleWindow::on_action_file_new()
{
    std::cout << "A File|New menu item was selected." << std::endl;
}

void ExampleWindow::on_action_others()
{
    std::cout << "A menu item was selected." << std::endl;
}

void ExampleWindow::on_action_toggle()
{
    std::cout << "The toggle menu item was selected." << std::endl;
}
```

---

```
bool active = false;
m_refActionRain->get_state(active);

//The toggle action's state does not change automatically:
active = !active;
m_refActionRain->change_state(active);

Glib::ustring message;
if(active)
    message = "Toggle is active.";
else
    message = "Toggle is not active";

std::cout << message << std::endl;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include <gtkmm.h>
#include "examplewindow.h"

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window(app);

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

**File: toolbar.gresource.xml (For use with gtkmm 3)**

```
<?xml version="1.0" encoding="UTF-8"?>
<gresources>
  <gresource prefix="/toolbar">
    <file preprocess="xml-stripblanks">toolbar.glade</file>
    <file>rain.png</file>
  </gresource>
</gresources>
```

### 12.5.3 Popup Menu example




Figure 12.3: Popup Menu

#### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

#include <memory>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    bool on_button_press_event(GdkEventButton* button_event) override;

    void on_menu_file_popup_generic();

    //Child widgets:
    Gtk::Box m_Box;
```

```

    Gtk::EventBox m_EventBox;
    Gtk::Label m_Label;

    Glib::RefPtr<Gtk::Builder> m_refBuilder;

    std::unique_ptr<Gtk::Menu> m_pMenuPopup;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

File: examplewindow.cc (For use with gtkmm 3)

```

#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: m_Box(Gtk::ORIENTATION_VERTICAL),
  m_Label("Right-click to see the popup menu."),
  m_pMenuPopup(nullptr)
{
    set_title("popup example");
    set_default_size(200, 200);

    add(m_Box);

    //Add an event box that can catch button_press events:
    m_Box.pack_start(m_EventBox);
    m_EventBox.signal_button_press_event().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_button_press_event) );

    m_EventBox.add(m_Label);

    //Create actions:

    //Fill menu:

    auto refActionGroup =
        Gio::SimpleActionGroup::create();

    //File|New sub menu:
    //These menu actions would normally already exist for a main menu, ↵
    //because a
    //context menu should not normally contain menu items that are only ↵
    //available
    //via a context menu.

    refActionGroup->add_action("edit",
        sigc::mem_fun(*this, &ExampleWindow::on_menu_file_popup_generic));

```



```

refActionGroup->add_action("process", //TODO: How to specify "<control>P ←
    " as an accelerator.
    sigc::mem_fun(*this, &ExampleWindow::on_menu_file_popup_generic));

refActionGroup->add_action("remove",
    sigc::mem_fun(*this, &ExampleWindow::on_menu_file_popup_generic));

insert_action_group("examplepopup", refActionGroup);

m_refBuilder = Gtk::Builder::create();

//Layout the actions in a menubar and toolbar:
Glib::ustring ui_info =
    "<interface>"
    "  <menu id='menu-examplepopup'>"
    "    <section>"
    "      <item>"
    "        <attribute name='label' translatable='yes'>Edit</attribute>"
    "        <attribute name='action'>examplepopup.edit</attribute>"
    "      </item>"
    "      <item>"
    "        <attribute name='label' translatable='yes'>Process</attribute ←
    "      >"
    "        <attribute name='action'>examplepopup.process</attribute>"
    "      </item>"
    "      <item>"
    "        <attribute name='label' translatable='yes'>Remove</attribute ←
    "      >"
    "        <attribute name='action'>examplepopup.remove</attribute>"
    "      </item>"
    "    </section>"
    "  </menu>"
    "</interface>";

try
{
    m_refBuilder->add_from_string(ui_info);
}
catch(const Glib::Error& ex)
{
    std::cerr << "building menus failed: " << ex.what();
}

//Get the menu:
auto object =

```

---

```

    m_refBuilder->get_object("menu-examplepopup");
    auto gmenu =
        Glib::RefPtr<Gio::Menu>::cast_dynamic(object);
    if(!gmenu)
        g_warning("GMenu not found");

    m_pMenuPopup = std::make_unique<Gtk::Menu>(gmenu);

    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_menu_file_popup_generic()
{
    std::cout << "A popup menu item was selected." << std::endl;
}

bool ExampleWindow::on_button_press_event(GdkEventButton* button_event)
{
    if( (button_event->type == GDK_BUTTON_PRESS) && (button_event->button == ↵
        3) )
    {
        if(!m_pMenuPopup->get_attach_widget())
        {
            m_pMenuPopup->attach_to_widget(*this);
        }

        if(m_pMenuPopup)
            m_pMenuPopup->popup_at_pointer((GdkEvent*)button_event);

        // Menu::popup_at_pointer() is new in gtkmm 3.22.
        // If you have an older revision, try this:
        //m_pMenuPopup->popup(button_event->button, button_event->time);

        return true; //It has been handled.
    }
    else
        return false;
}

```

File: main.cc (For use with gtkmm 3)

```

#include "examplewindow.h"
#include <gtkmm/application.h>

```

---

```
int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## Chapter 13

# ToolPalette

A `ToolPalette` is similar to a `Toolbar` but can contain a grid of items, categorized into groups. The user may hide or expand each group. As in a toolbar, the items may be displayed as only icons, as only text, or as icons with text.

The `ToolPalette`'s items might be dragged or simply activated. For instance, the user might drag objects to a canvas to create new items there. Or the user might click an item to activate a certain brush size in a drawing application.

`ToolItemGroups` should be added to the tool palette via the base class's `Gtk::Container::add()` method, for instance like so:

```
Gtk::ToolItemGroup* group_brushes =  
    Gtk::manage(new Gtk::ToolItemGroup("Brushes"));  
m_ToolPalette.add(*group_brushes);
```

`Gtk::ToolItems` can then be added to the group. For instance, like so:

```
Gtk::ToolButton* button = Gtk::manage(new Gtk::ToolButton(icon, "Big"));  
button->set_tooltip_text("Big Brush");  
group_brushes->insert(*button);
```

You might then handle the `ToolButton`'s clicked signal. Alternatively, you could allow the item to be dragged to another widget, by calling `Gtk::ToolPalette::add_drag_dest()` and then using `Gtk::ToolPalette::get_drag_item()` in the other widget's `drag_data_received` signal handler.

[ToolPalette Reference](#)

[ToolItemGroup Reference](#)

[ToolItem Reference](#)

---

## 13.1 Drag and Drop

Call `add_drag_dest()` to allow items or groups to be dragged from the tool palette to a particular destination widget. You can then use `get_drag_item()` to discover which `ToolItem` or `ToolItem-Group` is being dragged. You can use `dynamic_cast` to discover whether it is an item or a group. For instance, you might use this in your `drag_data_received` signal handler, to add a dropped item, or to show a suitable icon while dragging.

See the [Drag and Drop](#) chapter for general advice about Drag and Drop with gtkmm.

## 13.2 ToolPalette Example

This example adds a `ToolPalette` and a `DrawingArea` to a window and allows the user to drag icons from the tool palette to the drawing area. The tool palette contains several groups of items. The combo boxes allow the user to change the style and orientation of the tool palette.




Figure 13.1: ToolPalette

### Source Code

File: `canvas.h` (For use with gtkmm 3)

---

```
#ifndef GTKMM_EXAMPLE_CANVAS_H
#define GTKMM_EXAMPLE_CANVAS_H

#include <gtkmm.h>

// This little canvas class is only here
// because gtkmm does not have a canvas class yet.
// Applications should probably use GooCanvas::Canvas (gocanvasmm) ↔
// instead.
class Canvas : public Gtk::DrawingArea
{
public:
    Canvas();
    virtual ~Canvas();

private:

    class CanvasItem
    {
    public:
        CanvasItem(Gtk::Widget* canvas, Gtk::ToolButton* button, double x, ↔
            double y)
        {
            Glib::ustring icon_name(button->get_icon_name());
            if (icon_name.empty())
                icon_name = button->get_label();

            auto icon_theme = Gtk::IconTheme::get_for_screen(canvas->get_screen ↔
                ());
            int width = 0;
            int height = 0; //ignored
            Gtk::IconSize::lookup(Gtk::ICON_SIZE_DIALOG, width, height);
            this->m_pixbuf = icon_theme->load_icon(icon_name, width, Gtk:: ↔
                ICON_LOOKUP_GENERIC_FALLBACK);
            this->m_x = x;
            this->m_y = y;
        }

        Glib::RefPtr<Gdk::Pixbuf> m_pixbuf;
        double m_x, m_y;
    };

    void item_draw(const CanvasItem *item,
        const Cairo::RefPtr<Cairo::Context>& cr,
        bool preview);

    bool on_draw(const Cairo::RefPtr<Cairo::Context>& cr) override;
```

---

```

void on_drag_data_received(const Glib::RefPtr<Gdk::DragContext>& context ←
    ,
    int x, int y, const Gtk::SelectionData& selection_data, guint info, ←
    guint time) override;
bool on_drag_motion(const Glib::RefPtr<Gdk::DragContext>& context, int x ←
    , int y, guint time) override;
bool on_drag_drop(const Glib::RefPtr<Gdk::DragContext>& context, int x, ←
    int y, guint time) override;
void on_drag_leave(const Glib::RefPtr<Gdk::DragContext>& context, guint ←
    time) override;

bool m_drag_data_requested_for_drop; //So we know what to do in ←
on_drag_data_received().
CanvasItem* m_drop_item;

typedef std::vector<CanvasItem*> type_vec_items;
type_vec_items m_canvas_items;
};

#endif //GTKMM_EXAMPLE_CANVAS_H

```

**File: examplewindow.h (For use with gtkmm 3)**

```

#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>
#include "canvas.h"

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

private:

    void load_icon_items();
    void load_toggle_items();
    void load_special_items();

    //Signal handlers:
    void on_combo_orientation_changed();
    void on_combo_style_changed();

    //Tree model columns:
    class ModelColumnsOrientation : public Gtk::TreeModel::ColumnRecord
    {

```



```

public:

    ModelColumnsOrientation()
    { add(m_col_value); add(m_col_name); }

    Gtk::TreeModelColumn<Gtk::Orientation> m_col_value;
    Gtk::TreeModelColumn<Glib::ustring> m_col_name;
};

ModelColumnsOrientation m_ColumnsOrientation;

//Tree model columns:
class ModelColumnsStyle : public Gtk::TreeModel::ColumnRecord
{
public:

    ModelColumnsStyle()
    { add(m_col_value); add(m_col_name); }

    Gtk::TreeModelColumn<int> m_col_value; //We use int to also allow -1
    Gtk::TreeModelColumn<Glib::ustring> m_col_name;
};

ModelColumnsStyle m_ColumnsStyle;

//Child widgets:
Gtk::Box m_VBox;
Gtk::Box m_HBox;
Gtk::ComboBox m_ComboOrientation;
Glib::RefPtr<Gtk::ListStore> m_refTreeModelOrientation;
Gtk::ComboBox m_ComboStyle;
Glib::RefPtr<Gtk::ListStore> m_refTreeModelStyle;
Gtk::ToolPalette m_ToolPalette;
Gtk::ScrolledWindow m_ScrolledWindowPalette;
Gtk::ScrolledWindow m_ScrolledWindowCanvas;
Canvas m_Canvas;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

**File: canvas.cc (For use with gtkmm 3)**

```

#include "canvas.h"
#include <iostream>

Canvas::Canvas()
: m_drag_data_requested_for_drop(false),

```

---

```
m_drop_item(nullptr)
{
    set_app_paintable();
}

Canvas::~Canvas()
{
    while(!m_canvas_items.empty())
    {
        auto iter = m_canvas_items.begin();
        auto item = *iter;
        delete item;
        m_canvas_items.erase(iter);
    }

    delete m_drop_item;
}

void Canvas::item_draw(const CanvasItem *item,
    const Cairo::RefPtr<Cairo::Context>& cr,
    bool preview)
{
    if(!item || !item->m_pixbuf)
        return;

    const double cx = item->m_pixbuf->get_width();
    const double cy = item->m_pixbuf->get_height();

    Gdk::Cairo::set_source_pixbuf(cr,
        item->m_pixbuf,
        item->m_x - cx * 0.5, item->m_y - cy * 0.5);

    if(preview)
        cr->paint_with_alpha(0.6);
    else
        cr->paint();
}

bool Canvas::on_draw(const Cairo::RefPtr<Cairo::Context>& cr)
{
    cr->set_source_rgb(1.0, 1.0, 1.0);
    const Gtk::Allocation allocation = get_allocation();
    cr->rectangle(0, 0, allocation.get_width(), allocation.get_height());
    cr->fill();

    for(type_vec_items::iterator iter = m_canvas_items.begin();
        iter != m_canvas_items.end(); ++iter )
```

---

```
{
    item_draw(*iter, cr, false);
}

if(m_drop_item)
    item_draw (m_drop_item, cr, true);

return true;
}

bool Canvas::on_drag_motion(const Glib::RefPtr<Gdk::DragContext>& context,
    int x, int y, guint time)
{
    m_drag_data_requested_for_drop = false; //It's for drag-motion instead.

    if(m_drop_item)
    {
        // We already have a drop indicator so just update its position.

        m_drop_item->m_x = x;
        m_drop_item->m_y = y;

        queue_draw();
        context->drag_status(Gdk::ACTION_COPY, time);
    }
    else
    {
        // Request DnD data for creating a drop indicator.
        // This will cause on_drag_data_received() to be called.
        const Glib::ustring target = drag_dest_find_target(context);

        if (target.empty())
            return false;

        drag_get_data(context, target, time);
    }

    Gtk::DrawingArea::on_drag_motion(context, x, y, time);
    return true;
}

void Canvas::on_drag_data_received(const Glib::RefPtr<Gdk::DragContext>& ←
    context,
    int x, int y, const Gtk::SelectionData& selection_data, guint info, ←
    guint time)
```

---

```
{
    // Find the tool button which is the source of this DnD operation.
    auto widget = drag_get_source_widget(context);

    auto drag_palette = dynamic_cast<Gtk::ToolPalette*>(widget);
    while(widget && !drag_palette)
    {
        widget = widget->get_parent();
        drag_palette = dynamic_cast<Gtk::ToolPalette*>(widget);
    }

    Gtk::ToolItem* drag_item = nullptr;
    if(drag_palette)
        drag_item = drag_palette->get_drag_item(selection_data);

    // Create a drop indicator when a tool button was found:
    auto button = dynamic_cast<Gtk::ToolButton*>(drag_item);
    if(!button)
        return;

    delete m_drop_item;
    m_drop_item = nullptr;

    try
    {
        auto item = new CanvasItem(this, button, x, y);

        if(m_drag_data_requested_for_drop)
        {
            m_canvas_items.push_back(item);

            // Signal that the item was accepted and then redraw.
            context->drag_finish(true /* success */, false /* del */, time);
        }
        else
        {
            m_drop_item = item;

            // We are getting this data due to a request in drag_motion,
            // rather than due to a request in drag_drop, so we are just
            // supposed to call gdk_drag_status (), not actually paste in
            // the data.
            context->drag_status(Gdk::ACTION_COPY, time);
        }

        queue_draw();
    }
}
```

---

```
catch (const Gtk::IconThemeError& ex)
{
    std::cerr << "IconThemeError: " << ex.what() << std::endl;
}

Gtk::DrawingArea::on_drag_data_received(context, x, y, selection_data, ←
    info, time);
}

bool Canvas::on_drag_drop(const Glib::RefPtr<Gdk::DragContext>& context, ←
    int /* x */, int /* y */, guint time)
{
    // Request DnD data for creating a dopped item.
    // This will cause on_drag_data_received() to be called.
    const Glib::ustring target = drag_dest_find_target(context);

    if (target.empty())
        return false;

    m_drag_data_requested_for_drop = true;
    drag_get_data(context, target, time);

    return true;
}

void Canvas::on_drag_leave(const Glib::RefPtr<Gdk::DragContext>& context, ←
    guint time)
{
    //This signal is emitted to clean up the item used for drag-motion,
    //either when the cursor moves out of the widget or when we drop.

    if(!m_drop_item)
        return;

    delete m_drop_item;
    m_drop_item = nullptr;

    queue_draw();

    Gtk::DrawingArea::on_drag_leave(context, time);
}
```

**File:** examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
```

---

```
void ExampleWindow::load_icon_items()
{
    auto icon_theme = Gtk::IconTheme::get_for_screen(get_screen());

    typedef std::vector<Glib::ustring> type_stringvec;
    type_stringvec icon_names = icon_theme->list_icons();

    // Obtain the names of all contexts, and the icon names per context.
    type_stringvec contexts = icon_theme->list_contexts();
    std::sort(contexts.begin(), contexts.end());

    int requested_icon_size = 0;
    int requested_icon_height = 0; //ignored
    Gtk::IconSize::lookup(Gtk::ICON_SIZE_BUTTON, requested_icon_size, ↵
        requested_icon_height);
    const quint max_icons_per_group = 10;

    for (type_stringvec::const_iterator iter = contexts.begin(); iter != ↵
        contexts.end(); ++iter)
    {
        const Glib::ustring context_name = *iter;
        auto group = Gtk::make_managed<Gtk::ToolItemGroup>(context_name);
        m_ToolPalette.add(*group);

        // Iterate through the icon names, populating the ToolItemGroup as ↵
        // appropriate.
        type_stringvec icon_names_for_context = icon_theme->list_icons( ↵
            context_name);
        std::sort(icon_names_for_context.begin(), icon_names_for_context.end() ↵
            );
        quint icons_count = 0;
        for (type_stringvec::const_iterator iconiter = icon_names_for_context. ↵
            begin(); iconiter != icon_names_for_context.end(); ++iconiter)
        {
            const Glib::ustring icon_name = *iconiter;
            Glib::RefPtr<Gdk::Pixbuf> pixbuf;
            try
            {
                pixbuf = icon_theme->load_icon(icon_name, requested_icon_size, Gtk ↵
                    ::ICON_LOOKUP_GENERIC_FALLBACK);
            }
            catch (const Gtk::IconThemeError& /* ex */)
            {
                // Gtk::IconTheme::list_icons() may return some names of icons
                // that can't be loaded.
                continue;
            }
        }
    }
}
```

---

```
// Skip large icons, just to make the ToolPalette look better.
if (pixbuf->get_width() > 2*requested_icon_size ||
    pixbuf->get_height() > 2*requested_icon_size)
    continue;

auto image = Gtk::make_managed<Gtk::Image>(pixbuf);
auto button = Gtk::make_managed<Gtk::ToolButton>(*image, icon_name);
button->set_tooltip_text(icon_name);
button->set_is_important();
group->insert(*button);

// Prevent us having an insane number of icons:
++icons_count;
if(icons_count >= max_icons_per_group)
    break;
}
}
}

void ExampleWindow::load_toggle_items()
{
    auto group = Gtk::make_managed<Gtk::ToolItemGroup>("Radio Item");
    m_ToolPalette.add(*group);

    Gtk::RadioToolButton::Group radio_group;

    for(int i = 1; i <= 10; ++i)
    {
        const Glib::ustring label = Glib::ustring::compose("#%1", i);
        auto button = Gtk::make_managed<Gtk::RadioToolButton>();
        button->set_group(radio_group);
        button->set_label(label);

        group->insert(*button);
    }
}

static Gtk::ToolItem* create_entry_item(const Glib::ustring& text)
{
    auto entry = Gtk::make_managed<Gtk::Entry>();
    entry->set_text(text);
    entry->set_width_chars(5);

    auto item = Gtk::make_managed<Gtk::ToolItem>();
```

---

```
    item->add(*entry);

    return item;
}

void ExampleWindow::load_special_items()
{
    auto group = Gtk::make_managed<Gtk::ToolItemGroup>();

    Gtk::Button *label_button = Gtk::make_managed<Gtk::Button>("Advanced ↵
        Features");
    label_button->show();
    group->set_label_widget(*label_button);
    m_ToolPalette.add(*group);

    auto item = create_entry_item ("homogeneous=false");
    group->insert(*item);
    //TODO: Add Gtk::Container::set_child_property().
    gtk_container_child_set (GTK_CONTAINER (group->gobj()), GTK_WIDGET (item ↵
        ->gobj()),
                            "homogeneous", FALSE, NULL);

    item = create_entry_item ("homogeneous=FALSE, expand=TRUE");
    group->insert(*item);
    gtk_container_child_set (GTK_CONTAINER (group->gobj()), GTK_WIDGET (item ↵
        ->gobj()),
                            "homogeneous", FALSE, "expand", TRUE,
                            NULL);

    item = create_entry_item ("homogeneous=FALSE, expand=TRUE, fill=FALSE");
    group->insert(*item);
    gtk_container_child_set (GTK_CONTAINER (group->gobj()), GTK_WIDGET (item ↵
        ->gobj()),
                            "homogeneous", FALSE, "expand", TRUE,
                            "fill", FALSE, NULL);

    item = create_entry_item ("homogeneous=FALSE, expand=TRUE, new-row=TRUE ↵
        ");
    group->insert(*item);
    gtk_container_child_set (GTK_CONTAINER (group->gobj()), GTK_WIDGET (item ↵
        ->gobj()),
                            "homogeneous", FALSE, "expand", TRUE,
                            "new-row", TRUE, NULL);

    auto button = Gtk::make_managed<Gtk::ToolButton>();
    button->set_icon_name("go-up");
    button->set_tooltip_text("Show on vertical palettes only");
```

---



```

group->insert(*button);
button->set_visible_horizontal(false);

button = Gtk::make_managed<Gtk::ToolButton>();
button->set_icon_name("go-next");
button->set_tooltip_text("Show on horizontal palettes only");
group->insert(*button);
button->set_visible_vertical(false);

button = Gtk::make_managed<Gtk::ToolButton>();
button->set_icon_name("edit-delete");
button->set_tooltip_text("Do not show at all");
button->set_no_show_all();
group->insert(*button);
button->set_visible_vertical(false);

button = Gtk::make_managed<Gtk::ToolButton>();
button->set_icon_name("view-fullscreen");
button->set_tooltip_text("Expanded this item");
group->insert(*button);
gtk_container_child_set(GTK_CONTAINER(group->gobj()), GTK_WIDGET(button->gobj()),
                        "homogeneous", FALSE,
                        "expand", TRUE,
                        NULL);

button = Gtk::make_managed<Gtk::ToolButton>();
button->set_icon_name("help-contents");
button->set_tooltip_text("A regular item");
group->insert(*button);
}

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL, 6),
  m_HBox(Gtk::ORIENTATION_HORIZONTAL, 6)
{
    set_title("Gtk::ToolPalette example");
    set_size_request(600, 600);
    set_border_width(6);

    add(m_VBox);

    //The Orientation ComboBox:
    m_refTreeModelOrientation = Gtk::ListStore::create(m_ColumnsOrientation)
    ;
    Gtk::TreeModel::Row row = *(m_refTreeModelOrientation->append());
    row[m_ColumnsOrientation.m_col_value] = Gtk::ORIENTATION_HORIZONTAL;

```

---

```

row[m_ColumnsOrientation.m_col_name] = "Horizontal";\
row = *(m_refTreeModelOrientation->append());
row[m_ColumnsOrientation.m_col_value] = Gtk::ORIENTATION_VERTICAL;
row[m_ColumnsOrientation.m_col_name] = "Vertical";
m_ComboOrientation.set_model(m_refTreeModelOrientation);
m_VBox.pack_start(m_ComboOrientation, Gtk::PACK_SHRINK);
m_ComboOrientation.pack_start(m_ColumnsOrientation.m_col_name);
m_ComboOrientation.signal_changed().connect(
    sigc::mem_fun(*this, &ExampleWindow::on_combo_orientation_changed) );
m_ComboOrientation.set_active(row);

//The Style ComboBox:
m_refTreeModelStyle = Gtk::ListStore::create(m_ColumnsStyle);
row = *(m_refTreeModelStyle->append());
row[m_ColumnsStyle.m_col_value] = Gtk::TOOLBAR_TEXT;
row[m_ColumnsStyle.m_col_name] = "Text";\
row = *(m_refTreeModelStyle->append());
row[m_ColumnsStyle.m_col_value] = Gtk::TOOLBAR_BOTH;
row[m_ColumnsStyle.m_col_name] = "Both";
row = *(m_refTreeModelStyle->append());
row[m_ColumnsStyle.m_col_value] = Gtk::TOOLBAR_BOTH_HORIZ;
row[m_ColumnsStyle.m_col_name] = "Both: Horizontal";
row = *(m_refTreeModelStyle->append());
row[m_ColumnsStyle.m_col_value] = Gtk::TOOLBAR_ICONS;
row[m_ColumnsStyle.m_col_name] = "Icons";
row = *(m_refTreeModelStyle->append());
row[m_ColumnsStyle.m_col_value] = -1; // A custom meaning for this demo.
row[m_ColumnsStyle.m_col_name] = "Default";
m_ComboStyle.set_model(m_refTreeModelStyle);
m_VBox.pack_start(m_ComboStyle, Gtk::PACK_SHRINK);
m_ComboStyle.pack_start(m_ColumnsStyle.m_col_name);
m_ComboStyle.signal_changed().connect(
    sigc::mem_fun(*this, &ExampleWindow::on_combo_style_changed) );
m_ComboStyle.set_active(row);

//Add and fill the ToolPalette:
load_icon_items();
load_toggle_items();
load_special_items();

m_VBox.pack_start(m_HBox, Gtk::PACK_EXPAND_WIDGET);

m_ScrolledWindowPalette.set_policy(Gtk::POLICY_NEVER, Gtk::POLICY_AUTOMATIC);
m_ScrolledWindowPalette.set_border_width(6);
m_ScrolledWindowPalette.add(m_ToolPalette);
m_HBox.pack_start(m_ScrolledWindowPalette);

```

---

```
on_combo_orientation_changed();

m_ScrolledWindowCanvas.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::↵
    POLICY_ALWAYS);
m_ScrolledWindowCanvas.set_border_width(6);
m_ScrolledWindowCanvas.add(m_Canvas);
m_ScrolledWindowCanvas.set_size_request(200, -1);
m_HBox.pack_start(m_ScrolledWindowCanvas);

m_ToolPalette.add_drag_dest(m_Canvas,
    Gtk::DEST_DEFAULT_HIGHLIGHT, Gtk::TOOL_PALETTE_DRAG_ITEMS, Gdk::↵
    ACTION_COPY);

show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_combo_orientation_changed()
{
    Gtk::TreeModel::iterator iter = m_ComboOrientation.get_active();
    if(!iter)
        return;

    Gtk::TreeModel::Row row = *iter;
    const Gtk::Orientation value = row[m_ColumnsOrientation.m_col_value];

    m_ToolPalette.set_orientation(value);

    if(value == Gtk::ORIENTATION_HORIZONTAL)
        m_ScrolledWindowPalette.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::↵
            POLICY_NEVER);
    else
        m_ScrolledWindowPalette.set_policy(Gtk::POLICY_NEVER, Gtk::↵
            POLICY_AUTOMATIC);
}

void ExampleWindow::on_combo_style_changed()
{
    Gtk::TreeModel::iterator iter = m_ComboStyle.get_active();
    if(!iter)
        return;

    Gtk::TreeModel::Row row = *iter;
```

```
const int value = row[m_ColumnsStyle.m_col_value];

if(value == -1)
    m_ToolPalette.unset_style();
else
    m_ToolPalette.set_style((Gtk::ToolbarStyle) value);
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## Chapter 14

# Adjustments

gtkmm has various widgets that can be visually adjusted using the mouse or the keyboard, such as the Range widgets (described in the [Range Widgets](#) section). There are also a few widgets that display some adjustable part of a larger area, such as the Viewport widget. These widgets have `Gtk::Adjustment` objects that express this common part of their API.

So that applications can react to changes, for instance when a user moves a scrollbar, `Gtk::Adjustment` has a `value_changed` signal. You can then use the `get_value()` method to discover the new value.

### 14.1 Creating an Adjustment

The `Gtk::Adjustment` is created by its `create()` method which is as follows:

```
Glib::RefPtr<Gtk::Adjustment> Gtk::Adjustment::create(  
    double value,  
    double lower,  
    double upper,  
    double step_increment = 1,  
    double page_increment = 10,  
    double page_size = 0);
```

The *value* argument is the initial value of the adjustment, usually corresponding to the topmost or leftmost position of an adjustable widget. The *lower* and *upper* arguments specify the possible range of values which the adjustment can hold. The *step\_increment* argument specifies the smaller of the two increments by which the user can change the value, while the *page\_increment* is the larger one. The *page\_size* argument usually corresponds somehow to the visible area of a panning widget. The *upper* argument is used to represent the bottommost or rightmost coordinate in a panning widget's child.

---

## 14.2 Using Adjustments the Easy Way

The adjustable widgets can be roughly divided into those which use and require specific units for these values, and those which treat them as arbitrary numbers.

The group which treats the values as arbitrary numbers includes the Range widgets (`Scrollbar` and `Scale`), the `ScaleButton` widget, and the `SpinButton` widget. These widgets are typically "adjusted" directly by the user with the mouse or keyboard. They will treat the *lower* and *upper* values of an adjustment as a range within which the user can manipulate the adjustment's *value*. By default, they will only modify the *value* of an adjustment.

The other group includes the `Viewport` widget and the `ScrolledWindow` widget. All of these widgets use pixel values for their adjustments. These are also typically adjusted indirectly using scrollbars. While all widgets which use adjustments can either create their own adjustments or use ones you supply, you'll generally want to let this particular category of widgets create its own adjustments.

If you share an adjustment object between a `Scrollbar` and a `TextView` widget, manipulating the scrollbar will automatically adjust the `TextView` widget. You can set it up like this:

```
// creates its own adjustments
Gtk::TextView textview;
// uses the newly-created adjustment for the scrollbar as well
Gtk::Scrollbar vscrollbar (textview.get_vadjustment(), Gtk::↔
    ORIENTATION_VERTICAL);
```

## 14.3 Adjustment Internals

OK, you say, that's nice, but what if I want to create my own handlers to respond when the user adjusts a Range widget or a `SpinButton`. To access the value of a `Gtk::Adjustment`, you can use the `get_value()` and `set_value()` methods:

As mentioned earlier, `Gtk::Adjustment` can emit signals. This is, of course, how updates happen automatically when you share an `Adjustment` object between a `Scrollbar` and another adjustable widget; all adjustable widgets connect signal handlers to their adjustment's `value_changed` signal, as can your program.

So, for example, if you have a `Scale` widget, and you want to change the rotation of a picture whenever its value changes, you would create a signal handler like this:

```
void cb_rotate_picture (MyPicture* picture)
{
    picture->set_rotation(adj->get_value());
    ...
}
```

and connect it to the scale widget's adjustment like this:

---

```
adj->signal_value_changed().connect(sigc::bind<MyPicture*>(sigc::mem_fun(* ←  
    this,  
    &cb_rotate_picture), picture));
```

What if a widget reconfigures the *upper* or *lower* fields of its Adjustment, such as when a user adds more text to a text widget? In this case, it emits the *changed* signal.

Range widgets typically connect a handler to this signal, which changes their appearance to reflect the change - for example, the size of the slider in a scrollbar will grow or shrink in inverse proportion to the difference between the *lower* and *upper* values of its Adjustment.

You probably won't ever need to attach a handler to this signal, unless you're writing a new type of range widget.

```
adjustment->signal_changed();
```

---

## Chapter 15

# Widgets Without X-Windows

Some Widgets do not have an associated X-Window, so they therefore do not receive X events. This means that the signals described in the **X event signals** section will not be emitted. If you want to capture events for these widgets you can use a special container called `Gtk::EventBox`, which is described in the **EventBox** section.

Here is a list of some of these Widgets:

```
Gtk::Alignment (deprecated from gtkmm version 3.14)
Gtk::Arrow (deprecated from gtkmm version 3.14)
Gtk::AspectFrame
Gtk::Bin
Gtk::Box
Gtk::Button
Gtk::CheckButton
Gtk::Fixed
Gtk::Frame
Gtk::Grid
Gtk::Image
Gtk::Label
Gtk::MenuItem
Gtk::Notebook
Gtk::Paned
Gtk::RadioButton
Gtk::Range
Gtk::ScrolledWindow
Gtk::Separator
Gtk::Table (deprecated from gtkmm version 3.4)
Gtk::Toolbar
```



These widgets are mainly used for decoration or layout, so you won't often need to capture events on them. They are intended to have no X-Window in order to improve performance.

## 15.1 EventBox

Some gtkmm widgets don't have associated X windows; they draw on their parents' windows. Because of this, they cannot receive events. Also, if they are incorrectly sized, they don't clip, so you can get messy overwriting etc. To receive events on one of these widgets, you can place it inside an `EventBox` widget and then call `Gtk::Widget::set_events()` on the `EventBox` before showing it.

Although the name `EventBox` emphasises the event-handling method, the widget can also be used for clipping (and more; see the example below).

The constructor for `Gtk::EventBox` is:

```
Gtk::EventBox();
```

A child widget can be added to the `EventBox` using:

```
event_box.add(child_widget);
```

### Reference

#### 15.1.1 Example

The following example demonstrates both uses of an `EventBox` - a label is created that is clipped to a small box, and set up so that a mouse-click on the label causes the program to exit. Resizing the window reveals varying amounts of the label.




Figure 15.1: EventBox

### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

---

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    bool on_eventbox_button_press(GdkEventButton* button_event);

    //Child widgets:
    Gtk::EventBox m_EventBox;
    Gtk::Label m_Label;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_Label("Click here to quit, quit, quit, quit")
{
    set_title ("EventBox");
    set_border_width(10);

    add(m_EventBox);

    m_EventBox.add(m_Label);

    //Clip the label short:
    set_default_size(110, 20);
    m_Label.set_size_request(110, 20);
    m_Label.set_ellipsize(Pango::ELLIPSIZE_END);

    //And bind an action to it:
    m_EventBox.set_events(Gdk::BUTTON_PRESS_MASK);
    m_EventBox.signal_button_press_event().connect(
        sigc::mem_fun(*this, &ExampleWindow::on_eventbox_button_press) );

    m_EventBox.set_tooltip_text("Click me!");
```

```
    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

bool ExampleWindow::on_eventbox_button_press(GdkEventButton*)
{
    hide();
    return true;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## Chapter 16

# Dialogs

Dialogs are used as secondary windows, to provide specific information or to ask questions. `Gtk::Dialog` windows contain a few pre-packed widgets to ensure consistency, and a `run()` method which blocks until the user dismisses the dialog.

There are several derived `Dialog` classes which you might find useful. `Gtk::MessageDialog` is used for most simple notifications. But at other times you might need to derive your own dialog class to provide more complex functionality.

To pack widgets into a custom dialog, you should pack them into the `Gtk::Box`, available via `get_content_area()`. To just add a `Button` to the bottom of the `Dialog`, you could use the `add_button()` method.

The `run()` method returns an `int`. This may be a value from the `Gtk::ResponseType` if the user closed the dialog by clicking a standard button, or it could be the custom response value that you specified when using `add_button()`.

Reference

### 16.1 MessageDialog

`MessageDialog` is a convenience class, used to create simple, standard message dialogs, with a message, an icon, and buttons for user response. You can specify the type of message and the text in the constructor, as well as specifying standard buttons via the `Gtk::ButtonsType` enum.

Reference

---

### 16.1.1 Example



Figure 16.1: MessageDialog

#### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_info_clicked();
    void on_button_question_clicked();

    //Child widgets:
    Gtk::ButtonBox m_ButtonBox;
    Gtk::Button m_Button_Info, m_Button_Question;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: `examplewindow.cc` (For use with gtkmm 3)

---

```
#include "examplewindow.h"
#include <gtkmm/messagedialog.h>
#include <iostream>

ExampleWindow::ExampleWindow()
: m_ButtonBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_Info("Show Info MessageDialog"),
  m_Button_Question("Show Question MessageDialog")
{
    set_title("Gtk::MessageDialog example");

    add(m_ButtonBox);

    m_ButtonBox.pack_start(m_Button_Info);
    m_Button_Info.signal_clicked().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_button_info_clicked) );

    m_ButtonBox.pack_start(m_Button_Question);
    m_Button_Question.signal_clicked().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_button_question_clicked) );

    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_info_clicked()
{
    Gtk::MessageDialog dialog(*this, "This is an INFO MessageDialog");
    dialog.set_secondary_text(
        "And this is the secondary text that explains things.");

    dialog.run();
}

void ExampleWindow::on_button_question_clicked()
{
    Gtk::MessageDialog dialog(*this, "This is a QUESTION MessageDialog",
        false /* use_markup */, Gtk::MESSAGE_QUESTION,
        Gtk::BUTTONS_OK_CANCEL);
    dialog.set_secondary_text(
        "And this is the secondary text that explains things.");

    int result = dialog.run();
}
```

---

```
//Handle the response:
switch(result)
{
    case(Gtk::RESPONSE_OK):
    {
        std::cout << "OK clicked." << std::endl;
        break;
    }
    case(Gtk::RESPONSE_CANCEL):
    {
        std::cout << "Cancel clicked." << std::endl;
        break;
    }
    default:
    {
        std::cout << "Unexpected button clicked." << std::endl;
        break;
    }
}
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## 16.2 FileChooserDialog

The FileChooserDialog is suitable for use with "Open" or "Save" menu items.

Most of the useful member methods for this class are actually in the `Gtk::FileChooser` base class.

[Reference](#)

---

### 16.2.1 Example




Figure 16.2: FileChooser

#### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>
```



```
class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_file_clicked();
    void on_button_folder_clicked();

    //Child widgets:
    Gtk::ButtonBox m_ButtonBox;
    Gtk::Button m_Button_File, m_Button_Folder;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

**File:** examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: m_ButtonBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_File("Choose File"),
  m_Button_Folder("Choose Folder")
{
    set_title("Gtk::FileSelection example");

    add(m_ButtonBox);

    m_ButtonBox.pack_start(m_Button_File);
    m_Button_File.signal_clicked().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_button_file_clicked) );

    m_ButtonBox.pack_start(m_Button_Folder);
    m_Button_Folder.signal_clicked().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_button_folder_clicked) );

    show_all_children();
}

ExampleWindow::~~ExampleWindow()
{
}
```

```
void ExampleWindow::on_button_folder_clicked()
{
    Gtk::FileChooserDialog dialog("Please choose a folder",
                                   Gtk::FILE_CHOOSER_ACTION_SELECT_FOLDER);
    dialog.set_transient_for(*this);

    //Add response buttons the the dialog:
    dialog.add_button("_Cancel", Gtk::RESPONSE_CANCEL);
    dialog.add_button("Select", Gtk::RESPONSE_OK);

    int result = dialog.run();

    //Handle the response:
    switch(result)
    {
        case (Gtk::RESPONSE_OK) :
        {
            std::cout << "Select clicked." << std::endl;
            std::cout << "Folder selected: " << dialog.get_filename()
                      << std::endl;
            break;
        }
        case (Gtk::RESPONSE_CANCEL) :
        {
            std::cout << "Cancel clicked." << std::endl;
            break;
        }
        default:
        {
            std::cout << "Unexpected button clicked." << std::endl;
            break;
        }
    }
}

void ExampleWindow::on_button_file_clicked()
{
    Gtk::FileChooserDialog dialog("Please choose a file",
                                   Gtk::FILE_CHOOSER_ACTION_OPEN);
    dialog.set_transient_for(*this);

    //Add response buttons the the dialog:
    dialog.add_button("_Cancel", Gtk::RESPONSE_CANCEL);
    dialog.add_button("_Open", Gtk::RESPONSE_OK);

    //Add filters, so that only certain file types can be selected:
```

---

```
auto filter_text = Gtk::FileFilter::create();
filter_text->set_name("Text files");
filter_text->add_mime_type("text/plain");
dialog.add_filter(filter_text);

auto filter_cpp = Gtk::FileFilter::create();
filter_cpp->set_name("C/C++ files");
filter_cpp->add_mime_type("text/x-c");
filter_cpp->add_mime_type("text/x-c++");
filter_cpp->add_mime_type("text/x-c-header");
dialog.add_filter(filter_cpp);

auto filter_any = Gtk::FileFilter::create();
filter_any->set_name("Any files");
filter_any->add_pattern("*");
dialog.add_filter(filter_any);

//Show the dialog and wait for a user response:
int result = dialog.run();

//Handle the response:
switch(result)
{
    case(Gtk::RESPONSE_OK):
    {
        std::cout << "Open clicked." << std::endl;

        //Notice that this is a std::string, not a Glib::ustring.
        std::string filename = dialog.get_filename();
        std::cout << "File selected: " << filename << std::endl;
        break;
    }
    case(Gtk::RESPONSE_CANCEL):
    {
        std::cout << "Cancel clicked." << std::endl;
        break;
    }
    default:
    {
        std::cout << "Unexpected button clicked." << std::endl;
        break;
    }
}
}
```

File: main.cc (For use with gtkmm 3)

---

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## 16.3 ColorChooserDialog

The `ColorChooserDialog` allows the user to choose a color. The `ColorButton` opens a color selection dialog when it is clicked.

### Reference

### 16.3.1 Example




Figure 16.3: ColorChooserDialog

#### Source Code

File: examplewindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
```

```
//Signal handlers:
void on_color_button_color_set();
void on_button_dialog_clicked();
bool on_drawing_area_draw(const Cairo::RefPtr<Cairo::Context>& cr);

//Child widgets:
Gtk::Box m_VBox;
Gtk::ColorButton m_ColorButton;
Gtk::Button m_Button_Dialog;
Gtk::DrawingArea m_DrawingArea; //To show the color.

Gdk::RGBA m_Color;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL, 5),
  m_Button_Dialog("Choose Color")
{
    set_title("Gtk::ColorChooserDialog example");
    set_default_size(200, 200);

    add(m_VBox);

    m_VBox.pack_start(m_ColorButton, Gtk::PACK_SHRINK);
    m_ColorButton.signal_color_set().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_color_button_color_set) );

    m_VBox.pack_start(m_Button_Dialog, Gtk::PACK_SHRINK);
    m_Button_Dialog.signal_clicked().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_button_dialog_clicked) );

    //Set start color:
    m_Color.set_red(0.0);
    m_Color.set_green(0.0);
    m_Color.set_blue(1.0);
    m_Color.set_alpha(1.0); //opaque
    m_ColorButton.set_rgba(m_Color);

    m_VBox.pack_start(m_DrawingArea);
    m_DrawingArea.signal_draw().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_drawing_area_draw));
```

```
    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_color_button_color_set()
{
    //Store the chosen color:
    m_Color = m_ColorButton.get_rgba();
}

void ExampleWindow::on_button_dialog_clicked()
{
    Gtk::ColorChooserDialog dialog("Please choose a color");
    dialog.set_transient_for(*this);

    //Get the previously selected color:
    dialog.set_rgba(m_Color);

    const int result = dialog.run();

    //Handle the response:
    switch(result)
    {
        case Gtk::RESPONSE_OK:
        {
            //Store the chosen color:
            m_Color = dialog.get_rgba();
            m_ColorButton.set_rgba(m_Color);
            break;
        }
        case Gtk::RESPONSE_CANCEL:
        {
            std::cout << "Cancel clicked." << std::endl;
            break;
        }
        default:
        {
            std::cout << "Unexpected button clicked: " << result << std::endl;
            break;
        }
    }
}
```

---

```
bool ExampleWindow::on_drawing_area_draw(const Cairo::RefPtr<Cairo::↵
    Context>& cr)
{
    Gdk::Cairo::set_source_rgba(cr, m_Color);
    cr->paint();

    return true;
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## 16.4 FontChooserDialog

The `FontChooserDialog` allows the user to choose a font. The `FontButton` opens a font chooser dialog when it is clicked.

[Reference](#)



### 16.4.1 Example




Figure 16.4: FontChooserDialog

#### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
```

```
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_font_button_font_set();
    void on_button_dialog_clicked();

    //Child widgets:
    Gtk::ButtonBox m_ButtonBox;
    Gtk::FontButton m_FontButton;
    Gtk::Button m_Button_Dialog;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

**File:** examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: m_ButtonBox(Gtk::ORIENTATION_VERTICAL),
  m_FontButton("Sans 10"),
  m_Button_Dialog("Choose Font")
{
    set_title("Gtk::FontChooserDialog example");

    add(m_ButtonBox);

    m_ButtonBox.pack_start(m_FontButton);
    m_FontButton.set_use_font(true);
    m_FontButton.set_use_size(true);
    m_FontButton.signal_font_set().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_font_button_font_set) );

    m_ButtonBox.pack_start(m_Button_Dialog);
    m_Button_Dialog.signal_clicked().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_button_dialog_clicked) );
    show_all_children();
}
```

```
ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_font_button_font_set()
{
    Glib::ustring font_name = m_FontButton.get_font_name();
    std::cout << "Font chosen: " << font_name << std::endl;
}

void ExampleWindow::on_button_dialog_clicked()
{
    Gtk::FontChooserDialog dialog("Please choose a font", *this);

    //Get the previously selected font name from the FontButton:
    dialog.set_font(m_FontButton.get_font_name());

    int result = dialog.run();

    //Handle the response:
    switch(result)
    {
        case Gtk::RESPONSE_OK:
        {
            Glib::ustring font_name = dialog.get_font();
            std::cout << "Font chosen: " << font_name << std::endl;
            m_FontButton.set_font_name(font_name);
            break;
        }
        case Gtk::RESPONSE_CANCEL:
        {
            std::cout << "Cancel clicked." << std::endl;
            break;
        }
        default:
        {
            std::cout << "Unexpected button clicked: " << result << std::endl;
            break;
        }
    }
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>
```

```
int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## 16.5 Non-modal AboutDialog

The `AboutDialog` offers a simple way to display information about a program, like its logo, name, copyright, website and license.

Most dialogs in this chapter are modal, that is, they freeze the rest of the application while they are shown. It's also possible to create a non-modal dialog, which does not freeze other windows in the application. The following example shows a non-modal `AboutDialog`. This is perhaps not the kind of dialog you would normally make non-modal, but non-modal dialogs can be useful in other cases. E.g. gedit's search-and-replace dialog is non-modal.

Reference

### 16.5.1 Example



Figure 16.5: AboutDialog

#### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_clicked();
};
```

```

void on_about_dialog_response(int response_id);

//Child widgets:
Gtk::Box m_VBox;
Gtk::Label m_Label;
Gtk::ButtonBox m_ButtonBox;
Gtk::Button m_Button;
Gtk::AboutDialog m_Dialog;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

File: `examplewindow.cc` (For use with `gtkmm 3`)

```

#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Label("The AboutDialog is non-modal. "
    "You can select parts of this text while the AboutDialog is shown."),
  m_ButtonBox(Gtk::ORIENTATION_VERTICAL),
  m_Button("Show AboutDialog")
{
  set_title("Gtk::AboutDialog example");

  add(m_VBox);

  m_VBox.pack_start(m_Label);
  m_Label.set_line_wrap(true);
  m_Label.set_selectable(true);

  m_VBox.pack_start(m_ButtonBox);
  m_ButtonBox.pack_start(m_Button);
  m_Button.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_button_clicked) );

  m_Dialog.set_transient_for(*this);

  m_Dialog.set_logo(Gdk::Pixbuf::create_from_resource("/about/gtkmm_logo. ↵
    gif", -1, 40, true));
  m_Dialog.set_program_name("Example application");
  m_Dialog.set_version("1.0.0");
  m_Dialog.set_copyright("Murray Cumming");
  m_Dialog.set_comments("This is just an example application.");
  m_Dialog.set_license("LGPL");

  m_Dialog.set_website("http://www.gtkmm.org");

```

```
m_Dialog.set_website_label("gtkmm website");

std::vector<Glib::ustring> list_authors;
list_authors.push_back("Murray Cumming");
list_authors.push_back("Somebody Else");
list_authors.push_back("AN Other");
m_Dialog.set_authors(list_authors);

m_Dialog.signal_response().connect(
    sigc::mem_fun(*this, &ExampleWindow::on_about_dialog_response) );

show_all_children();

// The widget must be realized and mapped before grab_focus() is called.
// That's why it's called after show_all_children().
m_Button.grab_focus();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_about_dialog_response(int response_id)
{
    std::cout << response_id
        << ", close=" << Gtk::RESPONSE_CLOSE
        << ", cancel=" << Gtk::RESPONSE_CANCEL
        << ", delete_event=" << Gtk::RESPONSE_DELETE_EVENT
        << std::endl;

    switch (response_id)
    {
    case Gtk::RESPONSE_CLOSE:
    case Gtk::RESPONSE_CANCEL:
    case Gtk::RESPONSE_DELETE_EVENT:
        m_Dialog.hide();
        break;
    default:
        std::cout << "Unexpected response!" << std::endl;
        break;
    }
}

void ExampleWindow::on_button_clicked()
{
    m_Dialog.show();
}
```

---

```
//Bring it to the front, in case it was already shown:  
m_Dialog.present();  
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"  
#include <gtkmm/application.h>  
  
int main(int argc, char *argv[])  
{  
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");  
  
    ExampleWindow window;  
  
    //Shows the window and returns when it is closed.  
    return app->run(window);  
}
```

**File: aboutdialog.gresource.xml (For use with gtkmm 3)**

```
<?xml version="1.0" encoding="UTF-8"?>  
<gresources>  
    <gresource prefix="/about">  
        <file>gtkmm_logo.gif</file>  
    </gresource>  
</gresources>
```



## Chapter 17

# The Drawing Area Widget

The `DrawingArea` widget is a blank window that gives you the freedom to create any graphic you desire. Along with that freedom comes the responsibility to handle draw signals on the widget. When a widget is first shown, or when it is covered and then uncovered again it needs to redraw itself. Most widgets have code to do this, but the `DrawingArea` does not, allowing you to write your own draw signal handler to determine how the contents of the widget will be drawn. This is most often done by overriding the virtual `on_draw()` member function.

GTK+ uses the **Cairo** drawing API. With `gtkmm`, you may use the **cairomm** C++ API for cairo.

You can draw very sophisticated shapes using Cairo, but the methods to do so are quite basic. Cairo provides methods for drawing straight lines, curved lines, and arcs (including circles). These basic shapes can be combined to create more complex shapes and paths which can be filled with solid colors, gradients, patterns, and other things. In addition, Cairo can perform complex transformations, do compositing of images, and render antialiased text.

---

### Cairo and Pango

Although Cairo can render text, it's not meant to be a replacement for Pango. Pango is a better choice if you need to perform more advanced text rendering such as wrapping or ellipsizing text. Drawing text with Cairo should only be done if the text is part of a graphic.

---

In this section of the tutorial, we'll cover the basic Cairo drawing model, describe each of the basic drawing elements in some detail (with examples), and then present a simple application that uses Cairo to draw a custom clock widget.

---

## 17.1 The Cairo Drawing Model

The basic concept of drawing in Cairo involves defining 'invisible' paths and then stroking or filling them to make them visible.

To do any drawing in gtkmm with Cairo, you must first create a `Cairo::Context` object. This class holds all of the graphics state parameters that describe how drawing is to be done. This includes information such as line width, color, the surface to draw to, and many other things. This allows the actual drawing functions to take fewer arguments to simplify the interface. In gtkmm, a `Cairo::Context` is created by calling the `Gdk::Window::create_cairo_context()` function. Since Cairo contexts are reference-counted objects, this function returns a `Cairo::RefPtr<Cairo::Context>` object.

The following example shows how to set up a Cairo context with a foreground color of red and a width of 2. Any drawing functions that use this context will use these settings.

```
Gtk::DrawingArea myArea;  
Cairo::RefPtr<Cairo::Context> myContext = myArea.get_window()-> ↵  
    create_cairo_context();  
myContext->set_source_rgb(1.0, 0.0, 0.0);  
myContext->set_line_width(2.0);
```

Each `Cairo::Context` is associated with a particular `Gdk::Window`, so the first line of the above example creates a `Gtk::DrawingArea` widget and the second line uses its associated `Gdk::Window` to create a `Cairo::Context` object. The final two lines change the graphics state of the context.

There are a number of graphics state variables that can be set for a Cairo context. The most common context attributes are color (using `set_source_rgb()` or `set_source_rgba()` for translucent colors), line width (using `set_line_width()`), line dash pattern (using `set_dash()`), line cap style (using `set_line_cap()`), and line join style (using `set_line_join()`), and font styles (using `set_font_size()`, `set_font_face()` and others). There are many other settings as well, such as transformation matrices, fill rules, whether to perform antialiasing, and others. For further information, see the [cairomm](#) API documentation.

The current state of a `Cairo::Context` can be saved to an internal stack of saved states and later be restored to the state it was in when you saved it. To do this, use the `save()` method and the `restore()` method. This can be useful if you need to temporarily change the line width and color (or any other graphics setting) in order to draw something and then return to the previous settings. In this situation, you could call `Cairo::Context::save()`, change the graphics settings, draw the lines, and then call `Cairo::Context::restore()` to restore the original graphics state. Multiple calls to `save()` and `restore()` can be nested; each call to `restore()` restores the state from the matching paired `save()`.

---

---

**Tip**

It is good practice to put all modifications to the graphics state *between* `save()`/`restore()` function calls. For example, if you have a function that takes a `Cairo::Context` reference as an argument, you might implement it as follows:

```
void doSomething(const Cairo::RefPtr<Cairo::Context>& context, int x)
{
    context->save();
    // change graphics state
    // perform drawing operations
    context->restore();
}
```

---

The virtual `on_draw()` method provides a Cairo context that you shall use for drawing in the `Gtk::DrawingArea` widget. It is not necessary to save and restore this Cairo context in `on_draw()`.

## 17.2 Drawing Straight Lines

Now that we understand the basics of the Cairo graphics library, we're almost ready to start drawing. We'll start with the simplest of drawing elements: the straight line. But first you need to know a little bit about Cairo's coordinate system. The origin of the Cairo coordinate system is located in the upper-left corner of the window with positive x values to the right and positive y values going down.

---

**Tip**

Since the Cairo graphics library was written with support for multiple output targets (the X window system, PNG images, OpenGL, etc), there is a distinction between user-space and device-space coordinates. The mapping between these two coordinate systems defaults to one-to-one so that integer values map roughly to pixels on the screen, but this setting can be adjusted if desired. Sometimes it may be useful to scale the coordinates so that the full width and height of a window both range from 0 to 1 (the 'unit square') or some other mapping that works for your application. This can be done with the `Cairo::Context::scale()` function.

---

### 17.2.1 Example

In this example, we'll construct a small but fully functional gtkmm program and draw some lines into the window. The lines are drawn by creating a path and then stroking it. A path is created using the functions `Cairo::Context::move_to()` and `Cairo::Context::line_to()`. The function `move_to()` is similar to the act of lifting your pen off of the paper and placing it somewhere else -- no

---

line is drawn between the point you were at and the point you moved to. To draw a line between two points, use the `line_to()` function.

After you've finished creating your path, you still haven't drawn anything visible yet. To make the path visible, you must use the function `stroke()` which will stroke the current path with the line width and style specified in your `Cairo::Context` object. After stroking, the current path will be cleared so that you can start on your next path.

---

**Tip**

Many Cairo drawing functions have a `_preserve()` variant. Normally drawing functions such as `clip()`, `fill()`, or `stroke()` will clear the current path. If you use the `_preserve()` variant, the current path will be retained so that you can use the same path with the next drawing function.

---




Figure 17.1: Drawing Area - Lines

### Source Code

File: `myarea.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_MYAREA_H
#define GTKMM_EXAMPLE_MYAREA_H
```

```
#include <gtkmm/drawingarea.h>

class MyArea : public Gtk::DrawingArea
{
public:
    MyArea();
    virtual ~MyArea();

protected:
    //Override default signal handler:
    bool on_draw(const Cairo::RefPtr<Cairo::Context>& cr) override;
};

#endif // GTKMM_EXAMPLE_MYAREA_H
```

**File: main.cc (For use with gtkmm 3)**

```
#include "myarea.h"
#include <gtkmm/application.h>
#include <gtkmm/window.h>

int main(int argc, char** argv)
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    Gtk::Window win;
    win.set_title("DrawingArea");

    MyArea area;
    win.add(area);
    area.show();

    return app->run(win);
}
```

**File: myarea.cc (For use with gtkmm 3)**

```
#include "myarea.h"
#include <cairomm/context.h>

MyArea::MyArea()
{
}

MyArea::~MyArea()
{
}
```

```
bool MyArea::on_draw(const Cairo::RefPtr<Cairo::Context>& cr)
{
    Gtk::Allocation allocation = get_allocation();
    const int width = allocation.get_width();
    const int height = allocation.get_height();

    // coordinates for the center of the window
    int xc, yc;
    xc = width / 2;
    yc = height / 2;

    cr->set_line_width(10.0);

    // draw red lines out from the center of the window
    cr->set_source_rgb(0.8, 0.0, 0.0);
    cr->move_to(0, 0);
    cr->line_to(xc, yc);
    cr->line_to(0, height);
    cr->move_to(xc, yc);
    cr->line_to(width, yc);
    cr->stroke();

    return true;
}
```

This program contains a single class, `MyArea`, which is a subclass of `Gtk::DrawingArea` and contains an `on_draw()` member function. This function is called whenever the image in the drawing area needs to be redrawn. It is passed a `Cairo::RefPtr` pointer to a `Cairo::Context` that we use for the drawing. The actual drawing code sets the color we want to use for drawing by using `set_source_rgb()` which takes arguments defining the Red, Green, and Blue components of the desired color (valid values are between 0 and 1). After setting the color, we created a new path using the functions `move_to()` and `line_to()`, and then stroked this path with `stroke()`.

---

#### Drawing with relative coordinates

In the example above we drew everything using absolute coordinates. You can also draw using relative coordinates. For a straight line, this is done with the function `Cairo::Context::rel_line_to()`.

---

### 17.2.2 Line styles

In addition to drawing basic straight lines, there are a number of things that you can customize about a line. You've already seen examples of setting a line's color and width, but there are others as well.

---

If you've drawn a series of lines that form a path, you may want them to join together in a certain way. Cairo offers three different ways to join lines together: Miter, Bevel, and Round. These are shown below:



Figure 17.2: Different join types in Cairo

The line join style is set using the function `Cairo::Context::set_line_join()`.

Line ends can have different styles as well. The default style is for the line to start and stop exactly at the destination points of the line. This is called a Butt cap. The other options are Round (uses a round ending, with the center of the circle at the end point) or Square (uses a squared ending, with the center of the square at the end point). This setting is set using the function `Cairo::Context::set_line_cap()`.

There are other things you can customize as well, including creating dashed lines and other things. For more information, see the Cairo API documentation.

### 17.2.3 Drawing thin lines

If you try to draw one pixel wide lines, you may notice that the line sometimes comes up blurred and wider than it ought to be. This happens because Cairo will try to draw from the selected position, to both sides (half to each), so if you're positioned right on the intersection of the pixels, and want a one pixel wide line, Cairo will try to use half of each adjacent pixel, which isn't possible (a pixel is the smallest unit possible). This happens when the width of the line is an odd number of pixels (not just one pixel).

The trick is to position in the middle of the pixel where you want the line to be drawn, and thus guaranteeing you get the desired results. See [Cairo FAQ](#).




Figure 17.3: Drawing Area - Thin Lines

### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm/window.h>
#include <gtkmm/grid.h>
#include <gtkmm/checkbutton.h>
#include "myarea.h"

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_toggled();

private:
    Gtk::Grid m_Container;
    MyArea m_Area_Lines;
    Gtk::CheckButton m_Button_FixLines;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: `myarea.h` (For use with gtkmm 3)

---



```
#ifndef GTKMM_EXAMPLE_MYAREA_H
#define GTKMM_EXAMPLE_MYAREA_H

#include <gtkmm/drawingarea.h>

class MyArea : public Gtk::DrawingArea
{
public:
    MyArea();
    virtual ~MyArea();

    void fix_lines(bool fix = true);
    void force_redraw();

protected:
    //Override default signal handler:
    bool on_draw(const Cairo::RefPtr<Cairo::Context>& cr) override;

private:
    double m_fix;
};

#endif // GTKMM_EXAMPLE_MYAREA_H
```

**File:** examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_Button_FixLines("Fix lines")
{
    set_title("Thin lines example");

    m_Container.set_orientation(Gtk::ORIENTATION_HORIZONTAL);

    m_Container.add(m_Area_Lines);
    m_Container.add(m_Button_FixLines);

    add(m_Container);

    m_Button_FixLines.signal_toggled().connect(
        sigc::mem_fun(*this, &ExampleWindow::on_button_toggled));

    // Synchronize the drawing in m_Area_Lines with the state of the toggle ↔
    button.
    on_button_toggled();

    show_all_children();
}
```

```
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_toggled()
{
    m_Area_Lines.fix_lines(m_Button_FixLines.get_active());
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char* argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

**File: myarea.cc (For use with gtkmm 3)**

```
#include "myarea.h"

MyArea::MyArea()
: m_fix (0)
{
    set_size_request (200, 100);
}

MyArea::~MyArea()
{
}

bool MyArea::on_draw(const Cairo::RefPtr<Cairo::Context>& cr)
{
    Gtk::Allocation allocation = get_allocation();
    const int width = allocation.get_width();
    const int height = allocation.get_height();

    cr->set_line_width(1.0);
```

```
// draw one line, every two pixels
// without the 'fix', you won't notice any space between the lines,
// since each one will occupy two pixels (width)
for (int i = 0; i < width; i += 2)
{
    cr->move_to(i + m_fix, 0);
    cr->line_to(i + m_fix, height);
}

cr->stroke();

return true;
}

// Toogle between both values (0 or 0.5)
void MyArea::fix_lines(bool fix)
{
    // to get the width right, we have to draw in the middle of the pixel
    m_fix = fix ? 0.5 : 0.0;

    force_redraw();
}

// force the redraw of the image
void MyArea::force_redraw()
{
    auto win = get_window();
    if (win)
    {
        Gdk::Rectangle r(0, 0, get_allocation().get_width(), get_allocation().get_height());
        win->invalidate_rect(r, false);
    }
}
```

## 17.3 Drawing Curved Lines

In addition to drawing straight lines Cairo allows you to easily draw curved lines (technically a cubic Bézier spline) using the `Cairo::Context::curve_to()` and `Cairo::Context::rel_curve_to()` functions. These functions take coordinates for a destination point as well as coordinates for two 'control' points. This is best explained using an example, so let's dive in.

---

### 17.3.1 Example

This simple application draws a curve with Cairo and displays the control points for each end of the curve.




Figure 17.4: Drawing Area - Lines

#### Source Code

File: myarea.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_MYAREA_H
#define GTKMM_EXAMPLE_MYAREA_H

#include <gtkmm/drawingarea.h>

class MyArea : public Gtk::DrawingArea
{
public:
    MyArea();
    virtual ~MyArea();

protected:
    //Override default signal handler:
    bool on_draw(const Cairo::RefPtr<Cairo::Context>& cr) override;
};
```

```
#endif // GTKMM_EXAMPLE_MYAREA_H
```

**File: main.cc (For use with gtkmm 3)**

```
#include "myarea.h"
#include <gtkmm/application.h>
#include <gtkmm/window.h>

int main(int argc, char** argv)
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    Gtk::Window win;
    win.set_title("DrawingArea");

    MyArea area;
    win.add(area);
    area.show();

    return app->run(win);
}
```

**File: myarea.cc (For use with gtkmm 3)**

```
#include "myarea.h"
#include <cairomm/context.h>

MyArea::MyArea()
{
}

MyArea::~MyArea()
{
}

bool MyArea::on_draw(const Cairo::RefPtr<Cairo::Context>& cr)
{
    Gtk::Allocation allocation = get_allocation();
    const int width = allocation.get_width();
    const int height = allocation.get_height();

    double x0=0.1, y0=0.5, // start point
           x1=0.4, y1=0.9, // control point #1
           x2=0.6, y2=0.1, // control point #2
           x3=0.9, y3=0.5; // end point

    // scale to unit square (0 to 1 width and height)
```

```
cr->scale(width, height);

cr->set_line_width(0.05);
// draw curve
cr->move_to(x0, y0);
cr->curve_to(x1, y1, x2, y2, x3, y3);
cr->stroke();
// show control points
cr->set_source_rgba(1, 0.2, 0.2, 0.6);
cr->move_to(x0, y0);
cr->line_to (x1, y1);
cr->move_to(x2, y2);
cr->line_to (x3, y3);
cr->stroke();

return true;
}
```

The only difference between this example and the straight line example is in the `on_draw()` function, but there are a few new concepts and functions introduced here, so let's examine them briefly.

We make a call to `Cairo::Context::scale()`, passing in the width and height of the drawing area. This scales the user-space coordinate system such that the width and height of the widget are both equal to 1.0 'units'. There's no particular reason to scale the coordinate system in this case, but sometimes it can make drawing operations easier.

The call to `Cairo::Context::curve_to()` should be fairly self-explanatory. The first pair of coordinates define the control point for the beginning of the curve. The second set of coordinates define the control point for the end of the curve, and the last set of coordinates define the destination point. To make the concept of control points a bit easier to visualize, a line has been drawn from each control point to the end-point on the curve that it is associated with. Note that these control point lines are both translucent. This is achieved with a variant of `set_source_rgb()` called `set_source_rgba()`. This function takes a fourth argument specifying the alpha value of the color (valid values are between 0 and 1).

## 17.4 Drawing Arcs and Circles

With Cairo, the same function is used to draw arcs, circles, or ellipses: `Cairo::Context::arc()`. This function takes five arguments. The first two are the coordinates of the center point of the arc, the third argument is the radius of the arc, and the final two arguments define the start and end angle of the arc. All angles are defined in radians, so drawing a circle is the same as drawing an arc from 0 to  $2 * \text{M\_PI}$  radians. An angle of 0 is in the direction of the positive X axis (in user-space). An angle of  $\text{M\_PI}/2$  radians (90 degrees) is in the direction of the positive Y axis (in user-space). Angles increase in the direction from the positive X axis toward the positive Y axis. So with the default transformation matrix, angles increase in a clockwise direction. (Remember that the positive Y axis points downwards.)

---

To draw an ellipse, you can scale the current transformation matrix by different amounts in the X and Y directions. For example, to draw an ellipse with center at  $x, y$  and size  $width, height$ :

```
context->save();  
context->translate(x, y);  
context->scale(width / 2.0, height / 2.0);  
context->arc(0.0, 0.0, 1.0, 0.0, 2 * M_PI);  
context->restore();
```

### 17.4.1 Example

Here's an example of a simple program that draws an arc, a circle and an ellipse into a drawing area.




Figure 17.5: Drawing Area - Arcs

#### Source Code

File: myarea.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_MYAREA_H  
#define GTKMM_EXAMPLE_MYAREA_H  
  
#include <gtkmm/drawingarea.h>
```

```
class MyArea : public Gtk::DrawingArea
{
public:
    MyArea();
    virtual ~MyArea();

protected:
    //Override default signal handler:
    bool on_draw(const Cairo::RefPtr<Cairo::Context>& cr) override;
};

#endif // GTKMM_EXAMPLE_MYAREA_H
```

**File: main.cc (For use with gtkmm 3)**

```
#include "myarea.h"
#include <gtkmm/application.h>
#include <gtkmm/window.h>

int main(int argc, char** argv)
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    Gtk::Window win;
    win.set_title("DrawingArea");

    MyArea area;
    win.add(area);
    area.show();

    return app->run(win);
}
```

**File: myarea.cc (For use with gtkmm 3)**

```
#include "myarea.h"
#include <caiomm/context.h>
#include <cmath>

MyArea::MyArea()
{
}

MyArea::~MyArea()
{
}
```



[illegible]

```
cr->arc(0.0, 0.0, 1.0, 0.0, 2 * M_PI); // 'circle' centered at (0, 0)
                                         // with 'radius' of 1.0

cr->set_source_rgba(0.8, 0.0, 0.0, 0.7);
cr->fill_preserve();
cr->restore(); // back to opaque black
cr->stroke();

return true;
}
```

There are a couple of things to note about this example code. Again, the only real difference between this example and the previous ones is the `on_draw()` function, so we'll limit our focus to that function. In addition, the first part of the function is nearly identical to the previous examples, so we'll skip that portion.

Note that in this case, we've expressed nearly everything in terms of the height and width of the window, including the width of the lines. Because of this, when you resize the window, everything scales with the window. Also note that there are three drawing sections in the function and each is wrapped with a `save()/restore()` pair so that we're back at a known state after each drawing.

The section for drawing an arc introduces one new function, `close_path()`. This function will in effect draw a straight line from the current point back to the first point in the path. There is a significant difference between calling `close_path()` and manually drawing a line back to the starting point, however. If you use `close_path()`, the lines will be nicely joined together. If you use `line_to()` instead, the lines will end at the same point, but Cairo won't do any special joining.

---

**Drawing counter-clockwise**

The function `Cairo::Context::arc_negative()` is exactly the same as `Cairo::Context::arc()` but the angles go the opposite direction.

---

## 17.5 Drawing Text

### 17.5.1 Drawing Text with Pango

Text is drawn via Pango Layouts. The easiest way to create a `Pango::Layout` is to use `Gtk::Widget::create_pango_layout()`. Once created, the layout can be manipulated in various ways, including changing the text, font, etc. Finally, the layout can be rendered using the `Pango::Layout::show_in_cairo_context()` method.

---

### 17.5.2 Example

Here is an example of a program that draws some text, some of it upside-down. The Printing chapter contains another [example](#) of drawing text.



Figure 17.6: Drawing Area - Text

#### Source Code

File: myarea.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_MYAREA_H
#define GTKMM_EXAMPLE_MYAREA_H

#include <gtkmm/drawingarea.h>

class MyArea : public Gtk::DrawingArea
{
public:
    MyArea();
    virtual ~MyArea();

protected:
    //Override default signal handler:
    bool on_draw(const Cairo::RefPtr<Cairo::Context>& cr) override;
```

```
private:
    void draw_rectangle(const Cairo::RefPtr<Cairo::Context>& cr, int width, ↵
        int height);
    void draw_text(const Cairo::RefPtr<Cairo::Context>& cr, int ↵
        rectangle_width, int rectangle_height);

};

#endif // GTKMM_EXAMPLE_MYAREA_H
```

File: main.cc (For use with gtkmm 3)

```
#include "myarea.h"
#include <gtkmm/application.h>
#include <gtkmm/window.h>

int main(int argc, char* argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    Gtk::Window window;
    window.set_title("Drawing text example");

    MyArea area;
    window.add(area);
    area.show();

    return app->run(window);
}
```

File: myarea.cc (For use with gtkmm 3)

```
#include "myarea.h"

MyArea::MyArea()
{
}

MyArea::~MyArea()
{
}

bool MyArea::on_draw(const Cairo::RefPtr<Cairo::Context>& cr)
{
    Gtk::Allocation allocation = get_allocation();
    const int width = allocation.get_width();
    const int height = allocation.get_height();
```

```
const int rectangle_width = width;
const int rectangle_height = height / 2;

// Draw a black rectangle
cr->set_source_rgb(0.0, 0.0, 0.0);
draw_rectangle(cr, rectangle_width, rectangle_height);

// and some white text
cr->set_source_rgb(1.0, 1.0, 1.0);
draw_text(cr, rectangle_width, rectangle_height);

// flip the image vertically
// see http://www.cairographics.org/documentation/caiomm/reference/ ↵
// classCairo_1_1Matrix.html
// the -1 corresponds to the yy part (the flipping part)
// the height part is a translation (we could have just called cr-> ↵
// translate(0, height) instead)
// it's height and not height / 2, since we want this to be on the ↵
// second part of our drawing
// (otherwise, it would draw over the previous part)
Cairo::Matrix matrix(1.0, 0.0, 0.0, -1.0, 0.0, height);

// apply the matrix
cr->transform(matrix);

// white rectangle
cr->set_source_rgb(1.0, 1.0, 1.0);
draw_rectangle(cr, rectangle_width, rectangle_height);

// black text
cr->set_source_rgb(0.0, 0.0, 0.0);
draw_text(cr, rectangle_width, rectangle_height);

return true;
}

void MyArea::draw_rectangle(const Cairo::RefPtr<Cairo::Context>& cr,
                           int width, int height)
{
    cr->rectangle(0, 0, width, height);
    cr->fill();
}

void MyArea::draw_text(const Cairo::RefPtr<Cairo::Context>& cr,
                      int rectangle_width, int rectangle_height)
{

```

---

```
// http://developer.gnome.org/pangomm/unstable/ ↵
    classPango_1_1FontDescription.html
Pango::FontDescription font;

font.set_family("Monospace");
font.set_weight(Pango::WEIGHT_BOLD);

// http://developer.gnome.org/pangomm/unstable/classPango_1_1Layout.html
auto layout = create_pango_layout("Hi there!");

layout->set_font_description(font);

int text_width;
int text_height;

//get the text dimensions (it updates the variables -- by reference)
layout->get_pixel_size(text_width, text_height);

// Position the text in the middle
cr->move_to((rectangle_width-text_width)/2, (rectangle_height- ↵
    text_height)/2);

layout->show_in_cairo_context(cr);
}
```

## 17.6 Drawing Images

There is a method for drawing from a `Gdk::Pixbuf` to a `Cairo::Context`. A `Gdk::Pixbuf` buffer is a useful wrapper around a collection of pixels, which can be read from files, and manipulated in various ways.

Probably the most common way of creating `Gdk::Pixbufs` is to use `Gdk::Pixbuf::create_from_file()` or `Gdk::Pixbuf::create_from_resource()`, which can read an image file, such as a png file into a `pixbuf` ready for rendering.

The `Gdk::Pixbuf` can be rendered by setting it as the source pattern of the Cairo context with `Gdk::Cairo::set_source_pixbuf()`. Then draw the image with either `Cairo::Context::paint()` (to draw the whole image), or `Cairo::Context::rectangle()` and `Cairo::Context::fill()` (to fill the specified rectangle). `set_source_pixbuf()` is not a member of `Cairo::Context`. It takes a `Cairo::Context` as its first parameter.

Here is a small bit of code to tie it all together: (Note that usually you wouldn't load the image every time in the draw signal handler! It's just shown here to keep it all together.)

```
bool MyArea::on_draw(const Cairo::RefPtr<Cairo::Context>& cr)
{
```

```
Glib::RefPtr<Gdk::Pixbuf> image = Gdk::Pixbuf::create_from_file("myimage ←  
    .png");  
// Draw the image at 110, 90, except for the outermost 10 pixels.  
Gdk::Cairo::set_source_pixbuf(cr, image, 100, 80);  
cr->rectangle(110, 90, image->get_width()-20, image->get_height()-20);  
cr->fill();  
return true;  
}
```

### 17.6.1 Example

Here is an example of a simple program that draws an image. The program loads the image from a resource file. See the [Gio::Resource and glib-compile-resources](#) section. Use `glib-compile-resources` to compile the resources into a C source file that can be compiled and linked with the C++ code. E.g.

```
$ glib-compile-resources --target=resources.c --generate-source image. ←  
    gresource.xml
```




Figure 17.7: Drawing Area - Image

#### Source Code

File: `myarea.h` (For use with gtkmm 3)

---

```
#ifndef GTKMM_EXAMPLE_MYAREA_H
#define GTKMM_EXAMPLE_MYAREA_H

#include <gtkmm/drawingarea.h>
#include <gdkmm/pixbuf.h>

class MyArea : public Gtk::DrawingArea
{
public:
    MyArea();
    virtual ~MyArea();

protected:
    //Override default signal handler:
    bool on_draw(const Cairo::RefPtr<Cairo::Context>& cr) override;

    Glib::RefPtr<Gdk::Pixbuf> m_image;
};

#endif // GTKMM_EXAMPLE_MYAREA_H
```

**File: main.cc (For use with gtkmm 3)**

```
#include "myarea.h"
#include <gtkmm/application.h>
#include <gtkmm/window.h>

int main(int argc, char** argv)
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    Gtk::Window win;
    win.set_title("DrawingArea");
    win.set_default_size(300, 200);

    MyArea area;
    win.add(area);
    area.show();

    return app->run(win);
}
```

**File: myarea.cc (For use with gtkmm 3)**

```
#include "myarea.h"
#include <cairomm/context.h>
#include <giomm/resource.h>
```

---



```
#include <gdkmm/general.h> // set_source_pixbuf()
#include <glibmm/fileutils.h>
#include <iostream>

MyArea::MyArea()
{
    try
    {
        // The fractal image has been created by the XaoS program.
        // http://xaos.sourceforge.net
        m_image = Gdk::Pixbuf::create_from_resource("/image/fractal_image.png ↵
        ");
    }
    catch(const Gio::ResourceError& ex)
    {
        std::cerr << "ResourceError: " << ex.what() << std::endl;
    }
    catch(const Gdk::PixbufError& ex)
    {
        std::cerr << "PixbufError: " << ex.what() << std::endl;
    }

    // Show at least a quarter of the image.
    if (m_image)
        set_size_request(m_image->get_width()/2, m_image->get_height()/2);
}

MyArea::~MyArea()
{
}

bool MyArea::on_draw(const Cairo::RefPtr<Cairo::Context>& cr)
{
    if (!m_image)
        return false;

    Gtk::Allocation allocation = get_allocation();
    const int width = allocation.get_width();
    const int height = allocation.get_height();

    // Draw the image in the middle of the drawing area, or (if the image is
    // larger than the drawing area) draw the middle part of the image.
    Gdk::Cairo::set_source_pixbuf(cr, m_image,
        (width - m_image->get_width())/2, (height - m_image->get_height())/2);
    cr->paint();

    return true;
}
```

---


```
}
```

File: `image.gresource.xml` (For use with gtkmm 3)

```
<?xml version="1.0" encoding="UTF-8"?>
<gresources>
  <gresource prefix="/image">
    <file>fractal_image.png</file>
  </gresource>
</gresources>
```

## 17.7 Example Application: Creating a Clock with Cairo

Now that we've covered the basics of drawing with Cairo, let's try to put it all together and create a simple application that actually does something. The following example uses Cairo to create a custom `Clock` widget. The clock has a second hand, a minute hand, and an hour hand, and updates itself every second.



### Source Code

File: `clock.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_CLOCK_H
#define GTKMM_EXAMPLE_CLOCK_H
```

```
#include <gtkmm/drawingarea.h>

class Clock : public Gtk::DrawingArea
{
public:
    Clock();
    virtual ~Clock();

protected:
    //Override default signal handler:
    bool on_draw(const Cairo::RefPtr<Cairo::Context>& cr) override;

    bool on_timeout();

    double m_radius;
    double m_line_width;
};

#endif // GTKMM_EXAMPLE_CLOCK_H
```

**File: clock.cc (For use with gtkmm 3)**

```
#include <ctime>
#include <cmath>
#include <cairomm/context.h>
#include <glibmm/main.h>
#include "clock.h"

Clock::Clock()
: m_radius(0.42), m_line_width(0.05)
{
    Glib::signal_timeout().connect( sigc::mem_fun(*this, &Clock::on_timeout) ↵
        , 1000 );
}

Clock::~~Clock()
{
}

bool Clock::on_draw(const Cairo::RefPtr<Cairo::Context>& cr)
{
    Gtk::Allocation allocation = get_allocation();
    const int width = allocation.get_width();
    const int height = allocation.get_height();

    // scale to unit square and translate (0, 0) to be (0.5, 0.5), i.e.
```

```
// the center of the window
cr->scale(width, height);
cr->translate(0.5, 0.5);
cr->set_line_width(m_line_width);

cr->save();
cr->set_source_rgba(0.337, 0.612, 0.117, 0.9); // green
cr->paint();
cr->restore();
cr->arc(0, 0, m_radius, 0, 2 * M_PI);
cr->save();
cr->set_source_rgba(1.0, 1.0, 1.0, 0.8);
cr->fill_preserve();
cr->restore();
cr->stroke_preserve();
cr->clip();

//clock ticks
for (int i = 0; i < 12; i++)
{
    double inset = 0.05;

    cr->save();
    cr->set_line_cap(Cairo::LINE_CAP_ROUND);

    if(i % 3 != 0)
    {
        inset *= 0.8;
        cr->set_line_width(0.03);
    }

    cr->move_to(
        (m_radius - inset) * cos (i * M_PI / 6),
        (m_radius - inset) * sin (i * M_PI / 6));
    cr->line_to (
        m_radius * cos (i * M_PI / 6),
        m_radius * sin (i * M_PI / 6));
    cr->stroke();
    cr->restore(); /* stack-pen-size */
}

// store the current time
time_t rawtime;
time(&rawtime);
struct tm * timeinfo = localtime (&rawtime);

// compute the angles of the indicators of our clock
```

---

```
double minutes = timeinfo->tm_min * M_PI / 30;
double hours = timeinfo->tm_hour * M_PI / 6;
double seconds = timeinfo->tm_sec * M_PI / 30;

cr->save();
cr->set_line_cap(Cairo::LINE_CAP_ROUND);

// draw the seconds hand
cr->save();
cr->set_line_width(m_line_width / 3);
cr->set_source_rgba(0.7, 0.7, 0.7, 0.8); // gray
cr->move_to(0, 0);
cr->line_to(sin(seconds) * (m_radius * 0.9),
           -cos(seconds) * (m_radius * 0.9));
cr->stroke();
cr->restore();

// draw the minutes hand
cr->set_source_rgba(0.117, 0.337, 0.612, 0.9); // blue
cr->move_to(0, 0);
cr->line_to(sin(minutes + seconds / 60) * (m_radius * 0.8),
           -cos(minutes + seconds / 60) * (m_radius * 0.8));
cr->stroke();

// draw the hours hand
cr->set_source_rgba(0.337, 0.612, 0.117, 0.9); // green
cr->move_to(0, 0);
cr->line_to(sin(hours + minutes / 12.0) * (m_radius * 0.5),
           -cos(hours + minutes / 12.0) * (m_radius * 0.5));
cr->stroke();
cr->restore();

// draw a little dot in the middle
cr->arc(0, 0, m_line_width / 3.0, 0, 2 * M_PI);
cr->fill();

return true;
}

bool Clock::on_timeout()
{
    // force our program to redraw the entire clock.
    auto win = get_window();
    if (win)
    {
        Gdk::Rectangle r(0, 0, get_allocation().get_width(),
```

```
        get_allocation().get_height());
    win->invalidate_rect(r, false);
}
return true;
}
```

File: main.cc (For use with gtkmm 3)

```
#include "clock.h"
#include <gtkmm/application.h>
#include <gtkmm/window.h>

int main(int argc, char** argv)
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    Gtk::Window win;
    win.set_title("Cairomm Clock");

    Clock c;
    win.add(c);
    c.show();

    return app->run(win);
}
```

As before, almost all of the interesting stuff is done in the draw signal handler `on_draw()`. Before we dig into the draw signal handler, notice that the constructor for the `Clock` widget connects a handler function `on_timeout()` to a timer with a timeout period of 1000 milliseconds (1 second). This means that `on_timeout()` will get called once per second. The sole responsibility of this function is to invalidate the window so that gtkmm will be forced to redraw it.

Now let's take a look at the code that performs the actual drawing. The first section of `on_draw()` should be pretty familiar by now. This example again scales the coordinate system to be a unit square so that it's easier to draw the clock as a percentage of window size so that it will automatically scale when the window size is adjusted. Furthermore, the coordinate system is scaled over and down so that the (0, 0) coordinate is in the very center of the window.

The function `Cairo::Context::paint()` is used here to set the background color of the window. This function takes no arguments and fills the current surface (or the clipped portion of the surface) with the source color currently active. After setting the background color of the window, we draw a circle for the clock outline, fill it with white, and then stroke the outline in black. Notice that both of these actions use the `_preserve` variant to preserve the current path, and then this same path is clipped to make sure that our next lines don't go outside the outline of the clock.

After drawing the outline, we go around the clock and draw ticks for every hour, with a larger tick at 12, 3, 6, and 9. Now we're finally ready to implement the time-keeping functionality of the clock, which

---

simply involves getting the current values for hours, minutes and seconds, and drawing the hands at the correct angles.

## Chapter 18

# Drag and Drop

`Gtk::Widget` has several methods and signals which are prefixed with "drag\_". These are used for Drag and Drop.

### 18.1 Sources and Destinations

Things are dragged from `sources` to be dropped on `destinations`. Each source and destination has information about the data formats that it can send or receive, provided by `Gtk::TargetEntry` items. A drop destination will only accept a dragged item if they both share a compatible `Gtk::TargetEntry` item. Appropriate signals will then be emitted, telling the signal handlers which `Gtk::TargetEntry` was used.

`Gtk::TargetEntry` objects contain this information:

- `target`: A name, such as "STRING"
- `info`: An identifier which will be sent to your signals to tell you which `TargetEntry` was used.
- `flags`: Used only for drag and drop, this specifies whether the data may be dragged to other widgets and applications, or only to the same ones.

### 18.2 Methods

Widgets can be identified as sources or destinations using these `Gtk::Widget` methods:

```
void drag_source_set(const std::vector<Gtk::TargetEntry>& targets,  
                    Gdk::ModifierType start_button_mask, Gdk::DragAction actions);
```

---



- `targets` is a vector of `Gtk::TargetEntry` elements.
- `start_button_mask` is an ORed combination of values, which specify which modifier key or mouse button must be pressed to start the drag.
- `actions` is an ORed combination of values, which specified which Drag and Drop operations will be possible from this source - for instance, copy, move, or link. The user can choose between the actions by using modifier keys, such as **Shift** to change from copy to move, and this will be shown by a different cursor.

```
void drag_dest_set(const std::vector<Gtk::TargetEntry>& targets,  
                  Gtk::DestDefaults flags, Gdk::DragAction actions);
```

- `flags` is an ORed combination of values which indicates how the widget will respond visually to Drag and Drop items.
- `actions` indicates the Drag and Drop actions which this destination can receive - see the description above.

## 18.3 Signals

When a drop destination has accepted a dragged item, certain signals will be emitted, depending on what action has been selected. For instance, the user might have held down the **Shift** key to specify a move rather than a copy. Remember that the user can only select the actions which you have specified in your calls to `drag_dest_set()` and `drag_source_set()`.

### 18.3.1 Copy

The source widget will emit these signals, in this order:

- `drag_begin`: Provides `DragContext`.
- `drag_data_get`: Provides info about the dragged data format, and a `Gtk::SelectionData` structure, in which you should put the requested data.
- `drag_end`: Provides `DragContext`.

The destination widget will emit these signals, in this order:

- `drag_motion`: Provides `DragContext` and coordinates. You can call the `drag_status()` method of the `DragContext` to indicate which action will be accepted.

---

- `drag_drop`: Provides `DragContext` and coordinates. You can call `drag_get_data()`, which triggers the `drag_data_get` signal in the source widget, and then the `drag_data_received` signal in the destination widget.
- `drag_data_received`: Provides info about the dragged data format, and a `Gtk::SelectionData` structure which contains the dropped data. You should call the `drag_finish()` method of the `DragContext` to indicate whether the operation was successful.

### 18.3.2 Move

During a move, the source widget will also emit this signal:

- `drag_data_delete`: Gives the source the opportunity to delete the original data if that's appropriate.

## 18.4 DragContext

The drag and drop signals provide a `DragContext`, which contains some information about the drag and drop operation and can be used to influence the process. For instance, you can discover the source widget, or change the drag and drop icon, by using the `set_icon()` methods. More importantly, you should call the `drag_finish()` method from your `drag_data_received` signal handler to indicate whether the drop was successful.

## 18.5 Example

Here is a very simple example, demonstrating a drag and drop `Copy` operation:




Figure 18.1: Drag and Drop

### Source Code

File: `dndwindow.h` (For use with `gtkmm 3`)

---

```
#ifndef GTKMM_EXAMPLE_DNDWINDOW_H
#define GTKMM_EXAMPLE_DNDWINDOW_H

#include <gtkmm/box.h>
#include <gtkmm/label.h>
#include <gtkmm/window.h>
#include <gtkmm/button.h>

class DnDWindow : public Gtk::Window
{
public:
    DnDWindow();
    virtual ~DnDWindow();

protected:
    //Signal handlers:
    void on_button_drag_data_get(
        const Glib::RefPtr<Gdk::DragContext>& context,
        Gtk::SelectionData& selection_data, guint info, guint time);
    void on_label_drop_drag_data_received(
        const Glib::RefPtr<Gdk::DragContext>& context, int x, int y,
        const Gtk::SelectionData& selection_data, guint info, guint time ←
    );

    //Member widgets:
    Gtk::Box m_HBox;
    Gtk::Button m_Button_Drag;
    Gtk::Label m_Label_Drop;
};

#endif // GTKMM_EXAMPLE_DNDWINDOW_H
```

**File: dndwindow.cc (For use with gtkmm 3)**

```
#include "dndwindow.h"
#include <iostream>

DnDWindow::DnDWindow()
: m_Button_Drag("Drag Here\n"),
  m_Label_Drop("Drop here\n")
{
    set_title("DnD example");

    add(m_HBox);

    //Targets:
```

```
std::vector<Gtk::TargetEntry> listTargets;
listTargets.push_back( Gtk::TargetEntry("STRING") );
listTargets.push_back( Gtk::TargetEntry("text/plain") );

//Drag site:

//Make m_Button_Drag a DnD drag source:
m_Button_Drag.drag_source_set(listTargets);

//Connect signals:
m_Button_Drag.signal_drag_data_get().connect(sigc::mem_fun(*this,
    &DnDWindow::on_button_drag_data_get));

m_HBox.pack_start(m_Button_Drag);

//Drop site:

//Make m_Label_Drop a DnD drop destination:
m_Label_Drop.drag_dest_set(listTargets);

//Connect signals:
m_Label_Drop.signal_drag_data_received().connect(sigc::mem_fun(*this,
    &DnDWindow::on_label_drop_drag_data_received) );

m_HBox.pack_start(m_Label_Drop);

show_all();
}

DnDWindow::~DnDWindow()
{
}

void DnDWindow::on_button_drag_data_get(
    const Glib::RefPtr<Gdk::DragContext>&,
    Gtk::SelectionData& selection_data, guint, guint)
{
    selection_data.set(selection_data.get_target(), 8 /* 8 bits format */,
        (const gchar*)"I'm Data!",
        9 /* the length of I'm Data! in bytes */);
}

void DnDWindow::on_label_drop_drag_data_received(
    const Glib::RefPtr<Gdk::DragContext>& context, int, int,
    const Gtk::SelectionData& selection_data, guint, guint time)
{
    const int length = selection_data.get_length();
```

---

```
if((length >= 0) && (selection_data.get_format() == 8))
{
    std::cout << "Received \"" << selection_data.get_data_as_string()
        << "\" in label " << std::endl;
}

context->drag_finish(false, false, time);
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "dndwindow.h"
#include <gtkmm/application.h>

int main (int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    DnDWindow dndWindow;

    //Shows the window and returns when it is closed.
    return app->run(dndWindow);
}
```

There is a more complex example in [examples/others/dnd](#).

## Chapter 19

# The Clipboard

Simple text copy-paste functionality is provided for free by widgets such as `Gtk::Entry` and `Gtk::TextView`, but you might need special code to deal with your own data formats. For instance, a drawing program would need special code to allow copy and paste within a view, or between documents.

You can usually pretend that `Gtk::Clipboard` is a singleton. You can get the default clipboard instance with `Gtk::Clipboard::get()`. This is probably the only clipboard you will ever need.

Your application doesn't need to wait for clipboard operations, particularly between the time when the user chooses Copy and then later chooses Paste. Most `Gtk::Clipboard` methods take `sigc::slots` which specify callback methods. When `Gtk::Clipboard` is ready, it will call these methods, either providing the requested data, or asking for data.

### Reference

## 19.1 Targets

Different applications contain different types of data, and they might make that data available in a variety of formats. `gtkmm` calls these data types *targets*.

For instance, `gedit` can supply and receive the `"UTF8_STRING"` target, so you can paste data into `gedit` from any application that supplies that target. Or two different image editing applications might supply and receive a variety of image formats as targets. As long as one application can receive one of the targets that the other supplies then you will be able to copy data from one to the other.

A target can be in a variety of binary formats. This chapter, and the examples, assume that the data is 8-bit text. This would allow us to use an XML format for the clipboard data. However this would probably not be appropriate for binary data such as images. `Gtk::Clipboard` provides overloads that allow you to specify the format in more detail if necessary.

---

The **Drag and Drop** API uses the same mechanism. You should probably use the same data targets and formats for both Clipboard and Drag and Drop operations.

## 19.2 Copy

When the user asks to copy some data, you should tell the `Clipboard` what targets are available, and provide the callback methods that it can use to get the data. At this point you should store a copy of the data, to be provided when the clipboard calls your callback method in response to a paste.

For instance,

```
Glib::RefPtr<Gtk::Clipboard> refClipboard = Gtk::Clipboard::get();

//Targets:
std::vector<Gtk::TargetEntry> targets;
targets.push_back( Gtk::TargetEntry("example_custom_target") );
targets.push_back( Gtk::TargetEntry("UTF8_STRING") );

refClipboard->set( targets,
    sigc::mem_fun(*this, &ExampleWindow::on_clipboard_get),
    sigc::mem_fun(*this, &ExampleWindow::on_clipboard_clear) );
```

Your callback will then provide the stored data when the user chooses to paste the data. For instance:

```
void ExampleWindow::on_clipboard_get(
    Gtk::SelectionData& selection_data, guint /* info */)
{
    const std::string target = selection_data.get_target();

    if(target == "example_custom_target")
        selection_data.set("example_custom_target", m_ClipboardStore);
}
```

The ideal example below can supply more than one clipboard target.

The clear callback allows you to free the memory used by your stored data when the clipboard replaces its data with something else.

## 19.3 Paste

When the user asks to paste data from the `Clipboard`, you should request a specific format and provide a callback method which will be called with the actual data. For instance:

---

```
refClipboard->request_contents("example_custom_target",
    sigc::mem_fun(*this, &ExampleWindow::on_clipboard_received) );
```

Here is an example callback method:

```
void ExampleWindow::on_clipboard_received(
    const Gtk::SelectionData& selection_data)
{
    Glib::ustring clipboard_data = selection_data.get_data_as_string();
    //Do something with the pasted data.
}
```

### 19.3.1 Discovering the available targets

To find out what targets are currently available on the Clipboard for pasting, call the `request_targets()` method, specifying a method to be called with the information. For instance:

```
refClipboard->request_targets( sigc::mem_fun(*this,
    &ExampleWindow::on_clipboard_received_targets) );
```

In your callback, compare the vector of available targets with those that your application supports for pasting. You could enable or disable a Paste menu item, depending on whether pasting is currently possible. For instance:

```
void ExampleWindow::on_clipboard_received_targets(
    const std::vector<Glib::ustring>& targets)
{
    const bool bPasteIsPossible =
        std::find(targets.begin(), targets.end(),
            example_target_custom) != targets.end();

    // Enable/Disable the Paste button appropriately:
    m_Button_Paste.set_sensitive(bPasteIsPossible);
}
```

## 19.4 Examples

### 19.4.1 Simple

This example allows copy and pasting of application-specific data, using the standard text target. Although this is simple, it's not ideal because it does not identify the Clipboard data as being of a particular type.

---






Figure 19.1: Clipboard - Simple

### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_copy();
    void on_button_paste();
    void on_clipboard_text_received(const Glib::ustring& text);

    //Child widgets:
    Gtk::Box m_VBox;

    Gtk::Label m_Label;

    Gtk::Grid m_Grid;
    Gtk::ToggleButton m_ButtonA1, m_ButtonA2, m_ButtonB1, m_ButtonB2;

    Gtk::ButtonBox m_ButtonBox;
    Gtk::Button m_Button_Copy, m_Button_Paste;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Label("Select cells in the grid, click Copy, then open a second "
         "instance of this example to try pasting the copied data."),
  m_ButtonA1("A1"), m_ButtonA2("A2"), m_ButtonB1("B1"), m_ButtonB2("B2"),
  m_Button_Copy("_Copy", /* mnemonic= */ true), m_Button_Paste("_Paste", ↵
    true)
{
  set_title("Gtk::Clipboard example");
  set_border_width(12);

  add(m_VBox);

  m_VBox.pack_start(m_Label, Gtk::PACK_SHRINK);

  //Fill Grid:
  m_VBox.pack_start(m_Grid);
  m_Grid.set_row_homogeneous(true);
  m_Grid.set_column_homogeneous(true);
  m_Grid.attach(m_ButtonA1, 0, 0, 1, 1);
  m_Grid.attach(m_ButtonA2, 1, 0, 1, 1);
  m_Grid.attach(m_ButtonB1, 0, 1, 1, 1);
  m_Grid.attach(m_ButtonB2, 1, 1, 1, 1);

  //Add ButtonBox to bottom:
  m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);
  m_VBox.set_spacing(6);

  //Fill ButtonBox:
  m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);
  m_ButtonBox.pack_start(m_Button_Copy, Gtk::PACK_SHRINK);
  m_Button_Copy.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_button_copy) );
  m_ButtonBox.pack_start(m_Button_Paste, Gtk::PACK_SHRINK);
  m_Button_Paste.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_button_paste) );

  show_all_children();
}

ExampleWindow::~~ExampleWindow()
{
}
```

```
void ExampleWindow::on_button_copy()
{
    //Build a string representation of the stuff to be copied:
    //Ideally you would use XML, with an XML parser here:
    Glib::ustring strData;
    strData += m_ButtonA1.get_active() ? "1" : "0";
    strData += m_ButtonA2.get_active() ? "1" : "0";
    strData += m_ButtonB1.get_active() ? "1" : "0";
    strData += m_ButtonB2.get_active() ? "1" : "0";

    auto refClipboard = Gtk::Clipboard::get();
    refClipboard->set_text(strData);
}

void ExampleWindow::on_button_paste()
{
    //Tell the clipboard to call our method when it is ready:
    auto refClipboard = Gtk::Clipboard::get();
    refClipboard->request_text(sigc::mem_fun(*this,
        &ExampleWindow::on_clipboard_text_received) );
}

void ExampleWindow::on_clipboard_text_received(const Glib::ustring& text)
{
    //See comment in on_button_copy() about this silly clipboard format.
    if(text.size() >= 4)
    {
        m_ButtonA1.set_active( text[0] == '1' );
        m_ButtonA2.set_active( text[1] == '1' );
        m_ButtonB1.set_active( text[2] == '1' );
        m_ButtonB2.set_active( text[3] == '1' );
    }
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    //APPLICATION_NON_UNIQUE because it shall be possible to run several
    //instances of this application simultaneously.
    auto app = Gtk::Application::create(
        argc, argv, "org.gtkmm.example", Gio::APPLICATION_NON_UNIQUE);

    ExampleWindow window;
```

```
//Shows the window and returns when it is closed.  
return app->run(window);  
}
```

### 19.4.2 Ideal

This is like the simple example, but it

1. Defines a custom clipboard target, though the format of that target is still text.
2. It supports pasting of 2 targets - both the custom one and a text one that creates an arbitrary text representation of the custom data.
3. It uses `request_targets()` and the `owner_change` signal and disables the Paste button if it can't use anything on the clipboard.




Figure 19.2: Clipboard - Ideal

#### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H  
#define GTKMM_EXAMPLEWINDOW_H  
  
#include <gtkmm.h>  
  
class ExampleWindow : public Gtk::Window  
{  
public:  
    ExampleWindow();  
    virtual ~ExampleWindow();  
};
```

```
protected:
    //Signal handlers:
    void on_button_copy();
    void on_button_paste();

    void on_clipboard_owner_change(GdkEventOwnerChange* event);
    void on_clipboard_get(Gtk::SelectionData& selection_data, guint info);
    void on_clipboard_clear();

    void on_clipboard_received(const Gtk::SelectionData& selection_data);
    void on_clipboard_received_targets(const std::vector<Glib::ustring>& ↵
        targets);

    void update_paste_status(); //Disable the paste button if there is ↵
        nothing to paste.

    //Child widgets:
    Gtk::Box m_VBox;

    Gtk::Label m_Label;

    Gtk::Grid m_Grid;
    Gtk::ToggleButton m_ButtonA1, m_ButtonA2, m_ButtonB1, m_ButtonB2;

    Gtk::ButtonBox m_ButtonBox;
    Gtk::Button m_Button_Copy, m_Button_Paste;

    Glib::ustring m_ClipboardStore; //Keep copied stuff here, until it is ↵
        pasted. This could be a big complex data structure.
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

**File: examplewindow.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <algorithm>

namespace
{

    //These should usually be MIME types.
    const char example_target_custom[] = "gtkmmclipboardexample";
    const char example_target_text[] = "UTF8_STRING";

} // anonymous namespace
```

```

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Label("Select cells in the grid, click Copy, then open a second ↵
    instance "
        "of this example to try pasting the copied data.\nOr try pasting ↵
        the "
        "text representation into gedit."),
  m_ButtonA1("A1"), m_ButtonA2("A2"), m_ButtonB1("B1"), m_ButtonB2("B2"),
  m_Button_Copy("_Copy", /* mnemonic= */ true), m_Button_Paste("_Paste", ↵
    true)
{
  set_title("Gtk::Clipboard example");
  set_border_width(12);

  add(m_VBox);

  m_VBox.pack_start(m_Label, Gtk::PACK_SHRINK);

  //Fill Grid:
  m_VBox.pack_start(m_Grid);
  m_Grid.set_row_homogeneous(true);
  m_Grid.set_column_homogeneous(true);
  m_Grid.attach(m_ButtonA1, 0, 0, 1, 1);
  m_Grid.attach(m_ButtonA2, 1, 0, 1, 1);
  m_Grid.attach(m_ButtonB1, 0, 1, 1, 1);
  m_Grid.attach(m_ButtonB2, 1, 1, 1, 1);

  //Add ButtonBox to bottom:
  m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);
  m_VBox.set_spacing(6);

  //Fill ButtonBox:
  m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);
  m_ButtonBox.pack_start(m_Button_Copy, Gtk::PACK_SHRINK);
  m_Button_Copy.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_button_copy) );
  m_ButtonBox.pack_start(m_Button_Paste, Gtk::PACK_SHRINK);
  m_Button_Paste.signal_clicked().connect(sigc::mem_fun(*this,
    &ExampleWindow::on_button_paste) );

  //Connect a signal handler that will be called when the contents of
  //the clipboard change.
  Gtk::Clipboard::get()->signal_owner_change().connect(sigc::mem_fun(*this ↵
    ,
    &ExampleWindow::on_clipboard_owner_change) );

```

---

```
show_all_children();

update_paste_status();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_copy()
{
    //Build a string representation of the stuff to be copied:
    //Ideally you would use XML, with an XML parser here:
    Glib::ustring strData;
    strData += m_ButtonA1.get_active() ? "1" : "0";
    strData += m_ButtonA2.get_active() ? "1" : "0";
    strData += m_ButtonB1.get_active() ? "1" : "0";
    strData += m_ButtonB2.get_active() ? "1" : "0";

    auto refClipboard = Gtk::Clipboard::get();

    //Targets:
    std::vector<Gtk::TargetEntry> targets;

    targets.push_back( Gtk::TargetEntry(example_target_custom) );
    targets.push_back( Gtk::TargetEntry(example_target_text) );

    refClipboard->set(targets,
        sigc::mem_fun(*this, &ExampleWindow::on_clipboard_get),
        sigc::mem_fun(*this, &ExampleWindow::on_clipboard_clear) );

    //Store the copied data until it is pasted:
    //(Must be done after the call to refClipboard->set(), because that call
    //may trigger a call to on_clipboard_clear.)
    m_ClipboardStore = strData;

    update_paste_status();
}

void ExampleWindow::on_button_paste()
{
    //Tell the clipboard to call our method when it is ready:
    auto refClipboard = Gtk::Clipboard::get();

    refClipboard->request_contents(example_target_custom,
        sigc::mem_fun(*this, &ExampleWindow::on_clipboard_received) );
}
```

---

```
    update_paste_status();
}

void ExampleWindow::on_clipboard_owner_change(GdkEventOwnerChange*)
{
    update_paste_status();
}

void ExampleWindow::on_clipboard_get(Gtk::SelectionData& selection_data,
    guint /* info */)
{
    // info corresponds to the optional info parameter in Gtk::TargetEntry's
    // constructor. We don't use that, so we use selection_data's target ↵
    // instead.

    const std::string target = selection_data.get_target();

    if(target == example_target_custom)
    {
        // This set() overload uses an 8-bit text format for the data.
        selection_data.set(example_target_custom, m_ClipboardStore.raw());
    }
    else if(target == example_target_text)
    {
        //Build some arbitrary text representation of the data,
        //so that people see something when they paste into a text editor:
        Glib::ustring text_representation;

        text_representation += m_ButtonA1.get_active() ? "A1, " : "";
        text_representation += m_ButtonA2.get_active() ? "A2, " : "";
        text_representation += m_ButtonB1.get_active() ? "B1, " : "";
        text_representation += m_ButtonB2.get_active() ? "B2, " : "";

        selection_data.set_text(text_representation);
    }
    else
    {
        g_warning("ExampleWindow::on_clipboard_get(): "
            "Unexpected clipboard target format.");
    }
}

void ExampleWindow::on_clipboard_clear()
{
    //This isn't really necessary. I guess it might save memory.
    m_ClipboardStore.clear();
}
```

---



```
void ExampleWindow::on_clipboard_received(
    const Gtk::SelectionData& selection_data)
{
    const std::string target = selection_data.get_target();

    //It should always be this, because that's what we asked for when ←
    calling
    //request_contents().
    if(target == example_target_custom)
    {
        Glib::ustring clipboard_data = selection_data.get_data_as_string();

        //See comment in on_button_copy() about this silly clipboard format.
        if(clipboard_data.size() >= 4)
        {
            m_ButtonA1.set_active( clipboard_data[0] == '1' );
            m_ButtonA2.set_active( clipboard_data[1] == '1' );
            m_ButtonB1.set_active( clipboard_data[2] == '1' );
            m_ButtonB2.set_active( clipboard_data[3] == '1' );
        }
    }
}

void ExampleWindow::update_paste_status()
{
    //Disable the paste button if there is nothing to paste.

    auto refClipboard = Gtk::Clipboard::get();

    //Discover what targets are available:
    refClipboard->request_targets(sigc::mem_fun(*this,
        &ExampleWindow::on_clipboard_received_targets) );
}

void ExampleWindow::on_clipboard_received_targets(
    const std::vector<Glib::ustring>& targets)
{
    const bool bPasteIsPossible =
        std::find(targets.begin(), targets.end(),
            example_target_custom) != targets.end();

    // Enable/Disable the Paste button appropriately:
    m_Button_Paste.set_sensitive(bPasteIsPossible);
}
```

File: main.cc (For use with gtkmm 3)

---

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    //APPLICATION_NON_UNIQUE because it shall be possible to run several
    //instances of this application simultaneously.
    auto app = Gtk::Application::create(
        argc, argv, "org.gtkmm.example", Gio::APPLICATION_NON_UNIQUE);

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## Chapter 20

# Printing

At the application development level, gtkmm's printing API provides dialogs that are consistent across applications and allows use of Cairo's common drawing API, with Pango-driven text rendering. In the implementation of this common API, platform-specific backends and printer-specific drivers are used.

### 20.1 PrintOperation

The primary object is `Gtk::PrintOperation`, allocated for each print operation. To handle page drawing connect to its signals, or inherit from it and override the default virtual signal handlers. `PrintOperation` automatically handles all the settings affecting the print loop.

#### 20.1.1 Signals

The `PrintOperation::run()` method starts the print loop, during which various signals are emitted:

- `begin_print`: You must handle this signal, because this is where you create and set up a `Pango::Layout` using the provided `Gtk::PrintContext`, and break up your printing output into pages.
  - `paginate`: Pagination is potentially slow so if you need to monitor it you can call the `PrintOperation::set_show_page_dialog` method and handle this signal.
  - For each page that needs to be rendered, the following signals are emitted:
    - `request_page_setup`: Provides a `PrintContext`, page number and `Gtk::PageSetup`. Handle this signal if you need to modify page setup on a per-page basis.
-

- `draw_page`: You must handle this signal, which provides a `PrintContext` and a page number. The `PrintContext` should be used to create a `Cairo::Context` into which the provided page should be drawn. To render text, iterate over the `Pango::Layout` you created in the `begin_print` handler.
- `end_print`: A handler for it is a safe place to free any resources related to a `PrintOperation`. If you have your custom class that inherits from `PrintOperation`, it is naturally simpler to do it in the destructor.
- `done`: This signal is emitted when printing is finished, meaning when the print data is spooled. Note that the provided `Gtk::PrintOperationResult` may indicate that an error occurred. In any case you probably want to notify the user about the final status.
- `status_changed`: Emitted whenever a print job's status changes, until it is finished. Call the `PrintOperation::set_track_print_status()` method to monitor the job status after spooling. To see the status, use `get_status()` or `get_status_string()`.

## Reference

## 20.2 Page setup

The `PrintOperation` class has a method called `set_default_page_setup()` which selects the default paper size, orientation and margins. To show a page setup dialog from your application, use the `Gtk::run_page_setup_dialog()` method, which returns a `Gtk::PageSetup` object with the chosen settings. Use this object to update a `PrintOperation` and to access the selected `Gtk::PaperSize`, `Gtk::PageOrientation` and printer-specific margins.

You should save the chosen `Gtk::PageSetup` so you can use it again if the page setup dialog is shown again.

For instance,

```
//Within a class that inherits from Gtk::Window and keeps m_refPageSetup ←
    and m_refSettings as members...
Glib::RefPtr<Gtk::PageSetup> new_page_setup = Gtk::run_page_setup_dialog(* ←
    this, m_refPageSetup, m_refSettings);
m_refPageSetup = new_page_setup;
```

## Reference

The Cairo coordinate system, in the `draw_page` handler, is automatically rotated to the current page orientation. It is normally within the printer margins, but you can change that via the `PrintOperation::set_use_full_page()` method. The default measurement unit is device pixels. To select other units, use the `PrintOperation::set_unit()` method.

---

## 20.3 Rendering text

Text rendering is done using Pango. The `Pango::Layout` object for printing should be created by calling the `PrintContext::create_pango_layout()` method. The `PrintContext` object also provides the page metrics, via `get_width()` and `get_height()`. The number of pages can be set with `PrintOperation::set_n_pages()`. To actually render the Pango text in `on_draw_page`, get a `Cairo::Context` with `PrintContext::get_cairo_context()` and show the `Pango::LayoutLines` that appear within the requested page number.

See [an example](#) of exactly how this can be done.

## 20.4 Asynchronous operations

By default, `PrintOperation::run()` returns when a print operation is completed. If you need to run a non-blocking print operation, call `PrintOperation::set_allow_async()`. Note that `set_allow_async()` is not supported on all platforms, however the done signal will still be emitted.

`run()` may return `PRINT_OPERATION_RESULT_IN_PROGRESS`. To track status and handle the result or error you need to implement signal handlers for the `done` and `status_changed` signals:

For instance,

```
// in class ExampleWindow's method...
Glib::RefPtr<PrintOperation> op = PrintOperation::create();
// ...set up op...
op->signal_done().connect(sigc::bind(sigc::mem_fun(*this, &ExampleWindow:: ←
    on_printoperation_done), op));
// run the op
```

Second, check for an error and connect to the `status_changed` signal. For instance:

```
void ExampleWindow::on_printoperation_done(Gtk::PrintOperationResult ←
    result, const Glib::RefPtr<PrintOperation>& op)
{
    if (result == Gtk::PRINT_OPERATION_RESULT_ERROR)
        //notify user
    else if (result == Gtk::PRINT_OPERATION_RESULT_APPLY)
        //Update PrintSettings with the ones used in this PrintOperation

    if (! op->is_finished())
        op->signal_status_changed().connect(sigc::bind(sigc::mem_fun(*this, & ←
            ExampleWindow::on_printoperation_status_changed), op));
}
```

Finally, check the status. For instance,

```
void ExampleWindow::on_printoperation_status_changed(const Glib::RefPtr< ↵
    PrintFormOperation>& op)
{
    if (op->is_finished())
        //the print job is finished
    else
        //get the status with get_status() or get_status_string()

    //update UI
}
```

## 20.5 Export to PDF

The 'Print to file' option is available in the print dialog, without the need for extra implementation. However, it is sometimes useful to generate a pdf file directly from code. For instance,

```
Glib::RefPtr<Gtk::PrintOperation> op = Gtk::PrintOperation::create();
// ...set up op...
op->set_export_filename("test.pdf");
Gtk::PrintOperationResult res = op->run(Gtk::PRINT_OPERATION_ACTION_EXPORT ↵
    );
```

## 20.6 Extending the print dialog

You may add a custom tab to the print dialog:

- Set the title of the tab via `PrintOperation::set_custom_tab_label()`, create a new widget and return it from the `create_custom_widget` signal handler. You'll probably want this to be a container widget, packed with some others.
- Get the data from the widgets in the `custom_widget_apply` signal handler.

Although the `custom_widget_apply` signal provides the widget you previously created, to simplify things you can keep the widgets you expect to contain some user input as class members. For example, let's say you have a `Gtk::Entry` called `m_Entry` as a member of your `CustomPrintOperation` class:

```
Gtk::Widget* CustomPrintOperation::on_create_custom_widget()
{
    set_custom_tab_label("My custom tab");
```

```
Gtk::Box* hbox = new Gtk::Box(Gtk::ORIENTATION_HORIZONTAL, 8);
hbox->set_border_width(6);

Gtk::Label* label = Gtk::make_managed<Gtk::Label>("Enter some text: ");
hbox->pack_start(*label, false, false);
label->show();

hbox->pack_start(m_Entry, false, false);
m_Entry.show();

return hbox;
}

void CustomPrintOperation::on_custom_widget_apply(Gtk::Widget* /* widget */
/* */)
{
    Glib::ustring user_input = m_Entry.get_text();
    //...
}
```

The example in `examples/book/printing/advanced` demonstrates this.

## 20.7 Preview

The native GTK+ print dialog has a preview button, but you may also start a preview directly from an application:

```
// in a class that inherits from Gtk::Window...
Glib::RefPtr<PrintOperation> op = PrintOperation::create();
// ...set up op...
op->run(Gtk::PRINT_OPERATION_ACTION_PREVIEW, *this);
```

On Unix, the default preview handler uses an external viewer program. On Windows, the native preview dialog will be shown. If necessary you may override this behaviour and provide a custom preview dialog. See the example located in `/examples/book/printing/advanced`.

## 20.8 Example

### 20.8.1 Simple

The following example demonstrates how to print some input from a user interface. It shows how to implement `on_begin_print` and `on_draw_page`, as well as how to track print status and update the print settings.

---



Figure 20.1: Printing - Simple

### Source Code

File: examplewindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

// This file is part of the printing/simple and printing/advanced examples

#include <gtkmm.h>

class PrintFormOperation;

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow(const Glib::RefPtr<Gtk::Application>& app);
```



```
virtual ~ExampleWindow();

protected:

    void build_main_menu(const Glib::RefPtr<Gtk::Application>& app);

    void print_or_preview(Gtk::PrintOperationAction print_action);

    //PrintOperation signal handlers.
    //We handle these so can get necessary information to update the UI or ↵
    print settings.
    //Our derived PrintOperation class also overrides some default signal ↵
    handlers.
    void on_printoperation_status_changed();
    void on_printoperation_done(Gtk::PrintOperationResult result);

    //Action signal handlers:
    void on_menu_file_new();
    void on_menu_file_page_setup();
    void on_menu_file_print_preview();
    void on_menu_file_print();
    void on_menu_file_quit();

    //Printing-related objects:
    Glib::RefPtr<Gtk::PageSetup> m_refPageSetup;
    Glib::RefPtr<Gtk::PrintSettings> m_refSettings;
    Glib::RefPtr<PrintFormOperation> m_refPrintFormOperation;

    //Child widgets:
    Gtk::Box m_VBox;
    Gtk::Grid m_Grid;

    Gtk::Label m_NameLabel;
    Gtk::Entry m_NameEntry;

    Gtk::Label m_SurnameLabel;
    Gtk::Entry m_SurnameEntry;

    Gtk::Label m_CommentsLabel;
    Gtk::ScrolledWindow m_ScrolledWindow;
    Gtk::TextView m_TextView;

    Glib::RefPtr<Gtk::TextBuffer> m_refTextBuffer;

    unsigned m_ContextId;
    Gtk::Statusbar m_Statusbar;
```

---

```

    Glib::RefPtr<Gtk::Builder> m_refBuilder;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

**File: printformoperation.h (For use with gtkmm 3)**

```

#ifndef GTKMM_PRINT_FORM_OPERATION_H
#define GTKMM_PRINT_FORM_OPERATION_H

#include <gtkmm.h>
#include <pangomm.h>
#include <vector>

//We derive our own class from PrintOperation,
//so we can put the actual print implementation here.
class PrintFormOperation : public Gtk::PrintOperation
{
public:
    static Glib::RefPtr<PrintFormOperation> create();
    virtual ~PrintFormOperation();

    void set_name(const Glib::ustring& name) { m_Name = name; }
    void set_comments(const Glib::ustring& comments) { m_Comments = comments; }

protected:
    PrintFormOperation();

    //PrintOperation default signal handler overrides:
    void on_begin_print(const Glib::RefPtr<Gtk::PrintContext>& context) override;
    void on_draw_page(const Glib::RefPtr<Gtk::PrintContext>& context, int page_nr) override;

    Glib::ustring m_Name;
    Glib::ustring m_Comments;
    Glib::RefPtr<Pango::Layout> m_refLayout;
    std::vector<int> m_PageBreaks; // line numbers where a page break occurs
};

#endif // GTKMM_PRINT_FORM_OPERATION_H

```

**File: examplewindow.cc (For use with gtkmm 3)**

```

#include "examplewindow.h"
#include "printformoperation.h"
#include <iostream>

```

---

```
const Glib::ustring app_title = "gtkmm Printing Example";

ExampleWindow::ExampleWindow(const Glib::RefPtr<Gtk::Application>& app)
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_NameLabel("Name"),
  m_SurnameLabel("Surname"),
  m_CommentsLabel("Comments")
{
  m_refPageSetup = Gtk::PageSetup::create();
  m_refSettings = Gtk::PrintSettings::create();

  m_ContextId = m_Statusbar.get_context_id(app_title);

  set_title(app_title);
  set_default_size(400, 300);

  add(m_VBox);

  build_main_menu(app);

  m_VBox.pack_start(m_Grid);

  //Arrange the widgets inside the grid:
  m_Grid.set_row_spacing(5);
  m_Grid.set_column_spacing(5);
  m_Grid.attach(m_NameLabel, 0, 0, 1, 1);
  m_Grid.attach(m_NameEntry, 1, 0, 1, 1);

  m_Grid.attach(m_SurnameLabel, 0, 1, 1, 1);
  m_Grid.attach(m_SurnameEntry, 1, 1, 1, 1);

  //Add the TextView, inside a ScrolledWindow:
  m_ScrolledWindow.add(m_TextView);

  //Only show the scrollbars when they are necessary:
  m_ScrolledWindow.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC ←
  );

  m_Grid.attach(m_CommentsLabel, 0, 2, 1, 1);
  m_Grid.attach(m_ScrolledWindow, 1, 2, 1, 1);
  m_ScrolledWindow.set_hexpand(true);
  m_ScrolledWindow.set_vexpand(true);

  m_refTextBuffer = Gtk::TextBuffer::create();
  m_TextView.set_buffer(m_refTextBuffer);
```

---

```
m_VBox.pack_start(m_Statusbar);

show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::build_main_menu(const Glib::RefPtr<Gtk::Application>& ←
    app)
{
    //Create actions for menus and toolbars:
    auto refActionGroup = Gio::SimpleActionGroup::create();

    //File menu:
    refActionGroup->add_action("new",
        sigc::mem_fun(*this, &ExampleWindow::on_menu_file_new));

    refActionGroup->add_action("pagesetup",
        sigc::mem_fun(*this, &ExampleWindow::on_menu_file_page_setup));

    refActionGroup->add_action("printpreview",
        sigc::mem_fun(*this, &ExampleWindow::on_menu_file_print_preview));

    refActionGroup->add_action("print",
        sigc::mem_fun(*this, &ExampleWindow::on_menu_file_print));

    refActionGroup->add_action("quit",
        sigc::mem_fun(*this, &ExampleWindow::on_menu_file_quit));

    insert_action_group("example", refActionGroup);

    // When the menubar is a child of a Gtk::Window, keyboard accelerators ←
    // are not
    // automatically fetched from the Gio::Menu.
    // See the examples/book/menus/main_menu example for an alternative way ←
    // of
    // adding the menubar when using Gtk::ApplicationWindow.
    app->set_accel_for_action("example.new", "<Primary>n");
    app->set_accel_for_action("example.print", "<Primary>p");
    app->set_accel_for_action("example.quit", "<Primary>q");

    m_refBuilder = Gtk::Builder::create();

    // Layout the actions in a menubar:
    Glib::ustring ui_menu_info =
```

---

```

"<interface>"
"  <menu id='menu-example'>"
"    <submenu>"
"      <attribute name='label' translatable='yes'>_File</attribute>"
"      <section>"
"        <item>"
"          <attribute name='label' translatable='yes'>_New</attribute <↵
">"
"          <attribute name='action'>example.new</attribute>"
"        </item>"
"      </section>"
"      <section>"
"        <item>"
"          <attribute name='label' translatable='yes'>Page _Setup...</ <↵
"attribute>"
"          <attribute name='action'>example.pagesetup</attribute>"
"        </item>"
"        <item>"
"          <attribute name='label' translatable='yes'>Print Preview</ <↵
"attribute>"
"          <attribute name='action'>example.printpreview</attribute>"
"        </item>"
"        <item>"
"          <attribute name='label' translatable='yes'>_Print...</ <↵
"attribute>"
"          <attribute name='action'>example.print</attribute>"
"        </item>"
"      </section>"
"      <section>"
"        <item>"
"          <attribute name='label' translatable='yes'>_Quit</attribute <↵
">"
"          <attribute name='action'>example.quit</attribute>"
"        </item>"
"      </section>"
"    </submenu>"
"  </menu>"
"</interface>";

try
{
  m_refBuilder->add_from_string(ui_menu_info);
}
catch(const Glib::Error& ex)
{
  std::cerr << "building menus failed: " << ex.what();
}

```

---

```
// Layout the actions in a toolbar:
Glib::ustring ui_toolbar_info =
    "<!-- Generated with glade 3.18.3 -->"
    "<interface>"
    "  <requires lib='gtk+' version='3.8' />"
    "  <object class='GtkToolbar' id='toolbar'>"
    "    <property name='visible'>True</property>"
    "    <property name='can_focus'>False</property>"
    "    <child>"
    "      <object class='GtkToolButton' id='toolbutton_new'>"
    "        <property name='visible'>True</property>"
    "        <property name='can_focus'>False</property>"
    "        <property name='tooltip_text' translatable='yes'>New</ ↵  
        property>"
    "        <property name='action_name'>example.new</property>"
    "        <property name='icon_name'>document-new</property>"
    "      </object>"
    "    <packing>"
    "      <property name='expand'>False</property>"
    "      <property name='homogeneous'>True</property>"
    "    </packing>"
    "  </child>"
    "  <child>"
    "    <object class='GtkToolButton' id='toolbutton_print'>"
    "      <property name='visible'>True</property>"
    "      <property name='can_focus'>False</property>"
    "      <property name='tooltip_text' translatable='yes'>Print</ ↵  
      property>"
    "      <property name='action_name'>example.print</property>"
    "      <property name='icon_name'>document-print</property>"
    "    </object>"
    "    <packing>"
    "      <property name='expand'>False</property>"
    "      <property name='homogeneous'>True</property>"
    "    </packing>"
    "  </child>"
    "  <child>"
    "    <object class='GtkSeparatorToolItem' id='separator1'>"
    "      <property name='visible'>True</property>"
    "      <property name='can_focus'>False</property>"
    "    </object>"
    "    <packing>"
    "      <property name='expand'>False</property>"
    "      <property name='homogeneous'>False</property>"
    "    </packing>"
    "  </child>"
```

```

    "<child>"
    "<object class='GtkToolButton' id='toolbutton_quit'>"
    "  <property name='visible'>True</property>"
    "  <property name='can_focus'>False</property>"
    "  <property name='tooltip_text' translatable='yes'>Quit</ ↵
      property>"
    "  <property name='action_name'>example.quit</property>"
    "  <property name='icon_name'>application-exit</property>"
    "</object>"
    "<packing>"
    "  <property name='expand'>False</property>"
    "  <property name='homogeneous'>True</property>"
    "</packing>"
    "</child>"
    "</object>"
    "</interface>";

try
{
    m_refBuilder->add_from_string(ui_toolbar_info);
}
catch(const Glib::Error& ex)
{
    std::cerr << "building toolbar failed: " << ex.what();
}

// Get the menubar and add it to a container widget:
auto object = m_refBuilder->get_object("menu-example");
auto gmenu = Glib::RefPtr<Gio::Menu>::cast_dynamic(object);
if (!gmenu)
    g_warning("GMenu not found");
else
{
    auto pMenuBar = Gtk::make_managed<Gtk::MenuBar>(gmenu);

    // Add the MenuBar to the window:
    m_VBox.pack_start(*pMenuBar, Gtk::PACK_SHRINK);
}

// Get the toolbar and add it to a container widget:
Gtk::Toolbar* toolbar = nullptr;
m_refBuilder->get_widget("toolbar", toolbar);
if (!toolbar)
    g_warning("GtkToolbar not found");
else
    m_VBox.pack_start(*toolbar, Gtk::PACK_SHRINK);
}

```

---

```
void ExampleWindow::on_printoperation_status_changed()
{
    Glib::ustring status_msg;

    if (m_refPrintFormOperation->is_finished())
    {
        status_msg = "Print job completed.";
    }
    else
    {
        //You could also use get_status().
        status_msg = m_refPrintFormOperation->get_status_string();
    }

    m_Statusbar.push(status_msg, m_ContextId);
}

void ExampleWindow::on_printoperation_done(Gtk::PrintOperationResult ←
    result)
{
    //Printing is "done" when the print data is spooled.

    if (result == Gtk::PRINT_OPERATION_RESULT_ERROR)
    {
        Gtk::MessageDialog err_dialog(*this, "Error printing form", false,
            Gtk::MESSAGE_ERROR, Gtk::BUTTONS_OK, true);
        err_dialog.run();
    }
    else if (result == Gtk::PRINT_OPERATION_RESULT_APPLY)
    {
        //Update PrintSettings with the ones used in this PrintOperation:
        m_refSettings = m_refPrintFormOperation->get_print_settings();
    }

    if (!m_refPrintFormOperation->is_finished())
    {
        //We will connect to the status-changed signal to track status
        //and update a status bar. In addition, you can, for example,
        //keep a list of active print operations, or provide a progress dialog ←
        .
        m_refPrintFormOperation->signal_status_changed().connect(sigc::mem_fun ←
            (*this,
                &ExampleWindow::on_printoperation_status_changed));
    }
}
```

---



```

void ExampleWindow::print_or_preview(Gtk::PrintOperationAction &
    print_action)
{
    //Create a new PrintOperation with our PageSetup and PrintSettings:
    //(We use our derived PrintOperation class)
    m_refPrintFormOperation = PrintFormOperation::create();

    m_refPrintFormOperation->set_name(m_NameEntry.get_text() + " " +
        m_SurnameEntry.get_text());
    m_refPrintFormOperation->set_comments(m_refTextBuffer->get_text(false /*
        Don't include hidden*/));
    // In the printing/advanced example, the font will be set through a
        custom tab
    // in the print dialog.

    m_refPrintFormOperation->set_track_print_status();
    m_refPrintFormOperation->set_default_page_setup(m_refPageSetup);
    m_refPrintFormOperation->set_print_settings(m_refSettings);

    m_refPrintFormOperation->signal_done().connect(sigc::mem_fun(*this,
        &ExampleWindow::on_printoperation_done));
    try
    {
        m_refPrintFormOperation->run(print_action /* print or preview */, *
            this);
    }
    catch (const Gtk::PrintError& ex)
    {
        //See documentation for exact Gtk::PrintError error codes.
        std::cerr << "An error occurred while trying to run a print operation
            : "
            << ex.what() << std::endl;
    }
}

void ExampleWindow::on_menu_file_new()
{
    //Clear entries and textview:
    m_NameEntry.set_text("");
    m_SurnameEntry.set_text("");
    m_refTextBuffer->set_text("");
    m_TextView.set_buffer(m_refTextBuffer);
}

void ExampleWindow::on_menu_file_page_setup()
{
    //Show the page setup dialog, asking it to start with the existing

```

---

```
        settings:
        auto new_page_setup =
            Gtk::run_page_setup_dialog(*this, m_refPageSetup, m_refSettings);

        //Save the chosen page setup dialog for use when printing, previewing, ↵
        or
        //showing the page setup dialog again:
        m_refPageSetup = new_page_setup;
    }

void ExampleWindow::on_menu_file_print_preview()
{
    print_or_preview(Gtk::PRINT_OPERATION_ACTION_PREVIEW);
}

void ExampleWindow::on_menu_file_print()
{
    print_or_preview(Gtk::PRINT_OPERATION_ACTION_PRINT_DIALOG);
}

void ExampleWindow::on_menu_file_quit()
{
    hide();
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char* argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window(app);

    // Shows the window and returns when it is closed.
    return app->run(window);
}
```

**File: printformoperation.cc (For use with gtkmm 3)**

```
#include "printformoperation.h"

PrintFormOperation::PrintFormOperation()
{
}
```

---

```
PrintFormOperation::~PrintFormOperation()
{
}

Glib::RefPtr<PrintFormOperation> PrintFormOperation::create()
{
    return Glib::RefPtr<PrintFormOperation>(new PrintFormOperation());
}

void PrintFormOperation::on_begin_print(
    const Glib::RefPtr<Gtk::PrintContext>& print_context)
{
    //Create and set up a Pango layout for PrintData based on the passed
    //PrintContext: We then use this to calculate the number of pages needed ←→
    // , and
    //the lines that are on each page.
    m_refLayout = print_context->create_pango_layout();

    Pango::FontDescription font_desc("sans 12");
    m_refLayout->set_font_description(font_desc);

    const double width = print_context->get_width();
    const double height = print_context->get_height();

    m_refLayout->set_width(static_cast<int>(width * Pango::SCALE));

    //Set and mark up the text to print:
    Glib::ustring marked_up_form_text;
    marked_up_form_text += "<b>Name</b>: " + m_Name + "\n\n";
    marked_up_form_text += "<b>Comments</b>: " + m_Comments;

    m_refLayout->set_markup(marked_up_form_text);

    //Set the number of pages to print by determining the line numbers
    //where page breaks occur:
    const int line_count = m_refLayout->get_line_count();

    Glib::RefPtr<Pango::LayoutLine> layout_line;
    double page_height = 0;

    for (int line = 0; line < line_count; ++line)
    {
        Pango::Rectangle ink_rect, logical_rect;

        layout_line = m_refLayout->get_line(line);
        layout_line->get_extents(ink_rect, logical_rect);
    }
}
```

---

```
    const double line_height = logical_rect.get_height() / 1024.0;

    if (page_height + line_height > height)
    {
        m_PageBreaks.push_back(line);
        page_height = 0;
    }

    page_height += line_height;
}

set_n_pages(m_PageBreaks.size() + 1);
}

void PrintFormOperation::on_draw_page(
    const Glib::RefPtr<Gtk::PrintContext>& print_context, int page_nr)
{
    //Decide which lines we need to print in order to print the specified ↵
    page:
    int start_page_line = 0;
    int end_page_line = 0;

    if(page_nr == 0)
    {
        start_page_line = 0;
    }
    else
    {
        start_page_line = m_PageBreaks[page_nr - 1];
    }

    if(page_nr < static_cast<int>(m_PageBreaks.size()))
    {
        end_page_line = m_PageBreaks[page_nr];
    }
    else
    {
        end_page_line = m_refLayout->get_line_count();
    }

    //Get a Cairo Context, which is used as a drawing board:
    Cairo::RefPtr<Cairo::Context> cairo_ctx = print_context-> ↵
        get_cairo_context();

    //We'll use black letters:
    cairo_ctx->set_source_rgb(0, 0, 0);
}
```

---

```
//Render Pango LayoutLines over the Cairo context:
Pango::LayoutIter iter = m_refLayout->get_iter();

double start_pos = 0;
int line_index = 0;

do
{
    if(line_index >= start_page_line)
    {
        auto layout_line = iter.get_line();
        Pango::Rectangle logical_rect = iter.get_line_logical_extents();
        int baseline = iter.get_baseline();

        if (line_index == start_page_line)
        {
            start_pos = logical_rect.get_y() / 1024.0;
        }

        cairo_ctx->move_to(logical_rect.get_x() / 1024.0,
            baseline / 1024.0 - start_pos);

        layout_line->show_in_cairo_context(cairo_ctx);
    }

    line_index++;
}
while(line_index < end_page_line && iter.next_line());
}
```

## Chapter 21

# Recently Used Documents

gtkmm provides an easy way to manage recently used documents. The classes involved in implementing this functionality are `RecentManager`, `RecentChooserDialog`, `RecentChooserMenu`, `RecentChooserWidget`, and `RecentFilter`.

Each item in the list of recently used files is identified by its URI, and can have associated metadata. The metadata can be used to specify how the file should be displayed, a description of the file, its mime type, which application registered it, whether it's private to the registering application, and several other things.

### 21.1 RecentManager

`RecentManager` acts as a database of recently used files. You use this class to register new files, remove files from the list, or look up recently used files. There is one list of recently used files per user.

You can create a new `RecentManager`, but you'll most likely just want to use the default one. You can get a reference to the default `RecentManager` with `get_default()`.

`RecentManager` is the model of a model-view pattern, where the view is a class that implements the `RecentChooser` interface.

#### 21.1.1 Adding Items to the List of Recent Files

To add a new file to the list of recent documents, in the simplest case, you only need to provide the URI. For example:

```
Glib::RefPtr<Gtk::RecentManager> recent_manager = Gtk::RecentManager:: ←  
    get_default();  
recent_manager->add_item(uri);
```

If you want to register a file with metadata, you can pass a `RecentManager::Data` parameter to `add_item()`. The metadata that can be set on a particular file item is as follows:

- `app_exec`: The command line to be used to launch this resource. This string may contain the "f" and "u" escape characters which will be expanded to the resource file path and URI respectively
- `app_name`: The name of the application that registered the resource
- `description`: A short description of the resource as a UTF-8 encoded string
- `display_name`: The name of the resource to be used for display as a UTF-8 encoded string
- `groups`: A list of groups associated with this item. Groups are essentially arbitrary strings associated with a particular resource. They can be thought of as 'categories' (such as "email", "graphics", etc) or tags for the resource.
- `is_private`: Whether this resource should be visible only to applications that have registered it or not
- `mime_type`: The MIME type of the resource

In addition to adding items to the list, you can also look up items from the list and modify or remove items.

### 21.1.2 Looking up Items in the List of Recent Files

To look up recently used files, `RecentManager` provides several functions. To look up a specific item by its URI, you can use the `lookup_item()` function, which will return a `RecentInfo` class. If the specified URI did not exist in the list of recent files, `lookup_item()` throws a `RecentManagerError` exception. For example:

```
Glib::RefPtr<Gtk::RecentInfo> info;
try
{
    info = recent_manager->lookup_item(uri);
}
catch(const Gtk::RecentManagerError& ex)
{
    std::cerr << "RecentManagerError: " << ex.what() << std::endl;
}
if (info)
{
    // item was found
}
```

A `RecentInfo` object is essentially an object containing all of the metadata about a single recently-used file. You can use this object to look up any of the properties listed [above](#).

If you don't want to look for a specific URI, but instead want to get a list of all recently used items, `RecentManager` provides the `get_items()` function. The return value of this function is a `std::vector` of all recently used files. The following code demonstrates how you might get a list of recently used files:

```
std::vector< Glib::RefPtr<Gtk::RecentInfo> > info_list = recent_manager-> ↵  
    get_items();
```

The maximum age of items in the recently used files list can be set with `Gtk::Settings::property_gtk_recent_files_max_age`. Default value: 30 days.

### 21.1.3 Modifying the List of Recent Files

There may be times when you need to modify the list of recent files. For instance, if a file is moved or renamed, you may need to update the file's location in the recent files list so that it doesn't point to an incorrect location. You can update an item's location by using `move_item()`.

In addition to changing a file's URI, you can also remove items from the list, either one at a time or by clearing them all at once. The former is accomplished with `remove_item()`, the latter with `purge_items()`.

---

#### Note

The functions `move_item()`, `remove_item()` and `purge_items()` have no effect on the actual files that are referred to by the URIs, they only modify the list of recent files.

---

## 21.2 RecentChooser

`RecentChooser` is an interface that can be implemented by widgets displaying the list of recently used files. `gtkmm` provides four built-in implementations for choosing recent files: `RecentChooserWidget`, `RecentChooserDialog`, `RecentChooserMenu`, and the deprecated `RecentAction`.

`RecentChooserWidget` is a simple widget for displaying a list of recently used files. `RecentChooserWidget` is the basic building block for `RecentChooserDialog`, but you can embed it into your user interface if you want to.

`RecentChooserMenu` allows you to list recently used files as a menu.

---



### 21.2.1 Simple RecentChooserDialog example

Shown below is a simple example of how to use the `RecentChooserDialog` class in a program. This simple program has a menubar with a Recent Files Dialog menu item. When you select this menu item, a dialog pops up showing the list of recently used files.


---

**Note**

If this is the first time you're using a program that uses the Recent Files framework, the dialog may be empty at first. Otherwise it should show the list of recently used documents registered by other applications.

---

After selecting the Recent Files Dialog menu item, you should see something similar to the following window.



### Source Code

File: examplewindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow(const Glib::RefPtr<Gtk::Application>& app);
```

```

    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_menu_file_recent_files_item();
    void on_menu_file_recent_files_dialog();
    void on_menu_file_quit();
    void on_menu_file_new();

    //Child widgets:
    Gtk::Box m_Box;

    Glib::RefPtr<Gtk::Builder> m_refBuilder;
    Glib::RefPtr<Gio::SimpleActionGroup> m_refActionGroup;

    Glib::RefPtr<Gtk::RecentManager> m_refRecentManager;
};

#endif //GTKMM_EXAMPLEWINDOW_H

```

**File:** examplewindow.cc (For use with gtkmm 3)

```

#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow(const Glib::RefPtr<Gtk::Application>& app)
: m_Box(Gtk::ORIENTATION_VERTICAL),
  m_refRecentManager(Gtk::RecentManager::get_default())
{
    set_title("recent files example");
    set_default_size(200, 200);

    //We can put a MenuBar at the top of the box and other stuff below it.
    add(m_Box);

    //Create actions for menus and toolbars:
    m_refActionGroup = Gio::SimpleActionGroup::create();

    //File menu:
    m_refActionGroup->add_action("new",
        sigc::mem_fun(*this, &ExampleWindow::on_menu_file_new));

    //A menu item to open the recent-files dialog:
    m_refActionGroup->add_action("recent-files-dialog",
        sigc::mem_fun(*this, &ExampleWindow::on_menu_file_recent_files_dialog) ←
    );

    m_refActionGroup->add_action("quit",

```

```

    sigc::mem_fun(*this, &ExampleWindow::on_menu_file_quit) );

    insert_action_group("example", m_refActionGroup);

    m_refBuilder = Gtk::Builder::create();

    // When the menubar is a child of a Gtk::Window, keyboard accelerators ↵
    // are not
    // automatically fetched from the Gio::Menu.
    // See the examples/book/menus/main_menu example for an alternative way ↵
    // of
    // adding the menubar when using Gtk::ApplicationWindow.
    app->set_accel_for_action("example.new", "<Primary>n");
    app->set_accel_for_action("example.recent-files-dialog", "<Primary>o");
    app->set_accel_for_action("example.quit", "<Primary>q");

    //Layout the actions in a menubar and a toolbar:
    const char* ui_info =
        "<interface>"
        "  <menu id='menubar'>"
        "    <submenu>"
        "      <attribute name='label' translatable='yes'>_File</attribute>"
        "      <item>"
        "        <attribute name='label' translatable='yes'>_New</attribute>"
        "        <attribute name='action'>example.new</attribute>"
        "        <attribute name='accel'>&lt;Primary&gt;n</attribute>"
        "      </item>"
        "      <item>"
        "        <attribute name='label' translatable='yes'>Recent Files ↵
        _Dialog</attribute>"
        "        <attribute name='action'>example.recent-files-dialog</ ↵
        attribute>"
        "        <attribute name='accel'>&lt;Primary&gt;o</attribute>"
        "      </item>"
        "      <item>"
        "        <attribute name='label' translatable='yes'>_Quit</attribute>"
        "        <attribute name='action'>example.quit</attribute>"
        "        <attribute name='accel'>&lt;Primary&gt;q</attribute>"
        "      </item>"
        "    </submenu>"
        "  </menu>"
        "  <object class='GtkToolbar' id='toolbar'>"
        "    <property name='visible'>True</property>"
        "    <property name='can_focus'>False</property>"
        "    <child>"
        "      <object class='GtkToolButton' id='toolbutton_new'>"

```

---

```

"      <property name='visible'>True</property>"
"      <property name='can_focus'>False</property>"
"      <property name='tooltip_text' translatable='yes'>New</ ↵
property>"
"      <property name='action_name'>example.new</property>"
"      <property name='icon_name'>document-new</property>"
"    </object>"
"    <packing>"
"      <property name='expand'>False</property>"
"      <property name='homogeneous'>True</property>"
"    </packing>"
"  </child>"
"  <child>"
"    <object class='GtkToolButton' id='toolbutton_quit'>"
"      <property name='visible'>True</property>"
"      <property name='can_focus'>False</property>"
"      <property name='tooltip_text' translatable='yes'>Quit</ ↵
property>"
"      <property name='action_name'>example.quit</property>"
"      <property name='icon_name'>application-exit</property>"
"    </object>"
"    <packing>"
"      <property name='expand'>False</property>"
"      <property name='homogeneous'>True</property>"
"    </packing>"
"  </child>"
" </object>"
"</interface>";

try
{
  m_refBuilder->add_from_string(ui_info);
}
catch(const Glib::Error& ex)
{
  std::cerr << "building menubar and toolbar failed: " << ex.what();
}

//Get the menubar and toolbar widgets, and add them to a container ↵
widget:
auto object = m_refBuilder->get_object("menubar");
auto gmenu = Glib::RefPtr<Gio::Menu>::cast_dynamic(object);
if (gmenu)
{
  //Menubar:
  auto pMenubar = Gtk::make_managed<Gtk::MenuBar>(gmenu);
  m_Box.pack_start(*pMenubar, Gtk::PACK_SHRINK);
}

```

---

```
}
else
    g_warning("GMenu not found");

    Gtk::Toolbar* pToolbar = nullptr;
    m_refBuilder->get_widget("toolbar", pToolbar);
    if (pToolbar)
        //Toolbar:
        m_Box.pack_start(*pToolbar, Gtk::PACK_SHRINK);
    else
        g_warning("GtkToolbar not found");

    show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_menu_file_new()
{
    std::cout << " New File" << std::endl;
}

void ExampleWindow::on_menu_file_quit()
{
    hide(); //Closes the main window to stop the app->run().
}

void ExampleWindow::on_menu_file_recent_files_dialog()
{
    Gtk::RecentChooserDialog dialog(*this, "Recent Files", ←
        m_refRecentManager);
    dialog.add_button("Select File", Gtk::RESPONSE_OK);
    dialog.add_button("_Cancel", Gtk::RESPONSE_CANCEL);

    const int response = dialog.run();
    dialog.hide();
    if(response == Gtk::RESPONSE_OK)
    {
        std::cout << "URI selected = " << dialog.get_current_uri() << std:: ←
            endl;
    }
}
```

File: main.cc (For use with gtkmm 3)

---

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window(app);

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

The constructor for `ExampleWindow` creates the menu and the toolbar using `Builder` (see [Chapter 12](#) for more information). It then adds the menu and the toolbar to the window.

### 21.2.2 Filtering Recent Files

For any of the `RecentChooser` classes, if you don't wish to display all of the items in the list of recent files, you can filter the list to show only those that you want. You can filter the list with the help of the `RecentFilter` class. This class allows you to filter recent files by their name (`add_pattern()`), their mime type (`add_mime_type()`), the application that registered them (`add_application()`), or by a custom filter function (`add_custom()`). It also provides the ability to filter based on how long ago the file was modified and which groups it belongs to.

After you've created and set up the filter to match only the items you want, you can apply a filter to a chooser widget with the `RecentChooser::add_filter()` function.

## Chapter 22

# Plugs and Sockets

### 22.1 Overview

From time to time, it may be useful to be able to embed a widget from another application within your application. `gtkmm` allows you to do this with the `Gtk::Socket` and `Gtk::Plug` classes. It is not anticipated that very many applications will need this functionality, but in the rare case that you need to display a widget that is running in a completely different process, these classes can be very helpful.

The communication between a `Socket` and a `Plug` follows the XEmbed protocol. This protocol has also been implemented in other toolkits (e.g. Qt), which allows the same level of integration when embedding a Qt widget in GTK+ or vice versa.

The way that `Sockets` and `Plugs` work together is through their window ids. Both a `Socket` and a `Plug` have IDs that can be retrieved with their `get_id()` member functions. The use of these IDs will be explained below in Section [22.1.3](#).

#### 22.1.1 Sockets

A `Socket` is a special kind of container widget that provides the ability to embed widgets from one process into another process in a way that is transparent to the user.

#### 22.1.2 Plugs

A `Plug` is a special kind of `Window` that can be plugged into a `Socket`. Besides the normal properties and methods of `Gtk::Window`, a `Plug` provides a constructor that takes the ID of a `Socket`, which will automatically embed the `Plug` into the `Socket` that matches that ID.

Since a `Plug` is just a special type of `Gtk::Window` class, you can add containers or widgets to it like you would to any other window.

---



### 22.1.3 Connecting Plugs and Sockets

After a `Socket` or `Plug` object is realized, you can obtain its ID with its `get_id()` function. This ID can then be shared with other processes so that other processes know how to connect to each other.

There are two basic strategies that can be used:

- Create a `Socket` object in one process and pass the ID of that `Socket` to another process so that it can create a `Plug` object by specifying the given `Socket` ID in its constructor. There is no way to assign a `Plug` to a particular `Socket` after creation, so you must pass the `Socket` ID to the `Plug`'s constructor.
- Create a `Plug` independantly from any particular `Socket` and pass the ID of the `Plug` to other processes that need to use it. The ID of the `Plug` can be associated with a particular `Socket` object using the `Socket::add_id()` function. This is the approach used in the example below.

## 22.2 Plugs and Sockets Example

The following is a simple example of using sockets and plugs. The method of communication between processes is deliberately kept very simple: The `Plug` writes its ID out to a text file named `plug.id` and the process with the socket reads the ID from this file. In a real program, you may want to use a more sophisticated method of inter-process communication.

### Source Code

File: `plug.cc` (For use with `gtkmm 3`)

```
#include <iostream>
#include <fstream>
#include <gtkmm.h>
#include <gtkmm/plug.h>
#include <glib/gstdio.h>

using namespace std;

const char* id_filename = "plug.id";

void on_embed()
{
    cout << "I've been embedded." << endl;
}

class MyPlug : public Gtk::Plug
{
public:
    MyPlug() :
```

```

        m_label("I am the plug")
    {
        set_size_request(150, 100);
        add(m_label);
        signal_embedded().connect(sigc::ptr_fun(on_embed));
        show_all_children();
    }

private:
    Gtk::Label m_label;
};

int main(int argc, char** argv)
{
    // The plug and the socket have different application ids, so they can ↵
    run
    // simultaneously.
    auto app =
        Gtk::Application::create(argc, argv, "org.gtkmm.example.plug");
    MyPlug plug;
    plug.show();

    ofstream out(id_filename);
    out << plug.get_id();
    out.close();
    cout << "The window ID is: " << plug.get_id() << endl;

    app->run(plug);

    // remove the ID file when the program exits
    g_remove(id_filename);
    return 0;
}

```

**File: socket.cc (For use with gtkmm 3)**

```

#include <iostream>
#include <fstream>
#include <gtkmm.h>
#include <gtkmm/socket.h>

using namespace std;

const char* id_filename = "plug.id";

void plug_added()
{

```

```
    cout << "A plug was added" << endl;
}

bool plug_removed()
{
    cout << "A Plug was removed" << endl;
    return true;
}

class MySocketWindow : public Gtk::Window
{
public:
    MySocketWindow()
    {
        ifstream infile(id_filename);
        if (infile)
        {
            auto socket = Gtk::make_managed<Gtk::Socket>();
            add(*socket);
            socket->signal_plug_added().connect(sigc::ptr_fun(plug_added));
            socket->signal_plug_removed().connect(sigc::ptr_fun(plug_removed)) ←
                ;
            ::Window plug_id = 0;
            infile >> plug_id;
            infile.close();
            socket->add_id(plug_id);
        }
        else
        {
            auto label = Gtk::make_managed<Gtk::Label>(
                "Plug id file not found.\n Make sure plug is running.");
            add(*label);
            set_size_request(150, 50);
        }
        show_all();
    }
};

int main(int argc, char** argv)
{
    // The plug and the socket have different application ids, so they can ←
    // run
    // simultaneously.
    auto app =
        Gtk::Application::create(argc, argv, "org.gtkmm.example.socket");
    MySocketWindow win;
    app->run(win);
}
```

---

```
    return 0;
}
```

This example creates two executable programs: `socket` and `plug`. The idea is that `socket` has an application window that will embed a widget from the `plug` program. The way this example is designed, `plug` must be running first before starting `socket`. To see the example in action, execute the following commands in order from within the example directory:

Start the `plug` program and send it to the background (or just use a different terminal).

```
$ ./plug &
```

After which you should see something like the following:

```
The window ID is: 69206019
```


Then start the `socket` program:

```
$ ./socket
```

After starting `socket`, you should see the following output in the terminal:


```
I've been embedded.  
A plug was added
```

The first line of output is from `plug`, after it has been notified that it has been embedded inside of a `Socket`. The second line was emitted by `socket` in response to its `plug_added` signal. If everything was done as described above, the `socket` window should look roughly like the following:



If for some reason the `Socket` couldn't attach the `Plug`, the window would look something like this:

---



## Chapter 23

# Keyboard Events

X events differ in some ways from other signals. These differences are described in the [X Event signals](#) section in the appendix. Here we will use keyboard events to show how X events can be used in a program.

### 23.1 Overview

Whenever you press or release a key, an event is emitted. You can connect a signal handler to handle such events.

To receive the keyboard events, you must first call the `Gtk::Widget::add_events()` function with a bit mask of the events you're interested in. The event signal handler will receive an argument that depends on the type of event. For keyboard events it's a `GdkEventKey*`. As described in the [appendix](#), the event signal handler returns a `bool` value, to indicate that the signal is fully handled (`true`) or allow event propagation (`false`).

To determine which key was pressed or released, you read the value of `GdkEventKey::keyval` and compare it with a constant in the `<gdk/gdkkeysyms.h>` header file. The states of modifier keys (shift, ctrl, etc.) are available as bit-flags in `GdkEventKey::state`.

Here's a simple example:

```
bool on_key_press_or_release_event(GdkEventKey* event)
{
    if (event->type == GDK_KEY_PRESS &&
        event->keyval == GDK_KEY_1 &&
        (event->state & (GDK_SHIFT_MASK | GDK_CONTROL_MASK | GDK_MOD1_MASK)) == GDK_MOD1_MASK)
    {
        handle_alt_1_press(); // GDK_MOD1_MASK is normally the Alt key
    }
}
```

```

    return true;
}
return false;
}

Gtk::Entry m_entry; // in a class definition

// in the class constructor
m_entry.signal_key_press_event().connect( sigc::ptr_fun(& ↵
    on_key_press_or_release_event) );
m_entry.signal_key_release_event().connect( sigc::ptr_fun(& ↵
    on_key_press_or_release_event) );
m_entry.add_events(Gdk::KEY_PRESS_MASK | Gdk::KEY_RELEASE_MASK);

```

### 23.1.1 Example

In this example there are three keyboard shortcuts: **Alt+1** selects the first radio button, **Alt+2** selects the second one, and the **Esc** key hides (closes) the window. The default event signal handler is overridden, as described in the [Overriding default signal handlers](#) section in the appendix.




Figure 23.1: Keyboard Events - Simple

#### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```

#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:

    ExampleWindow();
    virtual ~ExampleWindow();

```

```
private:
    //Override default signal handler:
    bool on_key_press_event(GdkEventKey* event) override;

    Gtk::Grid m_container;
    Gtk::RadioButton m_first;
    Gtk::RadioButton m_second;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
{
    set_title("Keyboard Events");
    set_border_width(10);
    add(m_container);

    // Radio buttons:
    m_first.set_label("First");
    m_second.set_label("Second");

    m_second.join_group(m_first);
    m_first.set_active();

    // Main Container:
    m_container.add(m_first);
    m_container.add(m_second);

    // Events.
    // We override the default event signal handler.
    add_events(Gdk::KEY_PRESS_MASK);

    show_all_children();
}

bool ExampleWindow::on_key_press_event(GdkEventKey* key_event)
{
    //GDK_MOD1_MASK -> the 'alt' key (mask)
    //GDK_KEY_1 -> the '1' key
    //GDK_KEY_2 -> the '2' key

    //select the first radio button, when we press alt + 1
    if((key_event->keyval == GDK_KEY_1) &&
```



```

        (key_event->state & (GDK_SHIFT_MASK | GDK_CONTROL_MASK | GDK_MOD1_MASK) <=
        ) == GDK_MOD1_MASK)
    {
        m_first.set_active();
        //returning true, cancels the propagation of the event
        return true;
    }
    else if((key_event->keyval == GDK_KEY_2) &&
        (key_event->state & (GDK_SHIFT_MASK | GDK_CONTROL_MASK | GDK_MOD1_MASK <=
        )) == GDK_MOD1_MASK)
    {
        //and the second radio button, when we press alt + 2
        m_second.set_active();
        return true;
    }
    else if(key_event->keyval == GDK_KEY_Escape)
    {
        //close the window, when the 'esc' key is pressed
        hide();
        return true;
    }

    //if the event has not been handled, call the base class
    return Gtk::Window::on_key_press_event(key_event);
}

ExampleWindow::~ExampleWindow()
{
}

```

#### File: main.cc (For use with gtkmm 3)

```

#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}

```

## 23.2 Event Propagation

Event propagation means that, when an event is emitted on a particular widget, it can be passed to its parent widget (and that widget can pass it to its parent, and so on) and, if the parent has an event handler, that handler will be called.

Contrary to other events, keyboard events are first sent to the toplevel window (`Gtk::Window`), where it will be checked for any keyboard shortcuts that may be set (accelerator keys and mnemonics, used for selecting menu items from the keyboard). After this (and assuming the event wasn't handled), it is sent to the widget which has focus, and the propagation begins from there.

The event will propagate until it reaches the top-level widget, or until you stop the propagation by returning `true` from an event handler.

Notice, that after canceling an event, no other function will be called (even if it is from the same widget).

### 23.2.1 Example

In this example there are three event handlers that are called after `Gtk::Window`'s default event handler, one in the `Gtk::Entry`, one in the `Gtk::Grid` and one in the `Gtk::Window`.

In the `Gtk::Window`, we have also the default handler overridden (`on_key_release_event()`), and another handler being called before the default handler (`windowKeyReleaseBefore()`).

The purpose of this example is to show the steps the event takes when it is emitted.

When you write in the entry, a key release event will be emitted, which will go first to the toplevel window (`Gtk::Window`), since we have one event handler set to be called before, that's what is called first (`windowKeyReleaseBefore()`). Then the default handler is called (which we have overridden), and after that the event is sent to the widget that has focus, the `Entry` in our example and, depending on whether we let it propagate, it can reach the `Grid`'s and the `Window`'s event handlers. If it propagates, the text you're writing will appear in the `Label` above the `Entry`.



Figure 23.2: Keyboard Events - Event Propagation

## Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EVENT_PROPAGATION_H
#define GTKMM_EVENT_PROPAGATION_H

#include <gtkmm.h>

class ExampleWindow : public Gtk::Window
{
public:

    ExampleWindow();
    virtual ~ExampleWindow();

private:
    //Override default signal handler:
    bool on_key_release_event(GdkEventKey* event) override;

    bool entryKeyRelease(GdkEventKey* event);
    bool gridKeyRelease(GdkEventKey* event);
    bool windowKeyReleaseBefore(GdkEventKey* event);
    bool windowKeyRelease(GdkEventKey* event);

    Gtk::Grid m_container;

    Gtk::Label m_label;
    Gtk::Entry m_entry;
    Gtk::CheckButton m_checkbutton_can_propagate;
};

#endif //GTKMM_EVENT_PROPAGATION_H
```

File: `examplewindow.cc` (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow()
{
    add(m_container);
    set_title("Event Propagation");
    set_border_width(10);

    m_label.set_label("A label");
    m_checkbutton_can_propagate.set_label("Can Propagate");
    m_checkbutton_can_propagate.set_active();
}
```

```
// Main Container
m_container.set_orientation(Gtk::ORIENTATION_VERTICAL);
m_container.add(m_label);
m_container.add(m_entry);
m_container.add(m_checkbutton_can_propagate);

// Events
add_events(Gdk::KEY_RELEASE_MASK);

m_entry.signal_key_release_event().connect(
    sigc::mem_fun(*this, &ExampleWindow::entryKeyRelease));

m_container.signal_key_release_event().connect(
    sigc::mem_fun(*this, &ExampleWindow::gridKeyRelease));

// Called before the default event signal handler.
signal_key_release_event().connect(
    sigc::mem_fun(*this, &ExampleWindow::windowKeyReleaseBefore), false);

// Called after the default event signal handler.
signal_key_release_event().connect(
    sigc::mem_fun(*this, &ExampleWindow::windowKeyRelease));

show_all_children();
}

//By changing the return value we allow, or don't allow, the event to ↔
propagate to other elements.
bool ExampleWindow::entryKeyRelease(GdkEventKey* /* event */)
{
    std::cout << "Entry" << std::endl;

    if(m_checkbutton_can_propagate.get_active())
    {
        return false;
    }

    return true;
}

bool ExampleWindow::gridKeyRelease(GdkEventKey* /* event */)
{
    std::cout << "Grid" << std::endl;

    //Let it propagate:
    return false;
}
```

---

```
}

bool ExampleWindow::windowKeyReleaseBefore(GdkEventKey* /* event */ )
{
    std::cout << "Window before" << std::endl;
    return false;
}

bool ExampleWindow::on_key_release_event(GdkEventKey* key_event)
{
    std::cout << "Window overridden" << std::endl;

    // call base class function (to get the normal behaviour)
    return Gtk::Window::on_key_release_event(key_event);
}

// This will set the entry's text in the label, every time a key is ↵
// pressed.
bool ExampleWindow::windowKeyRelease(GdkEventKey* /* event */ )
{
    std::cout << "Window after";

    //checking if the entry is on focus, otherwise the label would get ↵
    // changed by pressing keys
    //on the window (when the entry is not on focus), even if ↵
    // m_checkbutton_can_propagate wasn't active
    if(m_entry.has_focus())
    {
        m_label.set_text(m_entry.get_text());
        std::cout << ", " << m_entry.get_text();
    }
    std::cout << std::endl;

    return true;
}

ExampleWindow::~ExampleWindow()
{
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
```

```
auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

ExampleWindow window;

//Shows the window and returns when it is closed.
return app->run(window);
}
```

## Chapter 24

# Timeouts, I/O and Idle Functions

### 24.1 Timeouts

You may be wondering how to make gtkmm do useful work while it's idling along. Happily, you have several options. Using the following methods you can create a timeout method that will be called every few milliseconds.

```
sigc::connection Glib::SignalTimeout::connect(const sigc::slot<bool>& slot ↵  
'  
                                         unsigned int interval, int priority ↵  
                                         = Glib::PRIORITY_DEFAULT);
```

The first argument is a `slot` you wish to have called when the timeout occurs. The second argument is the number of milliseconds between calls to that method. You receive a `sigc::connection` object that can be used to deactivate the connection using its `disconnect()` method:

```
my_connection.disconnect();
```

Another way of destroying the connection is your signal handler. It has to be of the type `sigc::slot<bool>`. As you see from the definition your signal handler has to return a value of the type `bool`. A definition of a sample method might look like this:

```
bool MyCallback() { std::cout << "Hello World!\n" << std::endl; return ↵  
    true; }
```

You can stop the timeout method by returning `false` from your signal handler. Therefore, if you want your method to be called repeatedly, it should return `true`.

Here's an example of this technique:

---

## Source Code

File: timerexample.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_TIMEREXAMPLE_H
#define GTKMM_EXAMPLE_TIMEREXAMPLE_H

#include <gtkmm.h>
#include <iostream>
#include <map>

class TimerExample : public Gtk::Window
{
public:
    TimerExample();

protected:
    // signal handlers
    void on_button_add_timer();
    void on_button_delete_timer();
    void on_button_quit();

    // This is the callback function the timeout will call
    bool on_timeout(int timer_number);

    // Member data:

    Gtk::Box m_Box;
    Gtk::Button m_ButtonAddTimer, m_ButtonDeleteTimer, m_ButtonQuit;

    // Keep track of the timers being added:
    int m_timer_number;

    // These two constants are initialized in the constructor's member ↵
    // initializer:
    const int count_value;
    const int timeout_value;

    // STL map for storing our connections
    std::map<int, sigc::connection> m_timers;

    // STL map for storing our timer values.
    // Each timer counts back from COUNT_VALUE to 0 and is removed when it ↵
    // reaches 0
    std::map<int, int> m_counters;
};

#endif // GTKMM_EXAMPLE_TIMEREXAMPLE_H
```



File: main.cc (For use with gtkmm 3)

```
#include "timerexample.h"
#include <gtkmm/application.h>

int main (int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    TimerExample example;
    return app->run(example);
}
```

File: timerexample.cc (For use with gtkmm 3)

```
#include "timerexample.h"

TimerExample::TimerExample() :
    m_Box(Gtk::ORIENTATION_HORIZONTAL, 10),
    m_ButtonAddTimer("_Add", true),
    m_ButtonDeleteTimer("_Remove", true),
    m_ButtonQuit("_Quit", true),
    m_timer_number(0), // start numbering the timers at 0
    count_value(5), // each timer will count down 5 times before ←
                    // disconnecting
    timeout_value(1500) // 1500 ms = 1.5 seconds
{
    set_border_width(10);

    add(m_Box);
    m_Box.pack_start(m_ButtonAddTimer);
    m_Box.pack_start(m_ButtonDeleteTimer);
    m_Box.pack_start(m_ButtonQuit);

    // Connect the three buttons:
    m_ButtonQuit.signal_clicked().connect(sigc::mem_fun(*this,
        &TimerExample::on_button_quit));
    m_ButtonAddTimer.signal_clicked().connect(sigc::mem_fun(*this,
        &TimerExample::on_button_add_timer));
    m_ButtonDeleteTimer.signal_clicked().connect(sigc::mem_fun(*this,
        &TimerExample::on_button_delete_timer));

    show_all_children();
}

void TimerExample::on_button_quit()
{
    hide();
}
```

```
}

void TimerExample::on_button_add_timer()
{
    // Creation of a new object prevents long lines and shows us a little
    // how slots work. We have 0 parameters and bool as a return value
    // after calling sigc::bind.
    sigc::slot<bool> my_slot = sigc::bind(sigc::mem_fun(*this,
        &TimerExample::on_timeout), m_timer_number);

    // This is where we connect the slot to the Glib::signal_timeout()
    sigc::connection conn = Glib::signal_timeout().connect(my_slot,
        timeout_value);

    // Remember the connection:
    m_timers[m_timer_number] = conn;

    // Initialize timer count:
    m_counters[m_timer_number] = count_value + 1;

    // Print some info to the console for the user:
    std::cout << "added timeout " << m_timer_number++ << std::endl;
}

void TimerExample::on_button_delete_timer()
{
    // any timers?
    if(m_timers.empty())
    {
        // no timers left
        std::cout << "Sorry, there are no timers left." << std::endl;
    }
    else
    {
        // get the number of the first timer
        int timer_number = m_timers.begin()->first;

        // Give some info to the user:
        std::cout << "manually disconnecting timer " << timer_number
            << std::endl;

        // Remove the entry in the counter values
        m_counters.erase(timer_number);

        // Disconnect the signal handler:
        m_timers[timer_number].disconnect();
    }
}
```

---

```

        // Forget the connection:
        m_timers.erase(timer_number);
    }
}

bool TimerExample::on_timeout(int timer_number)
{
    // Print the timer:
    std::cout << "This is timer " << timer_number;

    // decrement and check counter value
    if (--m_counters[timer_number] == 0)
    {
        std::cout << " being disconnected" << std::endl;

        // delete the counter entry in the STL MAP
        m_counters.erase(timer_number);

        // delete the connection entry in the STL MAP
        m_timers.erase(timer_number);

        // Note that we do not have to explicitly call disconnect() on the
        // connection since Gtk::Main does this for us when we return false.
        return false;
    }

    // Print the timer value
    std::cout << " - " << m_counters[timer_number] << "/"
        << count_value << std::endl;

    // Keep going (do not disconnect yet):
    return true;
}

```

## 24.2 Monitoring I/O

A nifty feature of Glib (one of the libraries underlying gtkmm) is the ability to have it check for data on a file descriptor for you. This is especially useful for networking applications. The following method is used to do this:

```

sigc::connection Glib::SignalIO::connect(const sigc::slot<bool,Glib::IOCondition>& slot,
                                         int fd, Glib::IOCondition condition,
                                         int priority = Glib::PRIORITY_DEFAULT);

```

The first argument is a slot you wish to have called when the specified event (see argument 3) occurs on the file descriptor you specify using argument two. Argument three may be one or more (using `|`) of:

- `Glib::IO_IN` - Call your method when there is data ready for reading on your file descriptor.
- `Glib::IO_OUT` - Call your method when the file descriptor is ready for writing.
- `Glib::IO_PRI` - Call your method when the file descriptor has urgent data to be read.
- `Glib::IO_ERR` - Call your method when an error has occurred on the file descriptor.
- `Glib::IO_HUP` - Call your method when hung up (the connection has been broken usually for pipes and sockets).

The return value is a `sigc::connection` that may be used to stop monitoring this file descriptor using its `disconnect()` method. The `slot` signal handler should be declared as follows:

```
bool input_callback(Glib::IOCondition condition);
```

where `condition` is as specified above. As usual the slot is created with `sigc::mem_fun()` (for a member method of an object), or `sigc::ptr_fun()` (for a function).

A little example follows. To use the example just execute it from a terminal; it doesn't create a window. It will create a pipe named `testfifo` in the current directory. Then start another shell and execute `echo "Hello" > testfifo`. The example will print each line you enter until you execute `echo "Q" > testfifo`.

### Source Code

File: `main.cc` (For use with gtkmm 3)

```
#include <gtkmm/application.h>
#include <glibmm/main.h>
#include <glibmm/iochannel.h>
#include <fcntl.h>
#include <iostream>

#include <unistd.h> //The SUN Forte compiler puts F_OK here.

//The SUN Forte compiler needs these for mkfifo:
#include <sys/types.h>
#include <sys/stat.h>

Glib::RefPtr<Gtk::Application> app;

int read_fd;
Glib::RefPtr<Glib::IOChannel> iochannel;
```

```
/*
    send to the fifo with:
    echo "Hello" > testfifo

    quit the program with:
    echo "Q" > testfifo
*/

// this will be our signal handler for read operations
// it will print out the message sent to the fifo
// and quit the program if the message was 'Q'.
bool MyCallback(Glib::IOCondition io_condition)
{
    if ((io_condition & Glib::IO_IN) == 0) {
        std::cerr << "Invalid fifo response" << std::endl;
    }
    else {
        Glib::ustring buf;

        iochannel->read_line(buf);
        std::cout << buf;
        if (buf == "Q\n")
            app->quit();
    }
    return true;
}

int main(int argc, char *argv[])
{
    app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    if (access("testfifo", F_OK) == -1) {
        // fifo doesn't exist - create it
        #ifndef DONT_HAVE_MKFIFO
        if (mkfifo("testfifo", 0666) != 0) {
            std::cerr << "error creating fifo" << std::endl;
            return -1;
        }
        #else
        std::cerr << "error creating fifo: This platform does not have ↵
            mkfifo()"
            << std::endl;
        #endif //DONT_HAVE_MKFIFO
    }
}
```

```

// Although we will only read from the fifo, we open it in read/write ↵
mode.
// Due to a peculiarity with the poll() system call, used deep down in ↵
glib,
// this small program will use all available CPU time, if the fifo is ↵
opened
// as O_RDONLY. See a discussion on the gtkmm-list, e.g.
// https://mail.gnome.org/archives/gtkmm-list/2015-September/msg00034. ↵
html
// and the link from there to stackoverflow.
read_fd = open("testfifo", O_RDWR);
if (read_fd == -1)
{
    std::cerr << "error opening fifo" << std::endl;
    return -1;
}

// connect the signal handler
Glib::signal_io().connect(sigc::ptr_fun(MyCallback), read_fd, Glib:: ↵
IO_IN);

// Creates a iochannel from the file descriptor
iochannel = Glib::IOChannel::create_from_fd(read_fd);

// and last but not least - run the application main loop
app->hold(); // keep the application running without a window
app->run();

// now remove the temporary fifo
if(unlink("testfifo"))
    std::cerr << "error removing fifo" << std::endl;

return 0;
}

```

## 24.3 Idle Functions

If you want to specify a method that gets called when nothing else is happening, use the following:

```

sigc::connection Glib::SignalIdle::connect(const sigc::slot<bool>& slot,
                                           int priority = Glib:: ↵
                                           PRIORITY_DEFAULT_IDLE);

```

This causes gtkmm to call the specified method whenever nothing else is happening. You can add a priority (lower numbers are higher priorities). There are two ways to remove the signal handler: calling

`disconnect()` on the `sigc::connection` object, or returning `false` in the signal handler, which should be declared as follows:

```
bool idleFunc();
```

Since this is very similar to the methods above this explanation should be sufficient to understand what's going on. However, here's a little example:

### Source Code

File: `idleexample.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_IDLEEXAMPLE_H
#define GTKMM_EXAMPLE_IDLEEXAMPLE_H

#include <gtkmm.h>
#include <iostream>

class IdleExample : public Gtk::Window
{
public:
    IdleExample();

protected:
    // Signal Handlers:
    bool on_timer();
    bool on_idle();
    void on_button_clicked();

    // Member data:
    Gtk::Box m_Box;
    Gtk::Button m_ButtonQuit;
    Gtk::ProgressBar m_ProgressBar_c;
    Gtk::ProgressBar m_ProgressBar_d;
};

#endif // GTKMM_EXAMPLE_IDLEEXAMPLE_H
```

File: `idleexample.cc` (For use with gtkmm 3)

```
#include "idleexample.h"

IdleExample::IdleExample() :
    m_Box(Gtk::ORIENTATION_VERTICAL, 5),
    m_ButtonQuit("_Quit", true)
{
    set_border_width(5);

    // Put buttons into container
```

```

// Adding a few widgets:
add(m_Box);
m_Box.pack_start(*Gtk::make_managed<Gtk::Label>("Formatting Windows ↵
    drive C:"));
m_Box.pack_start(*Gtk::make_managed<Gtk::Label>("100 MB"));
m_Box.pack_start(m_ProgressBar_c);

m_Box.pack_start(*Gtk::make_managed<Gtk::Label>(""));

m_Box.pack_start(*Gtk::make_managed<Gtk::Label>("Formatting Windows ↵
    drive D:"));
m_Box.pack_start(*Gtk::make_managed<Gtk::Label>("5000 MB"));
m_Box.pack_start(m_ProgressBar_d);

auto hbox = Gtk::make_managed<Gtk::Box>(Gtk::ORIENTATION_HORIZONTAL,10);
m_Box.pack_start(*hbox);
hbox->pack_start(m_ButtonQuit, Gtk::PACK_EXPAND_PADDING);

// Connect the signal handlers:
m_ButtonQuit.signal_clicked().connect( sigc::mem_fun(*this,
    &IdleExample::on_button_clicked) );

// formatting drive c in timeout signal handler - called once every 50ms
Glib::signal_timeout().connect( sigc::mem_fun(*this, &IdleExample:: ↵
    on_timer),
    50 );

// formatting drive d in idle signal handler - called as quickly as ↵
    possible
Glib::signal_idle().connect( sigc::mem_fun(*this, &IdleExample::on_idle) ↵
    );

show_all_children();
}

void IdleExample::on_button_clicked()
{
    hide();
}

// this timer callback function is executed once every 50ms (set in ↵
    connection
// above). Use timeouts when speed is not critical. (ie periodically ↵
    updating
// something).

```

---



```
bool IdleExample::on_timer()
{
    double value = m_ProgressBar_c.get_fraction();

    // Update progressbar 1/500th each time:
    m_ProgressBar_c.set_fraction(value + 0.002);

    return value < 0.99; // return false when done
}

// This idle callback function is executed as often as possible, hence it ←
// is
// ideal for processing intensive tasks.
bool IdleExample::on_idle()
{
    double value = m_ProgressBar_d.get_fraction();

    // Update progressbar 1/5000th each time:
    m_ProgressBar_d.set_fraction(value + 0.0002);

    return value < 0.99; // return false when done
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "idleexample.h"
#include <gtkmm/application.h>

int main (int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    IdleExample example;
    return app->run(example);
}
```

This example points out the difference of idle and timeout methods a little. If you need methods that are called periodically, and speed is not very important, then you want timeout methods. If you want methods that are called as often as possible (like calculating a fractal in background), then use idle methods.

Try executing the example and increasing the system load. The upper progress bar will increase steadily; the lower one will slow down.

---

## Chapter 25

# Memory management

### 25.1 Widgets

#### 25.1.1 Normal C++ memory management

gtkmm allows the programmer to control the lifetime (that is, the construction and destruction) of any widget in the same manner as any other C++ object. This flexibility allows you to use `new` and `delete` to create and destroy objects dynamically or to use regular class members (that are destroyed automatically when the class is destroyed) or to use local instances (that are destroyed when the instance goes out of scope). This flexibility is not present in some C++ GUI toolkits, which restrict the programmer to only a subset of C++'s memory management features.

Here are some examples of normal C++ memory management:

##### 25.1.1.1 Class Scope widgets

If a programmer does not need dynamic memory allocation, automatic widgets in class scope may be used. One advantage of automatic widgets in class scope is that memory management is grouped in one place. The programmer does not risk memory leaks from failing to `delete` a widget.

The primary disadvantage of using class scope widgets is revealing the class implementation rather than the class interface in the class header.

```
#include <gtkmm/button.h>
#include <gtkmm/window.h>
class Foo : public Gtk::Window
{
private:
```

```
Gtk::Button theButton;  
// will be destroyed when the Foo object is destroyed  
};
```

#### 25.1.1.2 Function scope widgets

If a programmer does not need a class scope widget, a function scope widget may also be used. The advantages to function scope over class scope are the increased data hiding and reduced dependencies.

```
{  
    Gtk::Button aButton;  
    aButton.show();  
    ...  
    app->run();  
}
```

#### 25.1.1.3 Dynamic allocation with new and delete

Usually, the programmer will prefer to allow containers to automatically destroy their children by creating them using `Gtk::make_managed()` (see below). This is not strictly required, as the `new` and `delete` operators may also be used, but modern C++ style discourages those in favour of safer models of memory management, so it is better to create widgets using `Gtk::make_managed()` and let their parent destroy them, than to manually perform dynamic allocation.

```
Gtk::Button* pButton = new Gtk::Button("Test");  
  
// do something useful with pButton  
  
delete pButton;
```

Here, the programmer deletes `pButton` to prevent a memory leak.

### 25.1.2 Managed Widgets

Alternatively, you can let a widget's container control when the widget is destroyed. In most cases, you want a widget to last only as long as the container it is in. To delegate the management of a widget's lifetime to its container, create it with `Gtk::make_managed()` and then pack it into its container with `Gtk::Container::add()`, `Gtk::Box::pack_start()`, or a similar method. Now the widget will be destroyed whenever its container is destroyed.

---

### 25.1.2.1 Dynamic allocation with `make_managed()` and `add()`

gtkmm provides ways including the `make_managed()` function and `Gtk::Container::add()` method to simplify creation and destruction of widgets whose lifetime can be managed by a parent.

Every widget except a top-level window must be added to a parent container in order to be displayed. The `manage()` function marks a widget so that when that widget is added to a parent container, said container becomes responsible for deleting the widget, meaning the user no longer needs to do so. The original way to create widgets whose lifetime is managed by their parent in this way was to call `manage()`, passing in the result of a `new` expression that created a dynamically allocated widget.

However, usually, when you create such a widget, you will already know that its parent container should be responsible for destroying it. In addition, modern C++ style discourages use of the `new` operator, which was required when passing a newly created widget to `manage()`. Therefore, gtkmm has added `make_managed()`, which combines creation and marking with `manage()` into a single step. This avoids you having to write `new`, which is discouraged in modern C++ style, and more clearly expresses intent to create a managed widget.

```
MyContainer::MyContainer()
{
    Gtk::Button* pButton = Gtk::make_managed<Gtk::Button>("Test");
    add(*pButton); //add *pButton to MyContainer
}
```

Now, when objects of type `MyContainer` are destroyed, the button will also be deleted. It is no longer necessary to delete `pButton` to free the button's memory; its deletion has been delegated to the `MyContainer` object.

Note that if you never added the widget to any parent container, or you did but later `Gtk::Container::remove()` it from said parent, gtkmm restores the widget's lifetime management to whatever state it had before `manage()` was called, which typically means that the responsibility for deleting the widget returns to the user.

Of course, a top-level container will not be added to another container. The programmer is responsible for destroying the top-level container using one of the traditional C++ techniques. For instance, your top-level Window might just be an instance in your `main()` function.

## 25.2 Shared resources

Some objects, such as `Gdk::Pixbufs` and `Pango::Fonts`, are obtained from a shared store. Therefore you cannot instantiate your own instances. These classes typically inherit from `Glib::Object`. Rather than requiring you to reference and unreference these objects, gtkmm uses the `Glib::RefPtr<>` smartpointer. Cairo has its own smartpointer, `Cairo::RefPtr<>`.

Objects such as `Gdk::Pixbuf` can only be instantiated with a `create()` function. For instance,

---

```
Glib::RefPtr<Gdk::Pixbuf> pixbuf = Gdk::Pixbuf::create_from_file(filename) ↵  
;
```

You have no way of getting a bare `Gdk::Pixbuf`. In the example, `pixbuf` is a smart pointer, so you can do this, much like a normal pointer:

```
int width = 0;  
if(pixbuf)  
{  
    width = pixbuf->get_width();  
}
```

When `pixbuf` goes out of scope an `unref()` will happen in the background and you don't need to worry about it anymore. There's no `new` so there's no `delete`.

If you copy a `RefPtr`, for instance

```
Glib::RefPtr<Gdk::Pixbuf> pixbuf2 = pixbuf;
```

, or if you pass it as a method argument or a return type, then `RefPtr` will do any necessary referencing to ensure that the instance will not be destroyed until the last `RefPtr` has gone out of scope.

See the [appendix](#) for detailed information about `RefPtr`.

If you wish to learn more about smartpointers, you might look in these books:

- Bjarne Stroustrup, "The C++ Programming Language" Forth Edition - section 34.3
- Nicolai M. Josuttis, "The C++ Standard Library" - section 4.2

## Chapter 26

# Glade and Gtk::Builder

Although you can use C++ code to instantiate and arrange widgets, this can soon become tedious and repetitive. And it requires a recompilation to show changes. The Glade application allows you to layout widgets on screen and then save an XML description of the arrangement. Your application can then use the Gtk::Builder API to load that XML file at runtime and obtain a pointer to specifically named widget instances.

This has the following advantages:

1. Less C++ code is required.
2. UI changes can be seen more quickly, so UIs are able to improve.
3. Designers without programming skills can create and edit UIs.

You still need C++ code to deal with User Interface changes triggered by user actions, but using Gtk::Builder for the widget layout allows you to focus on implementing that functionality.

### 26.1 Loading the .glade file

Gtk::Builder must be used via a Glib::RefPtr. Like all such classes, you need to use a create() method to instantiate it. For instance,

```
Glib::RefPtr<Gtk::Builder> builder = Gtk::Builder::create_from_file("basic ↵  
    .glade");
```

This will instantiate the windows defined in the .glade file, though they will not be shown immediately unless you have specified that via the Properties window in Glade.

---

To instantiate just one window, or just one of the child widgets, you can specify the name of a widget as the second parameter. For instance,

```
Glib::RefPtr<Gtk::Builder> builder = Gtk::Builder::create_from_file("basic.glade", "treeview_products");
```

## 26.2 Accessing widgets

To access a widget, for instance to `show()` a dialog, use the `get_widget()` method, providing the widget's name. This name should be specified in the Glade Properties window. If the widget could not be found, or is of the wrong type, then the pointer will be set to `nullptr`.

```
Gtk::Dialog* pDialog = nullptr;  
builder->get_widget("DialogBasic", pDialog);
```

`Gtk::Builder` checks for a null pointer, and checks that the widget is of the expected type, and will show warnings on the command line about these.

Remember that you are not instantiating a widget with `get_widget()`, you are just obtaining a pointer to one that already exists. You will always receive a pointer to the same instance when you call `get_widget()` on the same `Gtk::Builder`, with the same widget name. The widgets are instantiated during `Gtk::Builder::create_from_file()`.

`get_widget()` returns child widgets that are managed (see the [Memory Management](#) chapter), so they will be deleted when their parent container is deleted. Windows (such as Dialogs) cannot be managed because they have no parent container, so you must delete them at some point. The documentation of `Gtk::Builder` has more to say about the memory management of different kinds of objects.

### Reference

#### 26.2.1 Example

This simple example shows how to load a Glade file at runtime and access the widgets with `Gtk::Builder`.

#### Source Code

File: `main.cc` (For use with `gtkmm 3`)

```
#include <gtkmm.h>  
#include <iostream>  
  
Gtk::Dialog* pDialog = nullptr;  
  
static  
void on_button_clicked()
```

```
{
    if(pDialog)
        pDialog->hide(); //hide() will cause main::run() to end.
}

int main (int argc, char **argv)
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    //Load the GtkBuilder file and instantiate its widgets:
    auto refBuilder = Gtk::Builder::create();
    try
    {
        refBuilder->add_from_file("basic.glade");
    }
    catch(const Glib::FileError& ex)
    {
        std::cerr << "FileError: " << ex.what() << std::endl;
        return 1;
    }
    catch(const Glib::MarkupError& ex)
    {
        std::cerr << "MarkupError: " << ex.what() << std::endl;
        return 1;
    }
    catch(const Gtk::BuilderError& ex)
    {
        std::cerr << "BuilderError: " << ex.what() << std::endl;
        return 1;
    }

    //Get the GtkBuilder-instantiated Dialog:
    refBuilder->get_widget("DialogBasic", pDialog);
    if(pDialog)
    {
        //Get the GtkBuilder-instantiated Button, and connect a signal handler ↵
        :
        Gtk::Button* pButton = nullptr;
        refBuilder->get_widget("quit_button", pButton);
        if(pButton)
        {
            pButton->signal_clicked().connect( sigc::ptr_fun(on_button_clicked) ↵
            );
        }

        app->run(*pDialog);
    }
}
```

---



```
delete pDialog;

return 0;
}
```

## 26.3 Using derived widgets

You can use `Gtk::Builder` and `Glade` to layout your own custom widgets derived from gtkmm widget classes. This keeps your code organized and encapsulated, separating declarative presentation from business logic, avoiding having most of your source just be setting properties and packing in containers.

Use `Gtk::Builder::get_widget_derived()` like so:

```
DerivedDialog* pDialog = nullptr;
builder->get_widget_derived("DialogBasic", pDialog);
```

Your derived class must have a constructor that takes a pointer to the underlying C type, and the `Gtk::Builder` instance. All relevant classes of gtkmm typedef their underlying C type as `BaseObjectType` (`Gtk::Dialog` typedefs `BaseObjectType` as `GtkDialog`, for instance).

You must call the base class's constructor in the initialization list, providing the C pointer. For instance,

```
DerivedDialog::DerivedDialog(BaseObjectType* cobject, const Glib::RefPtr<
    Gtk::Builder>& builder)
: Gtk::Dialog(cobject)
{
}
```

You could then encapsulate the manipulation of the child widgets in the constructor of the derived class, maybe using `get_widget()` or `get_widget_derived()` again. For instance,

```
DerivedDialog::DerivedDialog(BaseObjectType* cobject, const Glib::RefPtr<
    Gtk::Builder>& builder)
: Gtk::Dialog(cobject),
  m_builder(builder),
  m_pButton(nullptr)
{
    //Get the Glade-instantiated Button, and connect a signal handler:
    m_builder->get_widget("quit_button", m_pButton);

    if(m_pButton)
    {
        m_pButton->signal_clicked().connect( sigc::mem_fun(*this, &
            DerivedDialog::on_button_quit) );
    }
}
```

```
}
}
```

Starting with gtkmm 3.19.7, it's possible to pass additional arguments from `get_widget_derived()` to the constructor of the derived widget. For instance, this call to `get_widget_derived()`

```
DerivedDialog* pDialog = nullptr;
builder->get_widget_derived("DialogBasic", pDialog, true);
```

can invoke this constructor

```
DerivedDialog::DerivedDialog(BaseObjectType* cobject, const Glib::RefPtr< ↵
    Gtk::Builder>& builder, bool warning)
: Gtk::Dialog(cobject),
  m_builder(builder),
  m_pButton(nullptr)
{
    // ....
}
```

### 26.3.1 Gtk::Builder and Glib::Property

---

#### Note

User-defined properties will be read correctly from the `.glade` file only if you use glibmm 2.62.0 or newer.

---

If your derived widget uses `Glib::Property`, it becomes slightly more complicated. A derived widget that contains `Glib::Property` members must be registered with its own name in the `GType` system. It must be registered before any of the `create_from_*`() or `add_from_*`() methods are called, meaning that you may have to create an instance of your derived widget just to have its class registered. Your derived widget must have a constructor that has the parameters required by `get_widget_derived()` and calls the `Glib::ObjectBase` constructor to register the `GType`.

```
DerivedButton::DerivedButton(BaseObjectType* cobject, const Glib::RefPtr< ↵
    Gtk::Builder>& builder)
: Glib::ObjectBase("MyButton"), // The GType name will be ↵
  gtkmm__CustomObject_MyButton.
  Gtk::Button(cobject),
  prop_ustring(*this, "button-ustring"),
  prop_int(*this, "button-int", 10)
{
    // ....
}
```

---

When using gtkmm with a version of glibmm from 2.62 onwards, it is possible also to specify properties of derived widgets, declared in C++ using gtkmm, within .glade files and load/set these using `Gtk::Builder`. See the documentation of `Gtk::Builder` for more details on how to achieve this. Glade won't recognise such properties as-is, but it should be able to through use of [property class definitions](#) and a catalog declaring those new properties.

### 26.3.2 Example

This example shows how to load a Glade file at runtime and access the widgets via derived classes.

#### Source Code

File: `derivedbutton.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_DERIVED_BUTTON_H
#define GTKMM_EXAMPLE_DERIVED_BUTTON_H

#include <gtkmm.h>

class DerivedButton : public Gtk::Button
{
public:
    DerivedButton();
    DerivedButton(BaseObjectType* cobject, const Glib::RefPtr<Gtk::Builder>& ↵
        refGlade);
    virtual ~DerivedButton();

    // Provide proxies for the properties. The proxy allows you to connect ↵
    // to
    // the 'changed' signal, etc.
    Glib::PropertyProxy<Glib::ustring> property_ustring() { return ↵
        prop_ustring.get_proxy(); }
    Glib::PropertyProxy<int> property_int() { return prop_int.get_proxy(); }

private:
    Glib::Property<Glib::ustring> prop_ustring;
    Glib::Property<int> prop_int;
};

#endif //GTKMM_EXAMPLE_DERIVED_BUTTON_H
```

File: `deriveddialog.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_DERIVED_DIALOG_H
#define GTKMM_EXAMPLE_DERIVED_DIALOG_H

#include <gtkmm.h>
```

```
#include "derivedbutton.h"

class DerivedDialog : public Gtk::Dialog
{
public:
    DerivedDialog(BaseObjectType* cobject, const Glib::RefPtr<Gtk::Builder>& ↵
        refGlade);
    DerivedDialog(BaseObjectType* cobject, const Glib::RefPtr<Gtk::Builder>& ↵
        refGlade,
        bool is_glad);
    virtual ~DerivedDialog();

protected:
    //Signal handlers:
    void on_button_quit();

    Glib::RefPtr<Gtk::Builder> m_refGlade;
    DerivedButton* m_pButton;
};

#endif //GTKMM_EXAMPLE_DERIVED_DIALOG_H
```

**File: derivedbutton.cc (For use with gtkmm 3)**

```
#include "derivedbutton.h"
#include <iostream>

namespace
{
void on_ustring_changed()
{
    std::cout << "- ustring property changed!" << std::endl;
}

void on_int_changed()
{
    std::cout << "- int property changed!" << std::endl;
}
} // anonymous namespace

// For creating a dummy object in main.cc.
DerivedButton::DerivedButton()
: Glib::ObjectBase("MyButton"),
  prop_ustring(*this, "button-ustring"),
  prop_int(*this, "button-int", 10)
{
}
```

```

DerivedButton::DerivedButton(BaseObjectType* cobject, const Glib::RefPtr< ↵
    Gtk::Builder>& /* refGlade */)
: // To register custom properties, you must register a custom GType. If
  // you don't know what that means, don't worry, just remember to add
  // this Glib::ObjectBase constructor call to your class' constructor.
  // The GType name will be gtkmm__CustomObject_MyButton.
  Glib::ObjectBase("MyButton"),
  Gtk::Button(cobject),
  // register the properties with the object and give them names
  prop_ustring(*this, "button-ustring"),
  // this one has a default value
  prop_int(*this, "button-int", 10)
{
  // Register some handlers that will be called when the values of the
  // specified parameters are changed.
  property_ustring().signal_changed().connect(sigc::ptr_fun(& ↵
    on_ustring_changed));
  property_int().signal_changed().connect(sigc::ptr_fun(&on_int_changed));
}

DerivedButton::~DerivedButton()
{
}

```

**File:** deriveddialog.cc (For use with gtkmm 3)

```

#include "deriveddialog.h"
#include <iostream>

DerivedDialog::DerivedDialog(BaseObjectType* cobject, const Glib::RefPtr< ↵
    Gtk::Builder>& refGlade)
: Gtk::Dialog(cobject),
  m_refGlade(refGlade),
  m_pButton(nullptr)
{
  // Get the Glade-instantiated Button, and connect a signal handler:
  m_refGlade->get_widget_derived("quit_button", m_pButton);
  if (m_pButton)
  {
    // The user-defined properties in DerivedButton are read correctly ↵
    // from the
    // derived.glade file only if you use glibmm 2.62.0 or newer.
    m_pButton->signal_clicked().connect( sigc::mem_fun(*this, & ↵
      DerivedDialog::on_button_quit) );
    std::cout << "ustring, int: " << m_pButton->property_ustring()
      << ", " << m_pButton->property_int() << std::endl;
    m_pButton->property_int() = 99;
    std::cout << "ustring, int: " << m_pButton->property_ustring()

```

```

        << " , " << m_pButton->property_int() << std::endl;
    }
}

// The first two parameters are mandatory in a constructor that will be ←
// called
// from Gtk::Builder::get_widget_derived().
// Additional parameters, if any, correspond to additional arguments in ←
// the call
// to Gtk::Builder::get_widget_derived().
DerivedDialog::DerivedDialog(BaseObjectType* cobject, const Glib::RefPtr< ←
    Gtk::Builder>& refGlade,
    bool is_glad)
: DerivedDialog(cobject, refGlade) // Delegate to the other constructor
{
    // Show an icon.
    auto pImage = Gtk::make_managed<Gtk::Image>();
    pImage->set_from_icon_name(is_glad ? "face-smile" : "face-sad", Gtk:: ←
        ICON_SIZE_DIALOG);
    pImage->show_all();
    get_content_area()->pack_start(*pImage);
}

DerivedDialog::~DerivedDialog()
{
}

void DerivedDialog::on_button_quit()
{
    hide(); //hide() will cause Gtk::Application::run() to end.
}

```

**File: main.cc (For use with gtkmm 3)**

```

#include "deriveddialog.h"
#include <iostream>
#include <cstring>

// Not really used anywhere, but force an instance to be created.
DerivedButton* my_globally_accessible_button = nullptr;

int main (int argc, char **argv)
{
    bool show_icon = false;
    bool is_glad = true;
    int argc1 = argc;
    if (argc > 1)
    {

```

```
if (std::strcmp(argv[1], "--glad") == 0)
{
    show_icon = true;
    is_glad = true;
    argc1 = 1; // Don't give the command line arguments to Gtk:: ↵
        Application.
}
else if (std::strcmp(argv[1], "--sad") == 0)
{
    show_icon = true;
    is_glad = false;
    argc1 = 1; // Don't give the command line arguments to Gtk:: ↵
        Application.
}
}

auto app = Gtk::Application::create(argc1, argv, "org.gtkmm.example");

// Create a dummy instance before the call to refBuilder->add_from_file ↵
    ().
// This creation registers DerivedButton's class in the GType system.
my_globally_accessible_button = new DerivedButton();

//Load the Glade file and instantiate its widgets:
auto refBuilder = Gtk::Builder::create();
try
{
    refBuilder->add_from_file("derived.glade");
}
catch(const Glib::FileError& ex)
{
    std::cerr << "FileError: " << ex.what() << std::endl;
    return 1;
}
catch(const Glib::MarkupError& ex)
{
    std::cerr << "MarkupError: " << ex.what() << std::endl;
    return 1;
}
catch(const Gtk::BuilderError& ex)
{
    std::cerr << "BuilderError: " << ex.what() << std::endl;
    return 1;
}

//Get the GtkBuilder-instantiated dialog:
DerivedDialog* pDialog = nullptr;
```

---

```
if (show_icon)
    // This call to get_widget_derived() requires gtkmm 3.19.7 or higher.
    refBuilder->get_widget_derived("DialogDerived", pDialog, is_glad);
else
    refBuilder->get_widget_derived("DialogDerived", pDialog);
if(pDialog)
{
    //Start:
    app->run(*pDialog);
}

delete pDialog;

return 0;
}
```



## Chapter 27

# Internationalization and Localization

gtkmm applications can easily support multiple languages, including non-European languages such as Chinese and right-to-left languages such as Arabic. An appropriately-written and translated gtkmm application will use the appropriate language at runtime based on the user's environment.

You might not anticipate the need to support additional languages, but you can never rule it out. And it's easier to develop the application properly in the first place rather than retrofitting later.

The process of writing source code that allows for translation is called *internationalization*, often abbreviated to *i18n*. The *Localization* process, sometimes abbreviated as *l10n*, provides translated text for other languages, based on that source code.

The main activity in the internationalization process is finding strings seen by users and marking them for translation. You do not need to do it all at once - if you set up the necessary project infrastructure correctly then your application will work normally regardless of how many strings you've covered.

String literals should be typed in the source code in English, but surrounded by a macro. The `gettext` (or `intltool`) utility can then extract the marked strings for translation, and substitute the translated text at runtime.

---

## 27.1 Preparing your project

---

### Note

In the instructions below we will assume that you will not be using `gettext` directly, but `intltool`, which was written specifically for GNOME. `intltool` uses `gettext()`, which extracts strings from source code, but `intltool` can also combine strings from other files, for example from desktop menu details, and GUI resource files such as Glade files, into standard `gettext .pot/.po` files.

We also assume that you are using autotools (`automake` and `autoconf`) to build your project (although autotools is not recommended for new applications), and that you are using `./autogen.sh` from `gnome-common` or a similar `autogen.sh` file, which, among other things, takes care of some `intltool` initialization.

---

---

### Note

If you are using `meson` (recommended), see the [Localisation](#) chapter in Meson's manual. You can then skip this section.

---

An alternative to `gnome-common`'s `autogen.sh` may look like this:

```
#!/bin/sh -e
test -n "$srcdir" || srcdir=`dirname "$0"`
test -n "$srcdir" || srcdir=.

autoreconf --force --install --verbose --warnings=all "$srcdir"
echo "Running intltoolize --copy --force --automake"
intltoolize --copy --force --automake
test -n "$NOCONFIGURE" || "$srcdir/configure" "$@"
```

Create a sub-directory named `po` in your project's root directory. This directory will eventually contain all of your translations. Within it, create a file named `LINGUAS` and a file named `POTFILES.in`. It is common practice to also create a `ChangeLog` file in the `po` directory so that translators can keep track of translation changes.

`LINGUAS` contains an alphabetically sorted list of codes identifying the languages for which your program is translated (comment lines starting with a `#` are ignored). Each language code listed in the `LINGUAS` file must have a corresponding `.po` file. So, if your program has German and Japanese translations, your `LINGUAS` file would look like this:

```
# keep this file sorted alphabetically, one language code per line
de
ja
```

(In addition, you'd have the files `de.po` and `ja.po` in your `po` directory which contain the German and Japanese translations, respectively.)

---

POTFILES.in is a list of paths to all files which contain strings marked up for translation, starting from the project root directory. So for example, if your project sources were located in a subdirectory named `src`, and you had two files that contained strings that should be translated, your POTFILES.in file might look like this:

```
src/main.cc
src/other.cc
```

If you are using `gettext` directly, you can only mark strings for translation if they are in source code file. However, if you use `intltool`, you can mark strings for translation in a variety of other file formats, including Glade UI files, xml, **.desktop files** and several more. So, if you have designed some of the application UI in Glade then also add your `.glade` files to the list in POTFILES.in.

Now that there is a place to put your translations, you need to initialize `intltool` and `gettext`. Add the following code to your `configure.ac`, substituting 'programname' with the name of your program:

```
IT_PROG_INTLTOOL([0.35.0])

GETTEXT_PACKAGE=programname
AC_SUBST(GETTEXT_PACKAGE)
AC_DEFINE_UNQUOTED([GETTEXT_PACKAGE], ["$GETTEXT_PACKAGE"],
                  [The domain to use with gettext])
AM_GNU_GETTEXT([external])
AM_GNU_GETTEXT_VERSION([0.17])

PROGRAMNAME_LOCALEDIR=[${datadir}/locale]
AC_SUBST(PROGRAMNAME_LOCALEDIR)
```

This `PROGRAMNAME_LOCALEDIR` variable will be used later in the `Makefile.am` file, to define a macro that will be used when you initialize `gettext` in your source code.

`AM_GLIB_GNU_GETTEXT` has been an alternative to `AM_GNU_GETTEXT` and `AM_GNU_GETTEXT_VERSION`, but `AM_GLIB_GNU_GETTEXT` is now deprecated, and shall not be used in new code.

In the top-level `Makefile.am`:

- Add `po` to the `SUBDIRS` variable. Without this, your translations won't get built and installed when you build the program
- Define `INTLTOOL_FILES` as:

```
INTLTOOL_FILES = intltool-extract.in \
                 intltool-merge.in \
                 intltool-update.in
```

- Add `INTLTOOL_FILES` to the `EXTRA_DIST` list of files. This ensures that when you do a **make dist**, these commands will be included in the source tarball.
-

- Update your `DISTCLEANFILES`:

```
DISTCLEANFILES = ... intltool-extract \
                  intltool-merge \
                  intltool-update \
                  po/.intltool-merge-cache
```

- Depending on the types of files that contain translatable strings, add code such as

```
desktopdir = $(datadir)/applications
desktop_in_files = programname.desktop.in
desktop_DATA = $(desktop_in_files:.desktop.in=.desktop)
@INTLTOOL_DESKTOP_RULE@
```

In your `src/Makefile.am`, update your `AM_CPPFLAGS` to add the following preprocessor macro definition:

```
AM_CPPFLAGS = ... -DPROGRAMNAME_LOCALEDIR=\"${PROGRAMNAME_LOCALEDIR}\"
```

This macro will be used when you initialize `gettext` in your source code.

## 27.2 Marking strings for translation

String literals should be typed in the source code in English, but they should be surrounded by a call to the `gettext()` function. These strings will be extracted for translation and the translations may be used at runtime instead of the original English strings.

The GNU `gettext` package allows you to mark strings in source code, extract those strings for translation, and use the translated strings in your application.

However, Glib defines `gettext()` support macros which are shorter wrappers in an easy-to-use form. To use these macros, include `<glibmm/i18n.h>`, and then, for example, substitute:

```
display_message("Getting ready for i18n.");
```

with:

```
display_message(_("Getting ready for i18n."));
```

For reference, it is possible to generate a file which contains all strings which appear in your code, even if they are not marked for translation, together with file name and line number references. To generate such a file named `my-strings`, execute the following command, within the source code directory:

```
xgettext -a -o my-strings --omit-header *.cc *.h
```

Finally, to let your program use the translation for the current locale, add this code to the beginning of your `main.cc` file, to initialize gettext.

```
bindtextdomain(GETTEXT_PACKAGE, PROGRAMNAME_LOCALEDIR);  
bind_textdomain_codeset(GETTEXT_PACKAGE, "UTF-8");  
textdomain(GETTEXT_PACKAGE);
```

### 27.2.1 How gettext works

`intltool / xgettext` script extracts the strings and puts them in a `mypackage.pot` file. The translators of your application create their translations by first copying this `.pot` file to a `localename.po` file. A locale identifies a language and an encoding for that language, including date and numerical formats. Later, when the text in your source code has changed, the `msgmerge` script is used to update the `localename.po` files from the regenerated `.pot` file.

At install time, the `.po` files are converted to a binary format (with the extension `.mo`) and placed in a system-wide directory for locale files, for example `/usr/share/locale/`.

When the application runs, the gettext library checks the system-wide directory to see if there is a `.mo` file for the user's locale environment (you can set the locale with, for instance, "export LANG=de\_DE.UTF-8" from a bash console). Later, when the program reaches a `gettext` call, it looks for a translation of a particular string. If none is found, the original string is used.

### 27.2.2 Testing and adding translations

To convince yourself that you've done well, you may wish to add a translation for a new locale. In order to do that, go to the `po` subdirectory of your project and execute the following command:

```
intltool-update --pot
```

That will create a file named `programname.pot`. Now copy that file to `languagecode.po`, such as `de.po` or `hu.po`. Also add that language code to `LINGUAS`. The `.po` file contains a header and a list of English strings, with space for the translated strings to be entered. Make sure you set the encoding of the `.po` file (specified in the header, but also as content) to `UTF-8`.

---

#### Note

It's possible that certain strings will be marked as `fuzzy` in the `.po` file. These translations will not substitute the original string. To make them appear, simply remove the `fuzzy` tag. A `fuzzy` tag appears if a string content changed, but the location is still the same.

---

### 27.2.3 Resources

More information about what lies behind the internationalization and localization process is presented and demonstrated in:

- [L10N Guidelines for Developers](#)
- [Intltool README](#)
- [How to use Git for GNOME translators](#)
- [gettext manual](#)
- [gtkmm\\_hello example package](#)
- [gnomemm\\_hello example package](#)

## 27.3 Expecting UTF8

A properly internationalized application will not make assumptions about the number of bytes in a character. That means that you shouldn't use pointer arithmetic to step through the characters in a string, and it means you shouldn't use `std::string` or standard C functions such as `strlen()` because they make the same assumption.

However, you probably already avoid bare `char*` arrays and pointer arithmetic by using `std::string`, so you just need to start using `Glib::ustring` instead. See the [Basics](#) chapter about `Glib::ustring`.

### 27.3.1 Glib::ustring and std::ostreams

Unfortunately, the integration with the standard `ostreams` is not completely foolproof. `gtkmm` converts `Glib::ustrings` to a locale-specific encoding (which usually is not UTF-8) if you output them to an `ostream` with `operator<<`. Likewise, retrieving `Glib::ustrings` from `istream` with `operator>>` causes a conversion in the opposite direction. But this scheme breaks down if you go through a `std::string`, e.g. by inputting text from a stream to a `std::string` and then implicitly converting it to a `Glib::ustring`. If the string contained non-ASCII characters and the current locale is not UTF-8 encoded, the result is a corrupted `Glib::ustring`. You can work around this with a manual conversion. For instance, to retrieve the `std::string` from a `ostreamstream`:

```
std::ostreamstream output;
output.imbue(std::locale("")); // use the user's locale for this stream
output << percentage << " % done";
label->set_text(Glib::locale_to_utf8(output.str()));
```

## 27.4 Pitfalls

There are a few common mistakes that you would discover eventually yourself. But this section might help you to avoid them.

### 27.4.1 Same strings, different semantics

Sometimes two english strings are identical but have different meanings in different contexts, so they would probably not be identical when translated. Since the English strings are used as look-up keys, this causes problems.

In these cases, you should add extra characters to the strings. For instance, use "jumps[noun]" and "jumps[verb]" instead of just "jumps" and strip them again outside the `gettext` call. If you add extra characters you should also add a comment for the translators before the `gettext` call. Such comments will be shown in the `.po` files. For instance:

```
// note to translators: don't translate the "[noun]" part - it is
// just here to distinguish the string from another "jumps" string
text = strip(gettext("jumps[noun]"), "[noun]");
```

### 27.4.2 Composition of strings

C programmers use `sprintf()` to compose and concatenate strings. C++ favours streams, but unfortunately, this approach makes translation difficult, because each fragment of text is translated separately, without allowing the translators to rearrange them according to the grammar of the language.

For instance, this code would be problematic:

```
std::cout << _("Current amount: ") << amount
          << _(" Future: ") << future << std::endl;

label.set_text(_("Really delete ") + filename + _(" now?"));
```

So you should either avoid this situation or use `Glib::ustring::compose()` which supports syntax such as:

```
std::cout << Glib::ustring::compose(
    _("Current amount: %1 Future: %2"), amount, future) << std::endl;

label.set_text(Glib::ustring::compose(_("Really delete %1 now?"), filename
    ));
```

### 27.4.3 Assuming the displayed size of strings

You never know how much space a string will take on screen when translated. It might very possibly be twice the size of the original English string. Luckily, most gtkmm widgets will expand at runtime to the required size.

### 27.4.4 Unusual words

You should avoid cryptic abbreviations, slang, or jargon. They are usually difficult to translate, and are often difficult for even native speakers to understand. For instance, prefer "application" to "app"

### 27.4.5 Using non-ASCII characters in strings

Currently, gettext does not support non-ASCII characters (i.e. any characters with a code above 127) in source code. For instance, you cannot use the copyright sign (©).

To work around this, you could write a comment in the source code just before the string, telling the translators to use the special character if it is available in their languages. For english, you could then make an American English `en_US.po` translation which used that special character.

## 27.5 Getting help with translations

If your program is free software, there is a whole GNOME subproject devoted to helping you make translations, the [GNOME Translation Project](#).

The way it works is that you upload your source code to a git repository where translators can access it, then contact the `gnome-i18n` mailing list and ask to have your program added to the [list of modules to translate](#).

Then you make sure you update the file `POTFILES.in` in the `po/` subdirectory (`intltool-update -M` can help with this) so that the translators always access updated `myprogram.pot` files, and simply freeze the strings at least a couple of days before you make a new release, announcing it on `gnome-i18n`. Depending on the number of strings your program contains and how popular it is, the translations will then start to tick in as `language.po` files.

Note that most language teams only consist of 1-3 persons, so if your program contains a lot of strings, it might last a while before anyone has the time to look at it. Also, most translators do not want to waste their time (translating is a very time-consuming task) so if they do not assess your project as being really serious (in the sense that it is polished and being maintained) they may decide to spend their time on some other project.

---



## Chapter 28

# Custom Widgets

gtkmm makes it very easy to derive new widgets by inheriting from an existing widget class, either by deriving from a container and adding child widgets, or by deriving from a single-item widget, and changing its behaviour. But you might occasionally find that no suitable starting point already exists. In this case, you can implement a widget from scratch.

### 28.1 Custom Containers

When deriving from `Gtk::Container`, you should override the following virtual methods:

- `get_request_mode_vfunc()`: Return what `Gtk::SizeRequestMode` is preferred by the container.
  - `get_preferred_width_vfunc()`: Calculate the minimum and natural width of the container.
  - `get_preferred_height_vfunc()`: Calculate the minimum and natural height of the container.
  - `get_preferred_width_for_height_vfunc()`: Calculate the minimum and natural width of the container, if it would be given the specified height.
  - `get_preferred_height_for_width_vfunc()`: Calculate the minimum and natural height of the container, if it would be given the specified width.
  - `on_size_allocate()`: Position the child widgets, given the height and width that the container has actually been given.
  - `forall_vfunc()`: Call the same callback for each of the children.
  - `on_add()`: Add a child widget to the container.
-

- `on_remove()`: Remove a child widget from the container.
- `child_type_vfunc()`: Return what type of child can be added.

The `get_request_mode_vfunc()`, `get_preferred_width_vfunc()`, `get_preferred_height_vfunc()`, `get_preferred_width_for_height_vfunc()`, `get_preferred_height_for_width_vfunc()`, and `on_size_allocate()` virtual methods control the layout of the child widgets. For instance, if your container has 2 child widgets, with one below the other, your `get_request_mode_vfunc()` might request height-for-width layout. Then your `get_preferred_width_vfunc()` might report the maximum of the widths of the child widgets, and `get_preferred_height_for_width_vfunc()` might report the sum of their heights. If you want padding between the child widgets then you would add that to the width and height too. Your widget's container will use this result to ensure that your widget gets enough space, and not less. By examining each widget's parent, and its parent, this logic will eventually decide the size of the top-level window.

You are not guaranteed to get the `Gtk::SizeMode` that you request. Therefore all four of the `get_preferred_xxx_vfunc()` methods must return sensible values.

`on_size_allocate()` receives the actual height and width that the parent container has decided to give to your widget. This might be more than the minimum, or even more than the natural size, for instance if the top-level window has been expanded. You might choose to ignore the extra space and leave a blank area, or you might choose to expand your child widgets to fill the space, or you might choose to expand the padding between your widgets. It's your container, so you decide. Don't forget to call `set_allocation()` inside your `on_size_allocate()` implementation to actually use the allocated space that has been offered by the parent container.

Unless your container is a top-level window that derives from `Gtk::Window`, you should probably also call `Gtk::Widget::set_has_window(false)` in your constructor. This means that your container does not create its own `Gdk::Window`, but uses its parent's window. (Note the difference between `Gtk::Window` and `Gdk::Window`.) If your container does need its own `Gdk::Window`, and does not derive from `Gtk::Window`, you must also override the `on_realize()` method as described in the [Custom Widgets](#) section. And unless your container draws directly onto the underlying `Gdk::Window`, you should probably call `set_redraw_on_allocate(false)` to improve performance.

By overriding `forall_vfunc()` you can allow applications to operate on all of the container's child widgets. For instance, `show_all_children()` uses this to find all the child widgets and show them.

Although your container might have its own method to set the child widgets, you should still provide an implementation for the virtual `on_add()` and `on_remove()` methods from the base class, so that the `add()` and `remove()` methods will do something appropriate if they are called.

Your implementation of the `child_type_vfunc()` method should report the type of widget that may be added to your container, if it is not yet full. This is usually `Gtk::Widget::get_type()` to indicate that the container may contain any class derived from `Gtk::Widget`. If the container may not contain any more widgets, then this method should return `G_TYPE_NONE`.

---

### 28.1.1 Example

This example implements a container with two child widgets, one above the other. Of course, in this case it would be far simpler just to use a vertical `Gtk::Box`.




Figure 28.1: Custom Container

#### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>
#include "mycontainer.h"

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
```

```
//Signal handlers:
void on_button_quit();

//Child widgets:
Gtk::Box m_VBox;
MyContainer m_MyContainer;
Gtk::Button m_Button_One;
Gtk::Label m_Label_Two;
Gtk::ButtonBox m_ButtonBox;
Gtk::Button m_Button_Quit;
};

#endif //GTKMM_EXAMPLEWINDOW_H
```

**File: mycontainer.h (For use with gtkmm 3)**

```
#ifndef GTKMM_CUSTOM_CONTAINER_MYCONTAINER_H
#define GTKMM_CUSTOM_CONTAINER_MYCONTAINER_H

#include <gtkmm/container.h>

class MyContainer : public Gtk::Container
{
public:
    MyContainer();
    virtual ~MyContainer();

    void set_child_widgets(Gtk::Widget& child_one, Gtk::Widget& child_two);

protected:

    //Overrides:
    Gtk::SizeRequestMode get_request_mode_vfunc() const override;
    void get_preferred_width_vfunc(int& minimum_width, int& natural_width) const override;
    void get_preferred_height_for_width_vfunc(int width, int& minimum_height, int& natural_height) const override;
    void get_preferred_height_vfunc(int& minimum_height, int& natural_height) const override;
    void get_preferred_width_for_height_vfunc(int height, int& minimum_width, int& natural_width) const override;
    void on_size_allocate(Gtk::Allocation& allocation) override;

    void forall_vfunc(gboolean include_internals, GtkCallback callback, gpointer callback_data) override;

    void on_add(Gtk::Widget* child) override;
    void on_remove(Gtk::Widget* child) override;
```

```
GType child_type_vfunc() const override;

Gtk::Widget* m_child_one;
Gtk::Widget* m_child_two;
};

#endif //GTKMM_CUSTOM_CONTAINER_MYCONTAINER_H
```

**File:** examplewindow.cc (For use with gtkmm 3)

```
#include <iostream>
#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_One("Child One"),
  m_Label_Two("Child 2", Gtk::ALIGN_END, Gtk::ALIGN_CENTER),
  m_Button_Quit("Quit")
{
  set_title("Custom Container example");
  set_border_width(6);
  set_default_size(400, 200);

  add(m_VBox);

  //Add the child widgets to the custom container:
  m_MyContainer.set_child_widgets(m_Button_One, m_Label_Two);

  m_VBox.pack_start(m_MyContainer, Gtk::PACK_EXPAND_WIDGET);
  m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);

  m_ButtonBox.pack_start(m_Button_Quit, Gtk::PACK_SHRINK);
  m_ButtonBox.set_border_width(6);
  m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);
  m_Button_Quit.signal_clicked().connect( sigc::mem_fun(*this,
    &ExampleWindow::on_button_quit) );

  show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_quit()
{
  hide();
}
```

File: main.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

File: mycontainer.cc (For use with gtkmm 3)

```
#include <iostream>
#include <algorithm> // std::max
#include "mycontainer.h"

MyContainer::MyContainer()
: m_child_one(nullptr), m_child_two(nullptr)
{
    set_has_window(false);
    set_redraw_on_allocate(false);
}

MyContainer::~MyContainer()
{
    /*
    // These calls to Gtk::Widget::unparent() are necessary if MyContainer ←
    is
    // deleted before its children. But if you use a version of gtkmm where ←
    bug
    // https://bugzilla.gnome.org/show_bug.cgi?id=605728
    // has not been fixed (gtkmm 3.7.10 or earlier) and the children are ←
    deleted
    // before the container, these calls can make the program crash.
    // That's because on_remove() is not called, when the children are ←
    deleted.
    if (m_child_one)
        m_child_one->unparent();

    if (m_child_two)
        m_child_two->unparent();
    */
}
```

```
*/
}

void MyContainer::set_child_widgets(Gtk::Widget& child_one,
    Gtk::Widget& child_two)
{
    m_child_one = &child_one;
    m_child_two = &child_two;

    m_child_one->set_parent(*this);
    m_child_two->set_parent(*this);
}

//This example container is a simplified VBox with at most two children.
Gtk::SizeRequestMode MyContainer::get_request_mode_vfunc() const
{
    return Gtk::SIZE_REQUEST_HEIGHT_FOR_WIDTH;
}

//Discover the total amount of minimum space and natural space needed by
//this container and its children.
void MyContainer::get_preferred_width_vfunc(int& minimum_width, int& ↵
    natural_width) const
{
    int child_minimum_width[2] = {0, 0};
    int child_natural_width[2] = {0, 0};

    if(m_child_one && m_child_one->get_visible())
        m_child_one->get_preferred_width(child_minimum_width[0], ↵
            child_natural_width[0]);

    if(m_child_two && m_child_two->get_visible())
        m_child_two->get_preferred_width(child_minimum_width[1], ↵
            child_natural_width[1]);

    //Request a width equal to the width of the widest visible child.
    minimum_width = std::max(child_minimum_width[0], child_minimum_width[1]) ↵
        ;
    natural_width = std::max(child_natural_width[0], child_natural_width[1]) ↵
        ;
}

void MyContainer::get_preferred_height_for_width_vfunc(int width,
    int& minimum_height, int& natural_height) const
{
    int child_minimum_height[2] = {0, 0};
    int child_natural_height[2] = {0, 0};
```

---

```
int nvis_children = 0;

if(m_child_one && m_child_one->get_visible())
{
    ++nvis_children;
    m_child_one->get_preferred_height_for_width(width, ↵
        child_minimum_height[0],
                                                child_natural_height[0]);
}

if(m_child_two && m_child_two->get_visible())
{
    ++nvis_children;
    m_child_two->get_preferred_height_for_width(width, ↵
        child_minimum_height[1],
                                                child_natural_height[1]);
}

//The allocated height will be divided equally among the visible ↵
    children.
//Request a height equal to the number of visible children times the ↵
    height
//of the highest child.
minimum_height = nvis_children * std::max(child_minimum_height[0],
                                            child_minimum_height[1]);
natural_height = nvis_children * std::max(child_natural_height[0],
                                            child_natural_height[1]);
}

void MyContainer::get_preferred_height_vfunc(int& minimum_height, int& ↵
    natural_height) const
{
    int child_minimum_height[2] = {0, 0};
    int child_natural_height[2] = {0, 0};
    int nvis_children = 0;

    if(m_child_one && m_child_one->get_visible())
    {
        ++nvis_children;
        m_child_one->get_preferred_height(child_minimum_height[0], ↵
            child_natural_height[0]);
    }

    if(m_child_two && m_child_two->get_visible())
    {
        ++nvis_children;
        m_child_two->get_preferred_height(child_minimum_height[1], ↵
```

---



```

        child_natural_height[1]);
    }

    //The allocated height will be divided equally among the visible ↵
    children.
    //Request a height equal to the number of visible children times the ↵
    height
    //of the highest child.
    minimum_height = nvis_children * std::max(child_minimum_height[0],
                                              child_minimum_height[1]);
    natural_height = nvis_children * std::max(child_natural_height[0],
                                              child_natural_height[1]);
}

void MyContainer::get_preferred_width_for_height_vfunc(int height,
    int& minimum_width, int& natural_width) const
{
    int child_minimum_width[2] = {0, 0};
    int child_natural_width[2] = {0, 0};
    int nvis_children = 0;

    //Get number of visible children.
    if(m_child_one && m_child_one->get_visible())
        ++nvis_children;
    if(m_child_two && m_child_two->get_visible())
        ++nvis_children;

    if(nvis_children > 0)
    {
        //Divide the height equally among the visible children.
        const int height_per_child = height / nvis_children;

        if(m_child_one && m_child_one->get_visible())
            m_child_one->get_preferred_width_for_height(height_per_child,
                child_minimum_width[0], child_natural_width[0]);

        if(m_child_two && m_child_two->get_visible())
            m_child_two->get_preferred_width_for_height(height_per_child,
                child_minimum_width[1], child_natural_width[1]);
    }

    //Request a width equal to the width of the widest child.
    minimum_width = std::max(child_minimum_width[0], child_minimum_width[1]) ↵
    ;
    natural_width = std::max(child_natural_width[0], child_natural_width[1]) ↵
    ;
}

```

---

```
void MyContainer::on_size_allocate(Gtk::Allocation& allocation)
{
    //Do something with the space that we have actually been given:
    //(We will not be given heights or widths less than we have requested, ↵
    though
    //we might get more.)

    //Use the offered allocation for this container:
    set_allocation(allocation);

    //Get number of visible children.
    int nvis_children = 0;
    if(m_child_one && m_child_one->get_visible())
        ++nvis_children;
    if(m_child_two && m_child_two->get_visible())
        ++nvis_children;

    if(nvis_children <= 0)
        return;

    //Assign space to the children:
    Gtk::Allocation child_allocation_one;
    Gtk::Allocation child_allocation_two;

    //Place the first child at the top-left:
    child_allocation_one.set_x( allocation.get_x() );
    child_allocation_one.set_y( allocation.get_y() );

    //Make it take up the full width available:
    child_allocation_one.set_width( allocation.get_width() );

    if(m_child_one && m_child_one->get_visible())
    {
        //Divide the height equally among the visible children.
        child_allocation_one.set_height( allocation.get_height() / ↵
            nvis_children);
        m_child_one->size_allocate(child_allocation_one);
    }
    else
        child_allocation_one.set_height(0);

    //Place the second child below the first child:
    child_allocation_two.set_x( allocation.get_x() );
    child_allocation_two.set_y( allocation.get_y() +
        child_allocation_one.get_height());
}
```

---

```
//Make it take up the full width available:
child_allocation_two.set_width( allocation.get_width() );

//Make it take up the remaining height:
child_allocation_two.set_height( allocation.get_height() -
    child_allocation_one.get_height() );

if(m_child_two && m_child_two->get_visible())
    m_child_two->size_allocate(child_allocation_two);
}

void MyContainer::forall_vfunc(gboolean, GtkCallback callback, gpointer ←
    callback_data)
{
    if(m_child_one)
        callback(m_child_one->gobj(), callback_data);

    if(m_child_two)
        callback(m_child_two->gobj(), callback_data);
}

void MyContainer::on_add(Gtk::Widget* child)
{
    if(!m_child_one)
    {
        m_child_one = child;
        m_child_one->set_parent(*this);
    }
    else if(!m_child_two)
    {
        m_child_two = child;
        m_child_two->set_parent(*this);
    }
}

void MyContainer::on_remove(Gtk::Widget* child)
{
    if(child)
    {
        const bool visible = child->get_visible();
        bool found = false;

        if(child == m_child_one)
        {
            m_child_one = nullptr;
            found = true;
        }
    }
}
```

---

```
        else if(child == m_child_two)
        {
            m_child_two = nullptr;
            found = true;
        }

        if(found)
        {
            child->unparent();

            if(visible)
                queue_resize();
        }
    }
}

GType MyContainer::child_type_vfunc() const
{
    //If there is still space for one widget, then report the type of widget ←
    that
    //may be added.
    if(!m_child_one || !m_child_two)
        return Gtk::Widget::get_type();
    else
    {
        //No more widgets may be added.
        return G_TYPE_NONE;
    }
}
```

## 28.2 Custom Widgets

By deriving directly from `Gtk::Widget` you can do all the drawing for your widget directly, instead of just arranging child widgets. For instance, a `Gtk::Label` draws the text of the label, but does not do this by using other widgets.

When deriving from `Gtk::Widget`, you should override the following virtual methods. The methods marked (optional) need not be overridden in all custom widgets. The base class's methods may be appropriate.

- `get_request_mode_vfunc()`: (optional) Return what `Gtk::SizeMode` is preferred by the widget.
  - `get_preferred_width_vfunc()`: Calculate the minimum and natural width of the widget.
-

- `get_preferred_height_vfunc()`: Calculate the minimum and natural height of the widget.
- `get_preferred_width_for_height_vfunc()`: Calculate the minimum and natural width of the widget, if it would be given the specified height.
- `get_preferred_height_for_width_vfunc()`: Calculate the minimum and natural height of the widget, if it would be given the specified width.
- `on_size_allocate()`: Position the widget, given the height and width that it has actually been given.
- `on_realize()`: Associate a `Gdk::Window` with the widget.
- `on_unrealize()`: (optional) Break the association with the `Gdk::Window`.
- `on_map()`: (optional)
- `on_unmap()`: (optional)
- `on_draw()`: Draw on the supplied `Cairo::Context`.

The first 6 methods in the previous table are also overridden in custom containers. They are briefly described in the [Custom Containers](#) section.

Most custom widgets need their own `Gdk::Window` to draw on. Then you can call `Gtk::Widget::set_has_window(true)` in your constructor. (This is the default value.) If you do not call `set_has_window(false)`, you must override `on_realize()` and call `Gtk::Widget::set_realized()` and `Gtk::Widget::set_window()` from there.

### 28.2.1 Custom Style Properties

You can add style properties to your widget class, whether it's derived directly from `Gtk::Widget` or from another widget class. The values of the style properties can be read from a CSS (Cascading Style Sheets) file. The users of your widget, or the users of an application program with your widget, can then modify the style of your widget without modifying the source code. Useful classes are `Gtk::StyleProperty` and `Gtk::CssProvider`. With `Gtk::Widget::get_style_property()` you can read the values of both your own style properties and those of your widget's base class. Note that style properties are not wrapped in gtkmm. See GTK+'s documentation for lists of existing style properties. The following example shows a simple use of a custom style property.

### 28.2.2 Example

This example implements a widget which draws a Penrose triangle.




Figure 28.2: Custom Widget

### Source Code

File: `examplewindow.h` (For use with `gtkmm 3`)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>
#include "mywidget.h"

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
    virtual ~ExampleWindow();

protected:
    //Signal handlers:
    void on_button_quit();

    //Child widgets:
    Gtk::Box m_VBox;
    MyWidget m_MyWidget;
```

```
    Gtk::ButtonBox m_ButtonBox;  
    Gtk::Button m_Button_Quit;  
};  
  
#endif //GTKMM_EXAMPLEWINDOW_H
```

**File: myextrainit.h (For use with gtkmm 3)**

```
#ifndef GTKMM_CUSTOM_WIDGET_MYEXTRAINIT_H  
#define GTKMM_CUSTOM_WIDGET_MYEXTRAINIT_H  
  
#include <glibmmconfig.h>  
  
#define HAS_EXTRA_CLASS_INIT (GLIBMM_MAJOR_VERSION > 2 || \  
    (GLIBMM_MAJOR_VERSION == 2 && GLIBMM_MINOR_VERSION >= 60))  
  
#if HAS_EXTRA_CLASS_INIT  
  
#include <glibmm/extraclassinit.h>  
#include <glibmm/ustring.h>  
  
// Calls gtk_widget_class_set_css_name() in the class init function  
// and gtk_set_has_window() in the instance init function.  
class MyExtraInit : public Glib::ExtraClassInit  
{  
public:  
    MyExtraInit(const Glib::ustring& css_name);  
  
private:  
    Glib::ustring m_css_name;  
};  
  
#endif // HAS_EXTRA_CLASS_INIT  
  
#endif //GTKMM_CUSTOM_WIDGET_MYEXTRAINIT_H
```

**File: mywidget.h (For use with gtkmm 3)**

```
#ifndef GTKMM_CUSTOM_WIDGET_MYWIDGET_H  
#define GTKMM_CUSTOM_WIDGET_MYWIDGET_H  
  
#include <gtkmm/widget.h>  
#include <gtkmm/cssprovider.h>  
#include <gtkmm/styleproperty.h>  
#include "myextrainit.h"  
  
#if HAS_EXTRA_CLASS_INIT  
class MyWidget : public MyExtraInit, public Gtk::Widget
```

```

#else
class MyWidget : public Gtk::Widget
#endif
{
public:
    MyWidget();
    virtual ~MyWidget();

protected:

    //Overrides:
    Gtk::SizeRequestMode get_request_mode_vfunc() const override;
    void get_preferred_width_vfunc(int& minimum_width, int& natural_width) ←
        const override;
    void get_preferred_height_for_width_vfunc(int width, int& minimum_height ←
        , int& natural_height) const override;
    void get_preferred_height_vfunc(int& minimum_height, int& natural_height ←
        ) const override;
    void get_preferred_width_for_height_vfunc(int height, int& minimum_width ←
        , int& natural_width) const override;
    void on_size_allocate(Gtk::Allocation& allocation) override;
    void on_map() override;
    void on_unmap() override;
    void on_realize() override;
    void on_unrealize() override;
    bool on_draw(const Cairo::RefPtr<Cairo::Context>& cr) override;

    //Signal handler:
    void on_parsing_error(const Glib::RefPtr<const Gtk::CssSection>& section ←
        , const Glib::Error& error);

    Gtk::StyleProperty<int> m_scale_prop;
    Glib::RefPtr<Gdk::Window> m_refGdkWindow;
    Glib::RefPtr<Gtk::CssProvider> m_refCssProvider;

    int m_scale;
};

#endif //GTKMM_CUSTOM_WIDGET_MYWIDGET_H

```

File: examplewindow.cc (For use with gtkmm 3)

```

#include "examplewindow.h"

ExampleWindow::ExampleWindow()
: m_VBox(Gtk::ORIENTATION_VERTICAL),
  m_Button_Quit("Quit")
{

```



```
set_title("Custom Widget example");
set_border_width(6);
set_default_size(400, 200);

add(m_VBox);
m_VBox.pack_start(m_MyWidget, Gtk::PACK_EXPAND_WIDGET);
m_MyWidget.show();

m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);

m_ButtonBox.pack_start(m_Button_Quit, Gtk::PACK_SHRINK);
m_ButtonBox.set_border_width(6);
m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);
m_Button_Quit.signal_clicked().connect( sigc::mem_fun(*this, & ←
    ExampleWindow::on_button_quit) );

show_all_children();
}

ExampleWindow::~ExampleWindow()
{
}

void ExampleWindow::on_button_quit()
{
    hide();
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main(int argc, char *argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

**File: myextrainit.cc (For use with gtkmm 3)**

```
#include "myextrainit.h"
#include <gtkmm/widget.h>
#include <gtk/gtk.h>
```

---

```

#ifdef HAS_EXTRA_CLASS_INIT

namespace
{
    using BaseObjectType = GtkWidget;
    using BaseClassType = GtkWidgetClass;

    // Extra class init function.
    void class_init_function(void* g_class, void* class_data)
    {
        g_return_if_fail(GTK_IS_WIDGET_CLASS(g_class));

        const auto klass = static_cast<BaseClassType*>(g_class);
        const auto css_name = static_cast<Glib::ustring*>(class_data);

        gtk_widget_class_set_css_name(klass, css_name->c_str());
    }

    // Extra instance init function.
    void instance_init_function(GTypeInstance* instance, void* /* g_class */)
    {
        g_return_if_fail(GTK_IS_WIDGET(instance));

        gtk_widget_set_has_window(GTK_WIDGET(instance), true);
    }

} // anonymous namespace

MyExtraInit::MyExtraInit(const Glib::ustring& css_name)
:
Glib::ExtraClassInit(class_init_function, &m_css_name, ←
    instance_init_function),
m_css_name(css_name)
{
}

#endif // HAS_EXTRA_CLASS_INIT

```

**File: mywidget.cc (For use with gtkmm 3)**

```

#include "mywidget.h"
#include <gdkmm/general.h> // for cairo helper functions
#include <iostream>
// #include <gtk/gtkwidget.h> //For GTK_IS_WIDGET()
#include <cstring>

```

```

// The MyWidget class uses API which was added in gtkmm 3.15.3 (Gtk::↵
    CssProviderError,
// Gtk::CssProvider::signal_parsing_error() and Gtk::CssSection) and in ↵
    gtkmm 3.15.2
// (Gtk::StyleProperty) and in glibmm 2.60.0 (Glib::ExtraClassInit).

MyWidget::MyWidget() :
    //The GType name will actually be gtkmm__CustomObject_mywidget
    Glib::ObjectBase("mywidget"),
#if HAS_EXTRA_CLASS_INIT
    MyExtraInit("my-widget-class"), // CSS node name, which must be used in ↵
        the CSS file.
#endif
    Gtk::Widget(),
    //Install a style property so that an aspect of this widget may be ↵
        themed
    //via a CSS style sheet file:
    m_scale_prop(*this, "example_scale", 500),
    m_scale(1000)
{
#if HAS_EXTRA_CLASS_INIT == 0
    set_has_window(true);
    // Set the widget name to use in the CSS file.
    set_name("my-widget-instance");
#endif

    //This shows the GType name, which must be used in the CSS file.
    std::cout << "GType name: " << G_OBJECT_TYPE_NAME(gobj()) << std::endl;

    //This shows that the GType still derives from GtkWidget:
    //std::cout << "Gtype is a GtkWidget?:" << GTK_IS_WIDGET(gobj()) << std ↵
        ::endl;

    // The CSS name can be set either
    // - for a GType (in this case for your custom class) with ↵
        gtk_widget_class_set_css_name(), or
    // - for a widget instance with gtk_widget_set_name() (Gtk::Widget:: ↵
        set_name()).
    //
    // gtk_widget_class_set_css_name() (new in gtk+ 3.19.1), if used, must ↵
        be called
    // in the class init function. It has not been wrapped in a C++ function ↵
        .
    // Gtk::Widget::set_name() can be called in a C++ constructor.
    //
    // Another alternative: The custom widget inherits the CSS name "widget" ↵
        from

```

---

```

// GtkWidget. That name can be used in the CSS file. This is not a very ↵
// good
// alternative. GtkWidget's CSS name is not documented. It can probably ↵
// be
// changed or removed in the future.

m_refCssProvider = Gtk::CssProvider::create();
auto refStyleContext = get_style_context();
refStyleContext->add_provider(m_refCssProvider,
    GTK_STYLE_PROVIDER_PRIORITY_APPLICATION);
m_refCssProvider->signal_parsing_error().connect(
    sigc::mem_fun(*this, &MyWidget::on_parsing_error));

try
{
    m_refCssProvider->load_from_path("custom_gtk.css");
}
catch(const Gtk::CssProviderError& ex)
{
    std::cerr << "CssProviderError, Gtk::CssProvider::load_from_path() ↵
        failed: "
        << ex.what() << std::endl;
}
catch(const Glib::Error& ex)
{
    std::cerr << "Error, Gtk::CssProvider::load_from_path() failed: "
        << ex.what() << std::endl;
}
}

MyWidget::~MyWidget()
{
}

Gtk::SizeRequestMode MyWidget::get_request_mode_vfunc() const
{
    //Accept the default value supplied by the base class.
    return Gtk::Widget::get_request_mode_vfunc();
}

//Discover the total amount of minimum space and natural space needed by
//this widget.
//Let's make this simple example widget always need minimum 60 by 50 and
//natural 100 by 70.
void MyWidget::get_preferred_width_vfunc(int& minimum_width, int& ↵
    natural_width) const
{

```

---

```
    minimum_width = 60;
    natural_width = 100;
}

void MyWidget::get_preferred_height_for_width_vfunc(int /* width */,
    int& minimum_height, int& natural_height) const
{
    minimum_height = 50;
    natural_height = 70;
}

void MyWidget::get_preferred_height_vfunc(int& minimum_height, int& ←
    natural_height) const
{
    minimum_height = 50;
    natural_height = 70;
}

void MyWidget::get_preferred_width_for_height_vfunc(int /* height */,
    int& minimum_width, int& natural_width) const
{
    minimum_width = 60;
    natural_width = 100;
}

void MyWidget::on_size_allocate(Gtk::Allocation& allocation)
{
    //Do something with the space that we have actually been given:
    //(We will not be given heights or widths less than we have requested, ←
    //though
    //(we might get more)

    //Use the offered allocation for this container:
    set_allocation(allocation);

    if(m_refGdkWindow)
    {
        m_refGdkWindow->move_resize( allocation.get_x(), allocation.get_y(),
            allocation.get_width(), allocation.get_height() );
    }
}

void MyWidget::on_map()
{
    //Call base class:
    Gtk::Widget::on_map();
}
```

---

```
void MyWidget::on_unmap()
{
    //Call base class:
    Gtk::Widget::on_unmap();
}

void MyWidget::on_realize()
{
    //Do not call base class Gtk::Widget::on_realize().
    //It's intended only for widgets that set_has_window(false).

    set_realized();

    //Get the themed style from the CSS file:
    m_scale = m_scale_prop.get_value();
    std::cout << "m_scale (example_scale from the theme/css-file) is: "
                << m_scale << std::endl;

    if(!m_refGdkWindow)
    {
        //Create the GdkWindow:

        GdkWindowAttr attributes;
        memset(&attributes, 0, sizeof(attributes));

        Gtk::Allocation allocation = get_allocation();

        //Set initial position and size of the Gdk::Window:
        attributes.x = allocation.get_x();
        attributes.y = allocation.get_y();
        attributes.width = allocation.get_width();
        attributes.height = allocation.get_height();

        attributes.event_mask = get_events () | Gdk::EXPOSURE_MASK;
        attributes.window_type = GDK_WINDOW_CHILD;
        attributes.wclass = GDK_INPUT_OUTPUT;

        m_refGdkWindow = Gdk::Window::create(get_parent_window(), &attributes,
                                             GDK_WA_X | GDK_WA_Y);
        set_window(m_refGdkWindow);

        //make the widget receive expose events
        m_refGdkWindow->set_user_data(gobj());
    }
}
```

---

```
void MyWidget::on_unrealize()
{
    m_refGdkWindow.reset();

    //Call base class:
    Gtk::Widget::on_unrealize();
}

bool MyWidget::on_draw(const Cairo::RefPtr<Cairo::Context>& cr)
{
    const Gtk::Allocation allocation = get_allocation();
    const double scale_x = (double)allocation.get_width() / m_scale;
    const double scale_y = (double)allocation.get_height() / m_scale;
    auto refStyleContext = get_style_context();

    // paint the background
    refStyleContext->render_background(cr,
        allocation.get_x(), allocation.get_y(),
        allocation.get_width(), allocation.get_height());

    // draw the foreground
    const auto state = refStyleContext->get_state();
    Gdk::Cairo::set_source_rgba(cr, refStyleContext->get_color(state));
    cr->move_to(155.*scale_x, 165.*scale_y);
    cr->line_to(155.*scale_x, 838.*scale_y);
    cr->line_to(265.*scale_x, 900.*scale_y);
    cr->line_to(849.*scale_x, 564.*scale_y);
    cr->line_to(849.*scale_x, 438.*scale_y);
    cr->line_to(265.*scale_x, 100.*scale_y);
    cr->line_to(155.*scale_x, 165.*scale_y);
    cr->move_to(265.*scale_x, 100.*scale_y);
    cr->line_to(265.*scale_x, 652.*scale_y);
    cr->line_to(526.*scale_x, 502.*scale_y);
    cr->move_to(369.*scale_x, 411.*scale_y);
    cr->line_to(633.*scale_x, 564.*scale_y);
    cr->move_to(369.*scale_x, 286.*scale_y);
    cr->line_to(369.*scale_x, 592.*scale_y);
    cr->move_to(369.*scale_x, 286.*scale_y);
    cr->line_to(849.*scale_x, 564.*scale_y);
    cr->move_to(633.*scale_x, 564.*scale_y);
    cr->line_to(155.*scale_x, 838.*scale_y);
    cr->stroke();

    return true;
}

void MyWidget::on_parsing_error(const Glib::RefPtr<const Gtk::CssSection>& ↵
```

```

        section, const Glib::Error& error)
{
    std::cerr << "on_parsing_error(): " << error.what() << std::endl;
    if (section)
    {
        const auto file = section->get_file();
        if (file)
        {
            std::cerr << "  URI = " << file->get_uri() << std::endl;
        }

        std::cerr << "  start_line = " << section->get_start_line()+1
                    << ", end_line = " << section->get_end_line()+1 << std::endl <↵
                    ;
        std::cerr << "  start_position = " << section->get_start_position()
                    << ", end_position = " << section->get_end_position() << std <↵
                    ::endl;
    }
}

```

**File:** custom\_gtk.css (For use with gtkmm 3)

```

/* Example of a CSS style sheet with a custom style property.
 *
 * The name of the style property must have its canonical form, i.e. <↵
 *   characters
 * other than ASCII letters, digits, and hyphens must be replaced by <↵
 *   hyphens.
 */

* {
    /* -<widget class name>-<style property canonical name>: <value>; */
    -gtkmm__CustomObject_mywidget-example-scale: 920;
}

my-widget-class {
    background-color: rgb(255,0,0);
    color:            rgb(0,0,255);
}

#my-widget-instance {
    background-color: rgb(255,128,0);
    color:            rgb(0,0,255);
}

```



## Chapter 29

# Multi-threaded programs

### 29.1 The constraints

Care is required when writing programs based on gtkmm using multiple threads of execution, arising from the fact that `libsigc++`, and in particular `sigc::trackable`, are not thread-safe. That's because none of the complex interactions that occur behind the scenes when using `libsigc++` are protected by a mutex or other means of synchronization.<sup>1</sup>

#### 29.1.1 The rules

This requires a number of rules to be observed when writing multi-threaded programs using gtkmm. These are set out below, but one point to note is that extra care is required when deriving classes from `sigc::trackable`, because the effects are unintuitive (see particularly points 4 and 5 below).

1. Use `Glib::Dispatcher` to invoke gtkmm functions from worker threads (this is dealt with in more detail in the next section).
2. A `sigc::signal` object should be regarded as owned by the thread which created it. Only that thread should connect a `sigc::slot` object to the signal object, and only that thread should

---

<sup>1</sup>These interactions arise from the fact that, amongst other things, a class inheriting from `sigc::trackable` will, via that inheritance, have a `std::list` object keeping track of slots created by calls to `sigc::mem_fun()` representing any of its non-static methods (more particularly it keeps a list of callbacks which will null the connected slots on its destruction). Each `sigc::slot` object also keeps, via `sigc::slot_rep`, its own `sigc::trackable` object to track any `sigc::connection` objects which it needs to inform about its demise, and also has a function to deregister itself from any `sigc::trackable` on disconnection or destruction. `sigc::signal` objects also keep lists of slots, which will be updated by a call to their `connect()` method or calls to any `sigc::connection` object relating to such a connection.

---

`emit()` or call `operator()()` on the signal, or null any connected `sigc::slot` object. It follows (amongst other things) that any signal object provided by a gtkmm widget should only be operated on in the main GUI thread and any object deriving from `sigc::trackable` having its non-static methods referenced by slots connected to the signal object should only be destroyed in that thread.

3. Any `sigc::connection` object should be regarded as owned by the thread in which the method returning the `sigc::connection` object was called. Only that thread should call `sigc::connection` methods on the object.
4. A `sigc::slot` object created by a call to `sigc::mem_fun()` which references a method of a class deriving from `sigc::trackable` should never be copied to another thread, nor destroyed by a different thread than the one which created it.
5. If a particular class object derives from `sigc::trackable`, only one thread should create `sigc::slot` objects representing any of the class's non-static methods by calling `sigc::mem_fun()`. The first thread to create such a slot should be regarded as owning the relevant object for the purpose of creating further slots referencing *any* of its non-static methods using that function, or nulling those slots by disconnecting them or destroying the trackable object.
6. Although glib is itself thread-safe, any glibmm wrappers which use `libsigc++` will not be. So for example, only the thread in which a main loop runs should call `Glib::SignalIdle::connect()`, `Glib::SignalIO::connect()`, `Glib::SignalTimeout::connect()`, `Glib::SignalTimeout::connect()` for that main loop, or manipulate any `sigc::connection` object returned by them.  
The `connect*_once()` variants, `Glib::SignalIdle::connect_once()`, `Glib::SignalTimeout::connect_once()`, `Glib::SignalTimeout::connect_seconds_once()`, are thread-safe for any case where the slot is not created by a call to `sigc::mem_fun()` which represents a method of a class deriving from `sigc::trackable`.

## 29.2 Using Glib::Dispatcher

The slots connected to `sigc::signal` objects execute in the thread which calls `emit()` or `operator()()` on the signal. `Glib::Dispatcher` does not behave this way: instead its connected slots execute in the thread in which the `Glib::Dispatcher` object was constructed (which must have a glib main loop). If a `Glib::Dispatcher` object is constructed in the main GUI thread (which will therefore be the receiver thread), any worker thread can emit on it and have the connected slots safely execute gtkmm functions.

Some thread safety rules on the use of `Glib::Dispatcher` still apply. As mentioned, a `Glib::Dispatcher` object must be constructed in the receiver thread (the thread in whose main loop it will execute its connected slots). By default this is the main program thread, although there is a `Glib::Dispatcher` constructor which can take the `Glib::MainContext` object of any thread which has a main loop. Only the receiver thread should call `connect()` on the `Glib::Dispatcher` object, or manipulate any related `sigc::connection` object, unless additional synchronization is employed. However, any

---

worker thread can safely emit on the `Glib::Dispatcher` object without any locking once the receiver thread has connected the slots, provided that it is constructed before the worker thread is started (if it is constructed after the thread has started, additional synchronization will normally be required to ensure visibility).

Aside from the fact that connected slots always execute in the receiver thread, `Glib::Dispatcher` objects are similar to `sigc::signal<void>` objects. They therefore cannot pass unbound arguments nor return a value. The best way to pass unbound arguments is with a thread-safe (asynchronous) queue. At the time of writing glibmm does not have one, although most people writing multi-threaded code will have one available to them (they are relatively easy to write although there are subtleties in combining thread safety with strong exception safety).

A `Glib::Dispatcher` object can be emitted on by the receiver thread as well as by a worker thread, although this should be done within reasonable bounds. On unix-like systems `Glib::Dispatcher` objects share a single common pipe, which could in theory at least fill up on a very heavily loaded system running a program with a very large number of `Dispatcher` objects in use. Were the pipe to fill up before the receiver thread's main loop has had an opportunity to read from it to empty it, and the receiver thread attempt to emit and so write to it when it is in that condition, the receiver thread would block on the write, so deadlocking. Where the receiver thread is to emit, a normal `sigc::signal<void>` object could of course be used instead.

## 29.3 Example

This is an example program with two threads, one GUI thread, like in all gtkmm programs, and one worker thread. The worker thread is created when you press the `Start work` button. It is deleted when the work is finished, when you press the `Stop work` button, or when you press the `Quit` button.

A `Glib::Dispatcher` is used for sending notifications from the worker thread to the GUI thread. The `ExampleWorker` class contains data which is accessed by both threads. This data is protected by a `std::mutex`. Only the GUI thread updates the GUI.

Compiling and linking a multi-threaded program can require special compiler and linker options. If you use the `g++` compiler, add the `-pthread` option. Other compilers may require other options. If you build with `meson`, it handles the multi-threading complications for you, if you add dependency `('threads')`.

---




Figure 29.1: Multi-Threaded Program

### Source Code

File: `examplewindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWINDOW_H
#define GTKMM_EXAMPLEWINDOW_H

#include <gtkmm.h>
#include "exampleworker.h"

class ExampleWindow : public Gtk::Window
{
public:
    ExampleWindow();
```

```
// Called from the worker thread.
void notify();

private:
// Signal handlers.
void on_start_button_clicked();
void on_stop_button_clicked();
void on_quit_button_clicked();

void update_start_stop_buttons();
void update_widgets();

// Dispatcher handler.
void on_notification_from_worker_thread();

// Member data.
Gtk::Box m_VBox;
Gtk::ButtonBox m_ButtonBox;
Gtk::Button m_ButtonStart;
Gtk::Button m_ButtonStop;
Gtk::Button m_ButtonQuit;
Gtk::ProgressBar m_ProgressBar;
Gtk::ScrolledWindow m_ScrolledWindow;
Gtk::TextView m_TextView;

Glib::Dispatcher m_Dispatcher;
ExampleWorker m_Worker;
std::thread* m_WorkerThread;
};

#endif // GTKMM_EXAMPLEWINDOW_H
```

File: exampleworker.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEWORKER_H
#define GTKMM_EXAMPLEWORKER_H

#include <gtkmm.h>
#include <thread>
#include <mutex>

class ExampleWindow;

class ExampleWorker
{
public:
    ExampleWorker();
```

```
// Thread function.
void do_work(ExampleWindow* caller);

void get_data(double* fraction_done, Glib::ustring* message) const;
void stop_work();
bool has_stopped() const;

private:
    // Synchronizes access to member data.
    mutable std::mutex m_Mutex;

    // Data used by both GUI thread and worker thread.
    bool m_shall_stop;
    bool m_has_stopped;
    double m_fraction_done;
    Glib::ustring m_message;
};

#endif // GTKMM_EXAMPLEWORKER_H
```

File: examplewindow.cc (For use with gtkmm 3)

```
#include "examplewindow.h"
#include <iostream>

ExampleWindow::ExampleWindow() :
    m_VBox(Gtk::ORIENTATION_VERTICAL, 5),
    m_ButtonBox(Gtk::ORIENTATION_HORIZONTAL),
    m_ButtonStart("Start work"),
    m_ButtonStop("Stop work"),
    m_ButtonQuit("_Quit", /* mnemonic= */ true),
    m_ProgressBar(),
    m_ScrolledWindow(),
    m_TextView(),
    m_Dispatcher(),
    m_Worker(),
    m_WorkerThread(nullptr)
{
    set_title("Multi-threaded example");
    set_border_width(5);
    set_default_size(300, 300);

    add(m_VBox);

    // Add the ProgressBar.
    m_VBox.pack_start(m_ProgressBar, Gtk::PACK_SHRINK);
```

```
m_ProgressBar.set_text("Fraction done");
m_ProgressBar.set_show_text();

// Add the TextView, inside a ScrolledWindow.
m_ScrolledWindow.add(m_TextView);

// Only show the scrollbars when they are necessary.
m_ScrolledWindow.set_policy(Gtk::POLICY_AUTOMATIC, Gtk::POLICY_AUTOMATIC ↵
);

m_VBox.pack_start(m_ScrolledWindow);

m_TextView.set_editable(false);

// Add the buttons to the ButtonBox.
m_VBox.pack_start(m_ButtonBox, Gtk::PACK_SHRINK);

m_ButtonBox.pack_start(m_ButtonStart, Gtk::PACK_SHRINK);
m_ButtonBox.pack_start(m_ButtonStop, Gtk::PACK_SHRINK);
m_ButtonBox.pack_start(m_ButtonQuit, Gtk::PACK_SHRINK);
m_ButtonBox.set_border_width(5);
m_ButtonBox.set_spacing(5);
m_ButtonBox.set_layout(Gtk::BUTTONBOX_END);

// Connect the signal handlers to the buttons.
m_ButtonStart.signal_clicked().connect(sigc::mem_fun(*this, & ↵
    ExampleWindow::on_start_button_clicked));
m_ButtonStop.signal_clicked().connect(sigc::mem_fun(*this, & ↵
    ExampleWindow::on_stop_button_clicked));
m_ButtonQuit.signal_clicked().connect(sigc::mem_fun(*this, & ↵
    ExampleWindow::on_quit_button_clicked));

// Connect the handler to the dispatcher.
m_Dispatcher.connect(sigc::mem_fun(*this, &ExampleWindow:: ↵
    on_notification_from_worker_thread));

// Create a text buffer mark for use in update_widgets().
auto buffer = m_TextView.get_buffer();
buffer->create_mark("last_line", buffer->end(), /* left_gravity= */ true ↵
);

update_start_stop_buttons();

show_all_children();
}

void ExampleWindow::on_start_button_clicked()
```

---

```
{
    if (m_WorkerThread)
    {
        std::cout << "Can't start a worker thread while another one is running ↵
        ." << std::endl;
    }
    else
    {
        // Start a new worker thread.
        m_WorkerThread = new std::thread(
            [this]
            {
                m_Worker.do_work(this);
            });
        update_start_stop_buttons();
    }
}

void ExampleWindow::on_stop_button_clicked()
{
    if (!m_WorkerThread)
    {
        std::cout << "Can't stop a worker thread. None is running." << std:: ↵
        endl;
    }
    else
    {
        // Order the worker thread to stop.
        m_Worker.stop_work();
        m_ButtonStop.set_sensitive(false);
    }
}

void ExampleWindow::update_start_stop_buttons()
{
    const bool thread_is_running = m_WorkerThread != nullptr;

    m_ButtonStart.set_sensitive(!thread_is_running);
    m_ButtonStop.set_sensitive(thread_is_running);
}

void ExampleWindow::update_widgets()
{
    double fraction_done;
    Glib::ustring message_from_worker_thread;
    m_Worker.get_data(&fraction_done, &message_from_worker_thread);
}
```

---



```
m_ProgressBar.set_fraction(fraction_done);

if (message_from_worker_thread != m_TextView.get_buffer()->get_text())
{
    auto buffer = m_TextView.get_buffer();
    buffer->set_text(message_from_worker_thread);

    // Scroll the last inserted line into view. That's somewhat ↵
    complicated.
    Gtk::TextIter iter = buffer->end();
    iter.set_line_offset(0); // Beginning of last line
    auto mark = buffer->get_mark("last_line");
    buffer->move_mark(mark, iter);
    m_TextView.scroll_to(mark);
    // TextView::scroll_to(iter) is not perfect.
    // We do need a TextMark to always get the last line into view.
}
}

void ExampleWindow::on_quit_button_clicked()
{
    if (m_WorkerThread)
    {
        // Order the worker thread to stop and wait for it to stop.
        m_Worker.stop_work();
        if (m_WorkerThread->joinable())
            m_WorkerThread->join();
    }
    hide();
}

// notify() is called from ExampleWorker::do_work(). It is executed in the ↵
// worker
// thread. It triggers a call to on_notification_from_worker_thread(), ↵
// which is
// executed in the GUI thread.
void ExampleWindow::notify()
{
    m_Dispatcher.emit();
}

void ExampleWindow::on_notification_from_worker_thread()
{
    if (m_WorkerThread && m_Worker.has_stopped())
    {
        // Work is done.
        if (m_WorkerThread->joinable())
```

---

```
        m_WorkerThread->join();
        delete m_WorkerThread;
        m_WorkerThread = nullptr;
        update_start_stop_buttons();
    }
    update_widgets();
}
```

**File:** `exampleworker.cc` (For use with gtkmm 3)

```
#include "exampleworker.h"
#include "examplewindow.h"
#include <sstream>
#include <chrono>

ExampleWorker::ExampleWorker() :
    m_Mutex(),
    m_shall_stop(false),
    m_has_stopped(false),
    m_fraction_done(0.0),
    m_message()
{
}

// Accesses to these data are synchronized by a mutex.
// Some microseconds can be saved by getting all data at once, instead of ←
// having
// separate get_fraction_done() and get_message() methods.
void ExampleWorker::get_data(double* fraction_done, Glib::ustring* message ←
    ) const
{
    std::lock_guard<std::mutex> lock(m_Mutex);

    if (fraction_done)
        *fraction_done = m_fraction_done;

    if (message)
        *message = m_message;
}

void ExampleWorker::stop_work()
{
    std::lock_guard<std::mutex> lock(m_Mutex);
    m_shall_stop = true;
}

bool ExampleWorker::has_stopped() const
{
}
```

---

```
std::lock_guard<std::mutex> lock(m_Mutex);
return m_has_stopped;
}

void ExampleWorker::do_work(ExampleWindow* caller)
{
    {
        std::lock_guard<std::mutex> lock(m_Mutex);
        m_has_stopped = false;
        m_fraction_done = 0.0;
        m_message = "";
    } // The mutex is unlocked here by lock's destructor.

    // Simulate a long calculation.
    for (int i = 0; ; ++i) // do until break
    {
        std::this_thread::sleep_for(std::chrono::milliseconds(250));

        {
            std::lock_guard<std::mutex> lock(m_Mutex);

            m_fraction_done += 0.01;

            if (i % 4 == 3)
            {
                std::ostringstream ostr;
                ostr << (m_fraction_done * 100.0) << "% done\n";
                m_message += ostr.str();
            }

            if (m_fraction_done >= 1.0)
            {
                m_message += "Finished";
                break;
            }
            if (m_shall_stop)
            {
                m_message += "Stopped";
                break;
            }
        }

        caller->notify();
    }

    {
        std::lock_guard<std::mutex> lock(m_Mutex);
```

```
        m_shall_stop = false;
        m_has_stopped = true;
    }

    caller->notify();
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "examplewindow.h"
#include <gtkmm/application.h>

int main (int argc, char* argv[])
{
    auto app = Gtk::Application::create(argc, argv, "org.gtkmm.example");

    ExampleWindow window;

    //Shows the window and returns when it is closed.
    return app->run(window);
}
```

## Chapter 30

# Recommended Techniques

This section is simply a gathering of wisdom, general style guidelines and hints for creating gtkmm applications.

Use Meson! It is your friend :) It examines C and C++ files, determines how they depend on each other, and generates `build.ninja` or an equivalent file so the files can be compiled in the correct order. Meson permits automatic configuration of software installation, handling a large number of system quirks to increase portability.

Subclass `Widgets` to better organize your code. You should probably subclass your main `Window` at least. Then you can make your child `Widgets` and signal handlers members of that class.

Create your own signals instead of passing pointers around. Objects can communicate with each other via signals and signal handlers. This is much simpler than objects holding pointers to each other and calling each other's methods. gtkmm's classes use special versions of `sigc::signal`, but you should use normal `sigc::signals`, as described in the libsigc++ documentation.

### 30.1 Application Lifetime

Most applications will have only one `Window`, or only one main window. These applications can use the `Gtk::Application::run(Gtk::Window&)` overload. It shows the window and returns when the window has been hidden. This might happen when the user closes the window, or when your code decides to `hide()` the window. You can prevent the user from closing the window (for instance, if there are unsaved changes) by overriding `Gtk::Window::on_delete_event()`.

Most of our examples use this technique.

---

## 30.2 Using a gtkmm widget

Our examples all tend to have the same structure. They follow these steps for using a `Widget`:

1. Declare a variable of the type of `Widget` you wish to use, generally as member variable of a derived container class. You could also declare a pointer to the widget type, and then create it with `new` in your code. Even when using the widget via a pointer, it's still probably best to make that pointer a member variable of a container class so that you can access it later.
2. Set the attributes of the widget. If the widget has no default constructor, then you will need to initialize the widget in the initializer list of your container class's constructor.
3. Connect any signals you wish to use to the appropriate handlers.
4. Pack the widget into a container using the appropriate call, e.g. `Gtk::Container::add()` or `pack_start()`.
5. Call `show()` to display the widget.

`Gtk::Widget::show()` lets gtkmm know that we have finished setting the attributes of the widget, and that it is ready to be displayed. You can use `Gtk::Widget::hide()` to make it disappear again. The order in which you show the widgets is not important, but we do suggest that you show the top-level window last; this way, the whole window will appear with its contents already drawn. Otherwise, the user will first see a blank window, into which the widgets will be gradually drawn.

## Chapter 31

# Building applications

This chapter is similar to *Building applications* and following sections in the [Getting Started](#) chapter in the GTK3 documentation. The same application is built, but gtkmm is used instead of GTK.

An application consists of a number of files:

**The binary file** This gets installed in `/usr/bin`.

**A desktop file** The desktop file provides important information about the application to the desktop shell, such as its name, icon, D-Bus name, commandline to launch it, etc. It is installed in `/usr/share/applications`.

**An icon** The icon gets installed in `/usr/share/icons/hicolor/48x48/apps`, where it will be found regardless of the current theme.

**A settings schema** If the application uses `Gio::Settings`, it will install its schema in `/usr/share/glib-2.0/schemas`, so that tools like `dconf-editor` can find it.

**Other resources** Other files, such as `Gtk::Builder` ui files, are best loaded from resources stored in the application binary itself. This eliminates the need for most of the files that would traditionally be installed in an application-specific location in `/usr/share`.

gtkmm includes application support that is built on top of `Gio::Application`. In this chapter we'll build a simple application by starting from scratch, adding more and more pieces over time. Along the way, we'll learn about `Gtk::Application`, `Gtk::Builder`, resources, application menus, settings, `Gtk::HeaderBar`, `Gtk::Stack`, `Gtk::SearchBar`, `Gtk::ListBox`, and more.

The full, buildable sources for these examples can be found in the `examples/book/buildapp` directory of the gtkmm-documentation source distribution, or online in the [gtkmm-documentation git repository](#). You can build each example separately by using **meson** and **ninja** with the `meson.build` file or by using **make** with the `Makefile.example` file. For more information, see the README included in the `buildapp` directory.

---

## 31.1 A trivial application

When using `Gtk::Application`, the `main()` function can be very simple. We just call `Gio::Application::run()` on an instance of our application class.

All the application logic is in the application class, which is a subclass of `Gtk::Application`. Our example does not yet have any interesting functionality. All it does is open a window when it is activated without arguments, and open the files it is given, if it is started with arguments. (Or rather, our application class tries to open the files, but our subclassed application window does not yet do what it's told to do.)

To handle these two cases, we override `signal_activate()`'s default handler, which gets called when the application is launched without commandline arguments, and `signal_open()`'s default handler, which gets called when the application is launched with commandline arguments.

### [Gio::Application Reference](#)

Another important class that is part of the application support in gtkmm is `Gtk::ApplicationWindow`. It is typically subclassed as well. Our subclass does not do anything yet, so we will just get an empty window.

As part of the initial setup of our application, we also create an icon and a desktop file. Note that `@bindir@` in the desktop file needs to be replaced with the actual path to the binary before this desktop file can be used.

Here is what we've achieved so far:

---






Figure 31.1: A trivial application

This does not look very impressive yet, but our application is already presenting itself on the session bus, it has single-instance semantics, and it accepts files as commandline arguments.

#### Source Code

File: `exampleapplication.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEAPPLICATION_H
#define GTKMM_EXAMPLEAPPLICATION_H

#include <gtkmm.h>

class ExampleAppWindow;

class ExampleApplication: public Gtk::Application
{
protected:
    ExampleApplication();

public:
    static Glib::RefPtr<ExampleApplication> create();

protected:
```

```
// Override default signal handlers:
void on_activate() override;
void on_open(const Gio::Application::type_vec_files& files,
             const Glib::ustring& hint) override;

private:
    ExampleAppWindow* create_appwindow();
    void on_hide_window(Gtk::Window* window);
};

#endif /* GTKMM_EXAMPLEAPPLICATION_H */
```

File: exampleappwindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEAPPWINDOW_H_
#define GTKMM_EXAMPLEAPPWINDOW_H_

#include <gtkmm.h>

class ExampleAppWindow : public Gtk::ApplicationWindow
{
public:
    ExampleAppWindow();

    void open_file_view(const Glib::RefPtr<Gio::File>& file);
};

#endif /* GTKMM_EXAMPLEAPPWINDOW_H_ */
```

File: exampleapplication.cc (For use with gtkmm 3)

```
#include "exampleapplication.h"
#include "exampleappwindow.h"

ExampleApplication::ExampleApplication()
: Gtk::Application("org.gtkmm.examples.application", Gio:: ↵
  APPLICATION_HANDLES_OPEN)
{
}

Glib::RefPtr<ExampleApplication> ExampleApplication::create()
{
    return Glib::RefPtr<ExampleApplication>(new ExampleApplication());
}

ExampleAppWindow* ExampleApplication::create_appwindow()
{
    auto appwindow = new ExampleAppWindow();
```

```
// Make sure that the application runs for as long this window is still ←
open.
add_window(*appwindow);

// Gtk::Application::add_window() connects a signal handler to the ←
window's
// signal_hide(). That handler removes the window from the application.
// If it's the last window to be removed, the application stops running.
// Gtk::Window::set_application() does not connect a signal handler, but ←
is
// otherwise equivalent to Gtk::Application::add_window().

// Delete the window when it is hidden.
appwindow->signal_hide().connect(sigc::bind<Gtk::Window*>(sigc::mem_fun ←
(*this,
&ExampleApplication::on_hide_window), appwindow));

return appwindow;
}

void ExampleApplication::on_activate()
{
    // The application has been started, so let's show a window.
    auto appwindow = create_appwindow();
    appwindow->present();
}

void ExampleApplication::on_open(const Gio::Application::type_vec_files& ←
files,
const Glib::ustring& /* hint */)
{
    // The application has been asked to open some files,
    // so let's open a new view for each one.
    ExampleAppWindow* appwindow = nullptr;
    auto windows = get_windows();
    if (windows.size() > 0)
        appwindow = dynamic_cast<ExampleAppWindow*>(windows[0]);

    if (!appwindow)
        appwindow = create_appwindow();

    for (const auto& file : files)
        appwindow->open_file_view(file);

    appwindow->present();
}
```

---

```
void ExampleApplication::on_hide_window(Gtk::Window* window)
{
    delete window;
}
```

File: exampleappwindow.cc (For use with gtkmm 3)

```
#include "exampleappwindow.h"

ExampleAppWindow::ExampleAppWindow()
: Gtk::ApplicationWindow()
{
}

void ExampleAppWindow::open_file_view(const Glib::RefPtr<Gio::File>& /* ←
    file */)
{
}
```

File: main.cc (For use with gtkmm 3)

```
#include "exampleapplication.h"

int main(int argc, char* argv[])
{
    auto application = ExampleApplication::create();

    // Start the application, showing the initial window,
    // and opening extra views for any files that it is asked to open,
    // for instance as a command-line parameter.
    // run() will return when the last window has been closed.
    return application->run(argc, argv);
}
```

File: exampleapp.desktop.in (For use with gtkmm 3)

```
[Desktop Entry]
Type=Application
Name=Gtkmm example
GenericName=Example
Comment=From the "Programming with gtkmm 3" tutorial
Icon=exampleapp
StartupNotify=true
Exec=@bindir@/exampleapp %U
Categories=GNOME;GTK;Utility
```

---

## 31.2 Populating the window

In this step, we use a `Gtk::Builder` instance to associate a `Gtk::Builder` ui file with our application window class.

Our simple ui file puts a `Gtk::HeaderBar` on top of a `Gtk::Stack` widget. The header bar contains a `Gtk::StackSwitcher`, which is a standalone widget to show a row of 'tabs' for the pages of a `Gtk::Stack`.

To make use of this file in our application, we revisit our `Gtk::ApplicationWindow` subclass, and call `Gtk::Builder::create_from_resource()` and `Gtk::Builder::get_widget_derived()` from the `ExampleAppWindow::create()` method to get an instance of our subclassed `Gtk::ApplicationWindow`. See the [Using derived widgets](#) section for more information about `get_widget_derived()`.

You may have noticed that we use the `_from_resource()` variant of the method that reads the ui file. Now we need to use GLib's resource functionality to include the ui file in the binary. This is commonly done by listing all resources in a `.gresource.xml` file. This file has to be converted into a C source file that will be compiled and linked into the application together with the other source files. To do so, we use the `glib-compile-resources` utility:

```
$ glib-compile-resources --target=resources.c --generate-source exampleapp ↵  
  .gresource.xml
```

The [Gio::Resource](#) and `glib-compile-resources` section contains more information about resource files. If you build with Meson, use the `compile_resources()` function in Meson's [GNOME module](#).

Our application now looks like this:

---




Figure 31.2: Populating the window

### Source Code

File: `exampleapplication.h` (For use with gtkmm 3)

```
#include "../step1/exampleapplication.h"  
// Equal to the corresponding file in step1
```

File: `exampleappwindow.h` (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEAPPWINDOW_H_  
#define GTKMM_EXAMPLEAPPWINDOW_H_  
  
#include <gtkmm.h>  
  
class ExampleAppWindow : public Gtk::ApplicationWindow  
{  
public:
```

```

    ExampleAppWindow(BaseObjectType* cobject,
        const Glib::RefPtr<Gtk::Builder>& refBuilder);

    static ExampleAppWindow* create();

    void open_file_view(const Glib::RefPtr<Gio::File>& file);

protected:
    Glib::RefPtr<Gtk::Builder> m_refBuilder;
};

#endif /* GTKMM_EXAMPLEAPPWINDOW_H */

```

File: `exampleapplication.cc` (For use with gtkmm 3)

```

#include "exampleapplication.h"
#include "exampleappwindow.h"
#include <iostream>
#include <exception>

ExampleApplication::ExampleApplication()
: Gtk::Application("org.gtkmm.examples.application", Gio:: ↵
    APPLICATION_HANDLES_OPEN)
{
}

Glib::RefPtr<ExampleApplication> ExampleApplication::create()
{
    return Glib::RefPtr<ExampleApplication>(new ExampleApplication());
}

ExampleAppWindow* ExampleApplication::create_appwindow()
{
    auto appwindow = ExampleAppWindow::create();

    // Make sure that the application runs for as long this window is still ↵
    // open.
    add_window(*appwindow);

    // Gtk::Application::add_window() connects a signal handler to the ↵
    // window's
    // signal_hide(). That handler removes the window from the application.
    // If it's the last window to be removed, the application stops running.
    // Gtk::Window::set_application() does not connect a signal handler, but ↵
    // is
    // otherwise equivalent to Gtk::Application::add_window().

    // Delete the window when it is hidden.

```

```
appwindow->signal_hide().connect(sigc::bind<Gtk::Window*>(sigc::mem_fun( ←
    (*this,
    &ExampleApplication::on_hide_window), appwindow));

return appwindow;
}

void ExampleApplication::on_activate()
{
    try
    {
        // The application has been started, so let's show a window.
        auto appwindow = create_appwindow();
        appwindow->present();
    }
    // If create_appwindow() throws an exception (perhaps from Gtk::Builder) ←
    // no window has been created, no window has been added to the ←
    // application,
    // and therefore the application will stop running.
    catch (const Glib::Error& ex)
    {
        std::cerr << "ExampleApplication::on_activate(): " << ex.what() << std:: ←
        ::endl;
    }
    catch (const std::exception& ex)
    {
        std::cerr << "ExampleApplication::on_activate(): " << ex.what() << std:: ←
        ::endl;
    }
}

void ExampleApplication::on_open(const Gio::Application::type_vec_files& ←
    files,
    const Glib::ustring& /* hint */)
{
    // The application has been asked to open some files,
    // so let's open a new view for each one.
    ExampleAppWindow* appwindow = nullptr;
    auto windows = get_windows();
    if (windows.size() > 0)
        appwindow = dynamic_cast<ExampleAppWindow*>(windows[0]);

    try
    {
        if (!appwindow)
            appwindow = create_appwindow();
    }
```

---



```
        for (const auto& file : files)
            appwindow->open_file_view(file);

        appwindow->present();
    }
    catch (const Glib::Error& ex)
    {
        std::cerr << "ExampleApplication::on_open(): " << ex.what() << std::endl;
    }
    catch (const std::exception& ex)
    {
        std::cerr << "ExampleApplication::on_open(): " << ex.what() << std::endl;
    }
}

void ExampleApplication::on_hide_window(Gtk::Window* window)
{
    delete window;
}
```

**File:** exampleappwindow.cc (For use with gtkmm 3)

```
#include "exampleappwindow.h"
#include <stdexcept>

ExampleAppWindow::ExampleAppWindow(BaseObjectType* cobject,
    const Glib::RefPtr<Gtk::Builder>& refBuilder)
: Gtk::ApplicationWindow(cobject),
  m_refBuilder(refBuilder)
{
}

//static
ExampleAppWindow* ExampleAppWindow::create()
{
    // Load the Builder file and instantiate its widgets.
    auto refBuilder = Gtk::Builder::create_from_resource("/org/gtkmm/
        exampleapp/window.ui");

    ExampleAppWindow* window = nullptr;
    refBuilder->get_widget_derived("app_window", window);
    if (!window)
        throw std::runtime_error("No \"app_window\" object in window.ui");

    return window;
}
```

```
}

void ExampleAppWindow::open_file_view(const Glib::RefPtr<Gio::File>& /* ↵
    file */)
{
}
```

File: main.cc (For use with gtkmm 3)

```
#include "../step1/main.cc"
// Equal to the corresponding file in step1
```

File: exampleapp.gresource.xml (For use with gtkmm 3)

```
<?xml version="1.0" encoding="UTF-8"?>
<gresources>
  <gresource prefix="/org/gtkmm/exampleapp">
    <file preprocess="xml-stripblanks">window.ui</file>
  </gresource>
</gresources>
```

File: window.ui (For use with gtkmm 3)

```
<?xml version="1.0" encoding="UTF-8"?>
<interface>
  <!-- interface-requires gtk+ 3.8 -->
  <object class="GtkApplicationWindow" id="app_window">
    <property name="title" translatable="yes">Example Application</ ↵
      property>
    <property name="default-width">600</property>
    <property name="default-height">400</property>
    <child>
      <object class="GtkBox" id="content_box">
        <property name="visible">True</property>
        <property name="orientation">vertical</property>
        <child>
          <object class="GtkHeaderBar" id="header">
            <property name="visible">True</property>
            <child type="title">
              <object class="GtkStackSwitcher" id="tabs">
                <property name="visible">True</property>
                <property name="stack">stack</property>
              </object>
            </child>
          </object>
        </child>
      </object>
    </child>
    <child>
      <object class="GtkStack" id="stack">
```

```
        <property name="visible">True</property>
      </object>
    </child>
  </object>
</child>
</object>
</interface>
```

### 31.3 Opening files

In this step, we make our application show the contents of all the files that it is given on the commandline.

To this end, we add a data member to our application window and keep a pointer to the `Gtk::Stack` there. We get the pointer with a call to `Gtk::Builder::get_widget()` in the application window's constructor.

Now we revisit the `ExampleAppWindow::open_file_view()` method that is called for each commandline argument, and construct a `Gtk::TextView` that we then add as a page to the stack.

Note that we do not have to touch the stack switcher at all. It gets all its information from the stack that it belongs to. Here, we are passing the label to show for each file as the last argument to the `Gtk::Stack::add()` method.

Our application is beginning to take shape:




Figure 31.3: Opening files

### Source Code

File: exampleapplication.h (For use with gtkmm 3)

```

#include "../step1/exampleapplication.h"
// Equal to the corresponding file in step1

```

File: exampleappwindow.h (For use with gtkmm 3)

```

#ifndef GTKMM_EXAMPLEAPPWINDOW_H_
#define GTKMM_EXAMPLEAPPWINDOW_H_

#include <gtkmm.h>

class ExampleAppWindow : public Gtk::ApplicationWindow
{
public:

```

```

ExampleAppWindow(BaseObjectType* cobject,
    const Glib::RefPtr<Gtk::Builder>& refBuilder);

static ExampleAppWindow* create();

void open_file_view(const Glib::RefPtr<Gio::File>& file);

protected:
    Glib::RefPtr<Gtk::Builder> m_refBuilder;
    Gtk::Stack* m_stack;
};

#endif /* GTKMM_EXAMPLEAPPWINDOW_H */

```

**File:** exampleapplication.cc (For use with gtkmm 3)

```

#include "../step2/exampleapplication.cc"
// Equal to the corresponding file in step2

```

**File:** exampleappwindow.cc (For use with gtkmm 3)

```

#include "exampleappwindow.h"
#include <iostream>
#include <stdexcept>

ExampleAppWindow::ExampleAppWindow(BaseObjectType* cobject,
    const Glib::RefPtr<Gtk::Builder>& refBuilder)
: Gtk::ApplicationWindow(cobject),
  m_refBuilder(refBuilder),
  m_stack(nullptr)
{
    m_refBuilder->get_widget("stack", m_stack);
    if (!m_stack)
        throw std::runtime_error("No \"stack\" object in window.ui");
}

//static
ExampleAppWindow* ExampleAppWindow::create()
{
    // Load the Builder file and instantiate its widgets.
    auto refBuilder = Gtk::Builder::create_from_resource("/org/gtkmm/ ↵
        exampleapp/window.ui");

    ExampleAppWindow* window = nullptr;
    refBuilder->get_widget_derived("app_window", window);
    if (!window)
        throw std::runtime_error("No \"app_window\" object in window.ui");
}

```

```

    return window;
}

void ExampleAppWindow::open_file_view(const Glib::RefPtr<Gio::File>& file)
{
    const Glib::ustring basename = file->get_basename();

    auto scrolled = Gtk::make_managed<Gtk::ScrolledWindow>();
    scrolled->set_hexpand(true);
    scrolled->set_vexpand(true);
    scrolled->show();
    auto view = Gtk::make_managed<Gtk::TextView>();
    view->set_editable(false);
    view->set_cursor_visible(false);
    view->show();
    scrolled->add(*view);
    m_stack->add(*scrolled, basename, basename);

    try
    {
        char* contents = nullptr;
        gsize length = 0;

        file->load_contents(contents, length);
        view->get_buffer()->set_text(contents, contents+length);
        g_free(contents);
    }
    catch (const Glib::Error& ex)
    {
        std::cout << "ExampleAppWindow::open_file_view(\"" << file->get_parse_name()
            << "\"): \n  " << ex.what() << std::endl;
    }
}

```

File: main.cc (For use with gtkmm 3)

```

#include "../step1/main.cc"
// Equal to the corresponding file in step1

```

## 31.4 An application menu

An application menu is shown by GNOME shell at the top of the screen. It is meant to collect infrequently used actions that affect the whole application. The application menu is shown either at the top of the screen, or at the top of the application's window, depending on which desktop shell you use.

Just like the application window, we specify our application menu in a ui file, and add it as a resource to our binary.

To associate the app menu with the application, we have to call `Gtk::Application::set_app_menu()`. Since app menus work by activating `Gio::Actions`, we also have to add a suitable set of actions to our application.

Both of these tasks are best done in the `on_startup()` default signal handler, which is guaranteed to be called once for each primary application instance.

Our preferences menu item does not do anything yet, but the Quit menu item is fully functional. It can also be activated by the usual Ctrl-Q shortcut. The shortcut is added with `Gtk::Application::set_accel_for_action()`

The application menu looks like this:




Figure 31.4: An application menu

#### Source Code

File: `exampleapplication.h` (For use with gtkmm 3)

```

#ifndef GTKMM_EXAMPLEAPPLICATION_H
#define GTKMM_EXAMPLEAPPLICATION_H

#include <gtkmm.h>

class ExampleAppWindow;

class ExampleApplication: public Gtk::Application
{
protected:
    ExampleApplication();

public:
    static Glib::RefPtr<ExampleApplication> create();

protected:
    // Override default signal handlers:
    void on_startup() override;
    void on_activate() override;
    void on_open(const Gio::Application::type_vec_files& files,
        const Glib::ustring& hint) override;

private:
    ExampleAppWindow* create_appwindow();
    void on_hide_window(Gtk::Window* window);
    void on_action_preferences();
    void on_action_quit();
};

#endif /* GTKMM_EXAMPLEAPPLICATION_H */

```

**File: exampleappwindow.h (For use with gtkmm 3)**

```

#include "../step3/exampleappwindow.h"
// Equal to the corresponding file in step3

```

**File: exampleapplication.cc (For use with gtkmm 3)**

```

#include "exampleapplication.h"
#include "exampleappwindow.h"
#include <iostream>
#include <exception>

ExampleApplication::ExampleApplication()
: Gtk::Application("org.gtkmm.examples.application", Gio:: ↵
    APPLICATION_HANDLES_OPEN)
{

```

---



```
}

Glib::RefPtr<ExampleApplication> ExampleApplication::create()
{
    return Glib::RefPtr<ExampleApplication>(new ExampleApplication());
}

ExampleAppWindow* ExampleApplication::create_appwindow()
{
    auto appwindow = ExampleAppWindow::create();

    // Make sure that the application runs for as long this window is still ←
    // open.
    add_window(*appwindow);

    // Gtk::Application::add_window() connects a signal handler to the ←
    // window's
    // signal_hide(). That handler removes the window from the application.
    // If it's the last window to be removed, the application stops running.
    // Gtk::Window::set_application() does not connect a signal handler, but ←
    // is
    // otherwise equivalent to Gtk::Application::add_window().

    // Delete the window when it is hidden.
    appwindow->signal_hide().connect(sigc::bind<Gtk::Window*>(sigc::mem_fun ←
    (*this,
        &ExampleApplication::on_hide_window), appwindow));

    return appwindow;
}

void ExampleApplication::on_startup()
{
    // Call the base class's implementation.
    Gtk::Application::on_startup();

    // Add actions and keyboard accelerators for the application menu.
    add_action("preferences", sigc::mem_fun(*this, &ExampleApplication:: ←
    on_action_preferences));
    add_action("quit", sigc::mem_fun(*this, &ExampleApplication:: ←
    on_action_quit));
    set_accel_for_action("app.quit", "<Ctrl>Q");

    auto refBuilder = Gtk::Builder::create();
    try
    {
        refBuilder->add_from_resource("/org/gtkmm/exampleapp/app_menu.ui");
    }
}
```

---

```

    }
    catch (const Glib::Error& ex)
    {
        std::cerr << "ExampleApplication::on_startup(): " << ex.what() << std::endl;
        return;
    }

    auto object = refBuilder->get_object("appmenu");
    auto app_menu = Glib::RefPtr<Gio::MenuModel>::cast_dynamic(object);
    if (app_menu)
        set_app_menu(app_menu);
    else
        std::cerr << "ExampleApplication::on_startup(): No \"appmenu\" object in app_menu.ui"
                    << std::endl;
}

void ExampleApplication::on_activate()
{
    try
    {
        // The application has been started, so let's show a window.
        auto appwindow = create_appwindow();
        appwindow->present();
    }
    // If create_appwindow() throws an exception (perhaps from Gtk::Builder)
    // no window has been created, no window has been added to the application,
    // and therefore the application will stop running.
    catch (const Glib::Error& ex)
    {
        std::cerr << "ExampleApplication::on_activate(): " << ex.what() << std::endl;
    }
    catch (const std::exception& ex)
    {
        std::cerr << "ExampleApplication::on_activate(): " << ex.what() << std::endl;
    }
}

void ExampleApplication::on_open(const Gio::Application::type_vec_files& files,
    const Glib::ustring& /* hint */)
{

```

---

```
// The application has been asked to open some files,
// so let's open a new view for each one.
ExampleAppWindow* appwindow = nullptr;
auto windows = get_windows();
if (windows.size() > 0)
    appwindow = dynamic_cast<ExampleAppWindow*>(windows[0]);

try
{
    if (!appwindow)
        appwindow = create_appwindow();

    for (const auto& file : files)
        appwindow->open_file_view(file);

    appwindow->present();
}
catch (const Glib::Error& ex)
{
    std::cerr << "ExampleApplication::on_open(): " << ex.what() << std::endl;
}
catch (const std::exception& ex)
{
    std::cerr << "ExampleApplication::on_open(): " << ex.what() << std::endl;
}
}

void ExampleApplication::on_hide_window(Gtk::Window* window)
{
    delete window;
}

void ExampleApplication::on_action_preferences()
{
}

void ExampleApplication::on_action_quit()
{
    // Gio::Application::quit() will make Gio::Application::run() return,
    // but it's a crude way of ending the program. The window is not removed
    // from the application. Neither the window's nor the application's
    // destructors will be called, because there will be remaining reference
    // counts in both of them. If we want the destructors to be called, we
    // must remove the window from the application. One way of doing this
```

```

// is to hide the window. See comment in create_appwindow().
auto windows = get_windows();
for (auto window : windows)
    window->hide();

// Not really necessary, when Gtk::Widget::hide() is called, unless
// Gio::Application::hold() has been called without a corresponding call
// to Gio::Application::release().
quit();
}

```

**File:** exampleappwindow.cc (For use with gtkmm 3)

```

#include "../step3/exampleappwindow.cc"
// Equal to the corresponding file in step3

```

**File:** main.cc (For use with gtkmm 3)

```

#include "../step1/main.cc"
// Equal to the corresponding file in step1

```

**File:** exampleapp.gresource.xml (For use with gtkmm 3)

```

<?xml version="1.0" encoding="UTF-8"?>
<gresources>
  <gresource prefix="/org/gtkmm/exampleapp">
    <file preprocess="xml-stripblanks">window.ui</file>
    <file preprocess="xml-stripblanks">app_menu.ui</file>
  </gresource>
</gresources>

```

**File:** app\_menu.ui (For use with gtkmm 3)

```

<?xml version="1.0"?>
<interface>
  <!-- interface-requires gtk+ 3.0 -->
  <menu id="appmenu">
    <section>
      <item>
        <attribute name="label" translatable="yes">_Preferences</attribute>
        <attribute name="action">app.preferences</attribute>
      </item>
    </section>
    <section>
      <item>
        <attribute name="label" translatable="yes">_Quit</attribute>

```

---

```

        <attribute name="action">app.quit</attribute>
    </item>
</section>
</menu>
</interface>

```

## 31.5 A preference dialog

A typical application will have some preferences that should be remembered from one run to the next. Even for our simple example application, we may want to change the font that is used for the content.

We are going to use `Gio::Settings` to store our preferences. `Gio::Settings` requires a schema that describes our settings, in our case the `org.gtkmm.exampleapp.gschema.xml` file.

Before we can make use of this schema in our application, we need to compile it into the binary form that `Gio::Settings` expects. `GIO` provides macros to do this in autotools-based projects. See the description of [GSettings](#). Meson provides the `compile_schemas()` function in the [GNOME module](#).

Next, we need to connect our settings to the widgets that they are supposed to control. One convenient way to do this is to use `Gio::Settings::bind()` to bind settings keys to object properties, as we do for the transition setting in `ExampleAppWindow`'s constructor.

```

m_settings = Gio::Settings::create("org.gtkmm.exampleapp");
m_settings->bind("transition", m_stack->property_transition_type());

```

The code to connect the font setting is a little more involved, since it corresponds to an object property in a `Gtk::TextTag` that we must first create. The code is in `ExampleAppWindow::open_file_view()`.

```

auto tag = buffer->create_tag();
m_settings->bind("font", tag->property_font());
buffer->apply_tag(tag, buffer->begin(), buffer->end());

```

At this point, the application will already react if you change one of the settings, e.g. using the **gsettings** commandline tool. Of course, we expect the application to provide a preference dialog for these. So let's do that now. Our preference dialog will be a subclass of `Gtk::Dialog`, and we'll use the same techniques that we've already seen in `ExampleAppWindow`: a `Gtk::Builder` ui file and settings bindings.

When we've created the `prefs.ui` file and the `ExampleAppPrefs` class, we revisit the `ExampleApplication::on_a` method in our application class, and make it open a new preference dialog.

```

auto prefs_dialog = ExampleAppPrefs::create(*get_active_window());
prefs_dialog->present();

```

After all this work, our application can now show a preference dialog like this:




Figure 31.5: An preference dialog

### Source Code

File: exampleapplication.h (For use with gtkmm 3)

```
#include "../step4/exampleapplication.h"
// Equal to the corresponding file in step4
```

File: exampleappprefs.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEAPPPREFS_H_
#define GTKMM_EXAMPLEAPPPREFS_H_

#include <gtkmm.h>

class ExampleAppPrefs : public Gtk::Dialog
{
public:
    ExampleAppPrefs(BaseObjectType* cobject,
        const Glib::RefPtr<Gtk::Builder>& refBuilder);

    static ExampleAppPrefs* create(Gtk::Window& parent);

protected:
    Glib::RefPtr<Gtk::Builder> m_refBuilder;
    Glib::RefPtr<Gio::Settings> m_settings;
    Gtk::FontButton* m_font;
    Gtk::ComboBoxText* m_transition;
};
```

```
#endif /* GTKMM_EXAMPLEAPPPREFS_H_ */
```

**File: exampleappwindow.h (For use with gtkmm 3)**

```
#ifndef GTKMM_EXAMPLEAPPWINDOW_H_
#define GTKMM_EXAMPLEAPPWINDOW_H_

#include <gtkmm.h>

class ExampleAppWindow : public Gtk::ApplicationWindow
{
public:
    ExampleAppWindow(BaseObjectType* cobject,
        const Glib::RefPtr<Gtk::Builder>& refBuilder);

    static ExampleAppWindow* create();

    void open_file_view(const Glib::RefPtr<Gio::File>& file);

protected:
    Glib::RefPtr<Gtk::Builder> m_refBuilder;
    Glib::RefPtr<Gio::Settings> m_settings;
    Gtk::Stack* m_stack;
};

#endif /* GTKMM_EXAMPLEAPPWINDOW_H_ */
```

**File: exampleapplication.cc (For use with gtkmm 3)**

```
#include "exampleapplication.h"
#include "exampleappwindow.h"
#include "exampleappprefs.h"
#include <iostream>
#include <exception>

ExampleApplication::ExampleApplication()
: Gtk::Application("org.gtkmm.examples.application", Gio:: ↵
    APPLICATION_HANDLES_OPEN)
{
}

Glib::RefPtr<ExampleApplication> ExampleApplication::create()
{
    return Glib::RefPtr<ExampleApplication>(new ExampleApplication());
}

ExampleAppWindow* ExampleApplication::create_appwindow()
```

```
{
    auto appwindow = ExampleAppWindow::create();

    // Make sure that the application runs for as long this window is still ←
    open.
    add_window(*appwindow);

    // Gtk::Application::add_window() connects a signal handler to the ←
    window's
    // signal_hide(). That handler removes the window from the application.
    // If it's the last window to be removed, the application stops running.
    // Gtk::Window::set_application() does not connect a signal handler, but ←
    is
    // otherwise equivalent to Gtk::Application::add_window().

    // Delete the window when it is hidden.
    appwindow->signal_hide().connect(sigc::bind<Gtk::Window*>(sigc::mem_fun ←
        (*this,
        &ExampleApplication::on_hide_window), appwindow));

    return appwindow;
}

void ExampleApplication::on_startup()
{
    // Call the base class's implementation.
    Gtk::Application::on_startup();

    // Add actions and keyboard accelerators for the application menu.
    add_action("preferences", sigc::mem_fun(*this, &ExampleApplication:: ←
        on_action_preferences));
    add_action("quit", sigc::mem_fun(*this, &ExampleApplication:: ←
        on_action_quit));
    set_accel_for_action("app.quit", "<Ctrl>Q");

    auto refBuilder = Gtk::Builder::create();
    try
    {
        refBuilder->add_from_resource("/org/gtkmm/exampleapp/app_menu.ui");
    }
    catch (const Glib::Error& ex)
    {
        std::cerr << "ExampleApplication::on_startup(): " << ex.what() << std ←
        ::endl;
        return;
    }
}
```

---



```

auto object = refBuilder->get_object("appmenu");
auto app_menu = Glib::RefPtr<Gio::MenuModel>::cast_dynamic(object);
if (app_menu)
    set_app_menu(app_menu);
else
    std::cerr << "ExampleApplication::on_startup(): No \"appmenu\" object ←
        in app_menu.ui"
        << std::endl;
}

void ExampleApplication::on_activate()
{
    try
    {
        // The application has been started, so let's show a window.
        auto appwindow = create_appwindow();
        appwindow->present();
    }
    // If create_appwindow() throws an exception (perhaps from Gtk::Builder) ←
    // no window has been created, no window has been added to the ←
    // application,
    // and therefore the application will stop running.
    catch (const Glib::Error& ex)
    {
        std::cerr << "ExampleApplication::on_activate(): " << ex.what() << std:: ←
            ::endl;
    }
    catch (const std::exception& ex)
    {
        std::cerr << "ExampleApplication::on_activate(): " << ex.what() << std:: ←
            ::endl;
    }
}

void ExampleApplication::on_open(const Gio::Application::type_vec_files& ←
    files,
    const Glib::ustring& /* hint */)
{
    // The application has been asked to open some files,
    // so let's open a new view for each one.
    ExampleAppWindow* appwindow = nullptr;
    auto windows = get_windows();
    if (windows.size() > 0)
        appwindow = dynamic_cast<ExampleAppWindow*>(windows[0]);

    try

```

---

```
{
    if (!appwindow)
        appwindow = create_appwindow();

    for (const auto& file : files)
        appwindow->open_file_view(file);

    appwindow->present();
}
catch (const Glib::Error& ex)
{
    std::cerr << "ExampleApplication::on_open(): " << ex.what() << std::endl;
}
catch (const std::exception& ex)
{
    std::cerr << "ExampleApplication::on_open(): " << ex.what() << std::endl;
}
}

void ExampleApplication::on_hide_window(Gtk::Window* window)
{
    delete window;
}

void ExampleApplication::on_action_preferences()
{
    try
    {
        auto prefs_dialog = ExampleAppPrefs::create(*get_active_window());
        prefs_dialog->present();

        // Delete the dialog when it is hidden.
        prefs_dialog->signal_hide().connect(sigc::bind<Gtk::Window*>(sigc::mem_fun(*this,
            &ExampleApplication::on_hide_window), prefs_dialog));
    }
    catch (const Glib::Error& ex)
    {
        std::cerr << "ExampleApplication::on_action_preferences(): " << ex.what() << std::endl;
    }
    catch (const std::exception& ex)
    {
        std::cerr << "ExampleApplication::on_action_preferences(): " << ex.what() << std::endl;
    }
}
```

---

```

    }
}

void ExampleApplication::on_action_quit()
{
    // Gio::Application::quit() will make Gio::Application::run() return,
    // but it's a crude way of ending the program. The window is not removed
    // from the application. Neither the window's nor the application's
    // destructors will be called, because there will be remaining reference
    // counts in both of them. If we want the destructors to be called, we
    // must remove the window from the application. One way of doing this
    // is to hide the window. See comment in create_appwindow().
    auto windows = get_windows();
    for (auto window : windows)
        window->hide();

    // Not really necessary, when Gtk::Widget::hide() is called, unless
    // Gio::Application::hold() has been called without a corresponding call
    // to Gio::Application::release().
    quit();
}

```

File: exampleappprefs.cc (For use with gtkmm 3)

```

#include "exampleappprefs.h"
#include "exampleappwindow.h"
#include <stdexcept>

ExampleAppPrefs::ExampleAppPrefs(BaseObjectType* cobject,
    const Glib::RefPtr<Gtk::Builder>& refBuilder)
: Gtk::Dialog(cobject),
  m_refBuilder(refBuilder),
  m_settings(),
  m_font(nullptr),
  m_transition(nullptr)
{
    m_refBuilder->get_widget("font", m_font);
    if (!m_font)
        throw std::runtime_error("No \"font\" object in prefs.ui");

    m_refBuilder->get_widget("transition", m_transition);
    if (!m_transition)
        throw std::runtime_error("No \"transition\" object in prefs.ui");

    m_settings = Gio::Settings::create("org.gtkmm.exampleapp");
    m_settings->bind("font", m_font->property_font_name());
    m_settings->bind("transition", m_transition->property_active_id());
}

```

```
//static
ExampleAppPrefs* ExampleAppPrefs::create(Gtk::Window& parent)
{
    // Load the Builder file and instantiate its widgets.
    auto refBuilder = Gtk::Builder::create_from_resource("/org/gtkmm/ ↔
        exampleapp/prefs.ui");

    ExampleAppPrefs* dialog = nullptr;
    refBuilder->get_widget_derived("prefs_dialog", dialog);
    if (!dialog)
        throw std::runtime_error("No \"prefs_dialog\" object in prefs.ui");

    dialog->set_transient_for(parent);

    return dialog;
}
```

File: exampleappwindow.cc (For use with gtkmm 3)

```
#include "exampleappwindow.h"
#include <iostream>
#include <stdexcept>

ExampleAppWindow::ExampleAppWindow(BaseObjectType* cobject,
    const Glib::RefPtr<Gtk::Builder>& refBuilder)
: Gtk::ApplicationWindow(cobject),
  m_refBuilder(refBuilder),
  m_settings(),
  m_stack(nullptr)
{
    m_refBuilder->get_widget("stack", m_stack);
    if (!m_stack)
        throw std::runtime_error("No \"stack\" object in window.ui");

    m_settings = Gio::Settings::create("org.gtkmm.exampleapp");
    m_settings->bind("transition", m_stack->property_transition_type());
}

//static
ExampleAppWindow* ExampleAppWindow::create()
{
    // Load the Builder file and instantiate its widgets.
    auto refBuilder = Gtk::Builder::create_from_resource("/org/gtkmm/ ↔
        exampleapp/window.ui");

    ExampleAppWindow* window = nullptr;
    refBuilder->get_widget_derived("app_window", window);
}
```

```
if (!window)
    throw std::runtime_error("No \"app_window\" object in window.ui");

return window;
}

void ExampleAppWindow::open_file_view(const Glib::RefPtr<Gio::File>& file)
{
    const Glib::ustring basename = file->get_basename();

    auto scrolled = Gtk::make_managed<Gtk::ScrolledWindow>();
    scrolled->set_hexpand(true);
    scrolled->set_vexpand(true);
    scrolled->show();
    auto view = Gtk::make_managed<Gtk::TextView>();
    view->set_editable(false);
    view->set_cursor_visible(false);
    view->show();
    scrolled->add(*view);
    m_stack->add(*scrolled, basename, basename);

    auto buffer = view->get_buffer();
    try
    {
        char* contents = nullptr;
        gsize length = 0;

        file->load_contents(contents, length);
        buffer->set_text(contents, contents+length);
        g_free(contents);
    }
    catch (const Glib::Error& ex)
    {
        std::cout << "ExampleAppWindow::open_file_view(\"" << file->↳
            get_parse_name()
            << "\"): \n " << ex.what() << std::endl;
    }

    auto tag = buffer->create_tag();
    m_settings->bind("font", tag->property_font());
    buffer->apply_tag(tag, buffer->begin(), buffer->end());
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "exampleapplication.h"

int main(int argc, char* argv[])
```

---

```
{
  // Since this example is running uninstalled, we have to help it find ↵
  // its
  // schema. This is *not* necessary in a properly installed application.
  Glib::setenv ("GSETTINGS_SCHEMA_DIR", ".", false);

  auto application = ExampleApplication::create();

  // Start the application, showing the initial window,
  // and opening extra views for any files that it is asked to open,
  // for instance as a command-line parameter.
  // run() will return when the last window has been closed.
  return application->run(argc, argv);
}
```

**File: exampleapp.gresource.xml (For use with gtkmm 3)**

```
<?xml version="1.0" encoding="UTF-8"?>
<gresources>
  <gresource prefix="/org/gtkmm/exampleapp">
    <file preprocess="xml-stripblanks">window.ui</file>
    <file preprocess="xml-stripblanks">app_menu.ui</file>
    <file preprocess="xml-stripblanks">prefs.ui</file>
  </gresource>
</gresources>
```

**File: prefs.ui (For use with gtkmm 3)**

```
<?xml version="1.0" encoding="UTF-8"?>
<interface>
  <!-- interface-requires gtk+ 3.8 -->
  <object class="GtkDialog" id="prefs_dialog">
    <property name="title" translatable="yes">Preferences</property>
    <property name="resizable">False</property>
    <property name="modal">True</property>
    <property name="use-header-bar">1</property>
    <child internal-child="vbox">
      <object class="GtkBox" id="vbox">
        <child>
          <object class="GtkGrid" id="grid">
            <property name="visible">True</property>
            <property name="margin">6</property>
            <property name="row-spacing">12</property>
            <property name="column-spacing">6</property>
            <child>
              <object class="GtkLabel" id="fontlabel">
                <property name="visible">True</property>
                <property name="label">_Font:</property>
              </object>
            </child>
          </object>
        </child>
      </object>
    </child>
  </object>
```

---

```

        <property name="use-underline">True</property>
        <property name="mnemonic-widget">font</property>
        <property name="xalign">1</property>
    </object>
    <packing>
        <property name="left-attach">0</property>
        <property name="top-attach">0</property>
    </packing>
</child>
<child>
    <object class="GtkFontButton" id="font">
        <property name="visible">True</property>
    </object>
    <packing>
        <property name="left-attach">1</property>
        <property name="top-attach">0</property>
    </packing>
</child>
<child>
    <object class="GtkLabel" id="transitionlabel">
        <property name="visible">True</property>
        <property name="label">_Transition:</property>
        <property name="use-underline">True</property>
        <property name="mnemonic-widget">transition</property>
        <property name="xalign">1</property>
    </object>
    <packing>
        <property name="left-attach">0</property>
        <property name="top-attach">1</property>
    </packing>
</child>
<child>
    <object class="GtkComboBoxText" id="transition">
        <property name="visible">True</property>
        <items>
            <item translatable="yes" id="none">None</item>
            <item translatable="yes" id="crossfade">Fade</item>
            <item translatable="yes" id="slide-left-right">Slide</ ←
                item>
        </items>
    </object>
    <packing>
        <property name="left-attach">1</property>
        <property name="top-attach">1</property>
    </packing>
</child>
</object>

```

---

```

    </child>
  </object>
</child>
</object>
</interface>

```

File: `org.gtkmm.exampleapp.gschema.xml` (For use with gtkmm 3)

```

<?xml version="1.0" encoding="UTF-8"?>
<schemalist>
  <schema path="/org/gtkmm/exampleapp/" id="org.gtkmm.exampleapp">
    <key name="font" type="s">
      <default>'Monospace 12'</default>
      <summary>Font</summary>
      <description>The font to be used for content.</description>
    </key>
    <key name="transition" type="s">
      <choices>
        <choice value='none' />
        <choice value='crossfade' />
        <choice value='slide-left-right' />
      </choices>
      <default>'none'</default>
      <summary>Transition</summary>
      <description>The transition to use when switching tabs.</description>
    </key>
  </schema>
</schemalist>

```

## 31.6 Adding a search bar

We continue to flesh out the functionality of our application. For now, we add search. `gtkmm` supports this with `Gtk::SearchEntry` and `Gtk::SearchBar`. The search bar is a widget that can slide in from the top to present a search entry.

We add a toggle button to the header bar, which can be used to slide out the search bar below the header bar. The new widgets are added in the `window.ui` file.

Implementing the search needs quite a few code changes that we are not going to completely go over here. The central piece of the search implementation is a signal handler that listens for text changes in the search entry, shown here without error handling.

```

void ExampleAppWindow::on_search_text_changed()
{

```



```

const auto text = m_searchentry->get_text();
auto tab = dynamic_cast<Gtk::ScrolledWindow*>(m_stack->get_visible_child ←
    ());
auto view = dynamic_cast<Gtk::TextView*>(tab->get_child());

// Very simple-minded search implementation.
auto buffer = view->get_buffer();
Gtk::TextIter match_start;
Gtk::TextIter match_end;
if (buffer->begin().forward_search(text, Gtk:: ←
    TEXT_SEARCH_CASE_INSENSITIVE,
    match_start, match_end))
{
    buffer->select_range(match_start, match_end);
    view->scroll_to(match_start);
}
}

```

With the search bar, our application now looks like this:




Figure 31.6: Adding a search bar

### Source Code

**File:** exampleapplication.h (For use with gtkmm 3)

```
#include "../step4/exampleapplication.h"
// Equal to the corresponding file in step4
```

**File:** exampleappprefs.h (For use with gtkmm 3)

```
#include "../step5/exampleappprefs.h"
// Equal to the corresponding file in step5
```

**File:** exampleappwindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEAPPWINDOW_H_
#define GTKMM_EXAMPLEAPPWINDOW_H_

#include <gtkmm.h>

class ExampleAppWindow : public Gtk::ApplicationWindow
{
public:
    ExampleAppWindow(BaseObjectType* cobject,
        const Glib::RefPtr<Gtk::Builder>& refBuilder);

    static ExampleAppWindow* create();

    void open_file_view(const Glib::RefPtr<Gio::File>& file);

protected:
    // Signal handlers
    void on_search_text_changed();
    void on_visible_child_changed();

    Glib::RefPtr<Gtk::Builder> m_refBuilder;
    Glib::RefPtr<Gio::Settings> m_settings;
    Gtk::Stack* m_stack;
    Gtk::ToggleButton* m_search;
    Gtk::SearchBar* m_searchbar;
    Gtk::SearchEntry* m_searchentry;
    Glib::RefPtr<Glib::Binding> m_prop_binding;
};

#endif /* GTKMM_EXAMPLEAPPWINDOW_H_ */
```

**File:** exampleapplication.cc (For use with gtkmm 3)

```
#include "../step5/exampleapplication.cc"
// Equal to the corresponding file in step5
```

---

File: exampleappprefs.cc (For use with gtkmm 3)

```
#include "../step5/exampleappprefs.cc"
// Equal to the corresponding file in step5
```

File: exampleappwindow.cc (For use with gtkmm 3)

```
#include "exampleappwindow.h"
#include <iostream>
#include <stdexcept>

ExampleAppWindow::ExampleAppWindow(BaseObjectType* cobject,
    const Glib::RefPtr<Gtk::Builder>& refBuilder)
: Gtk::ApplicationWindow(cobject),
  m_refBuilder(refBuilder),
  m_settings(),
  m_stack(nullptr),
  m_search(nullptr),
  m_searchbar(nullptr),
  m_searchentry(nullptr),
  m_prop_binding()
{
  m_refBuilder->get_widget("stack", m_stack);
  if (!m_stack)
    throw std::runtime_error("No \"stack\" object in window.ui");

  m_refBuilder->get_widget("search", m_search);
  if (!m_search)
    throw std::runtime_error("No \"search\" object in window.ui");

  m_refBuilder->get_widget("searchbar", m_searchbar);
  if (!m_searchbar)
    throw std::runtime_error("No \"searchbar\" object in window.ui");

  m_refBuilder->get_widget("searchentry", m_searchentry);
  if (!m_searchentry)
    throw std::runtime_error("No \"searchentry\" object in window.ui");

  m_settings = Gio::Settings::create("org.gtkmm.exampleapp");
  m_settings->bind("transition", m_stack->property_transition_type());

  m_prop_binding = Glib::Binding::bind_property(m_search->property_active() <-
    (),
    m_searchbar->property_search_mode_enabled(), Glib:: <-
    BINDING_BIDIRECTIONAL);

  // Connect signal handlers.
  m_searchentry->signal_search_changed().connect(
```

```
    sigc::mem_fun(*this, &ExampleAppWindow::on_search_text_changed));
    m_stack->property_visible_child().signal_changed().connect(
        sigc::mem_fun(*this, &ExampleAppWindow::on_visible_child_changed));
}

//static
ExampleAppWindow* ExampleAppWindow::create()
{
    // Load the Builder file and instantiate its widgets.
    auto refBuilder = Gtk::Builder::create_from_resource("/org/gtkmm/ ↵
        exampleapp/window.ui");

    ExampleAppWindow* window = nullptr;
    refBuilder->get_widget_derived("app_window", window);
    if (!window)
        throw std::runtime_error("No \"app_window\" object in window.ui");

    return window;
}

void ExampleAppWindow::open_file_view(const Glib::RefPtr<Gio::File>& file)
{
    const Glib::ustring basename = file->get_basename();

    auto scrolled = Gtk::make_managed<Gtk::ScrolledWindow>();
    scrolled->set_hexpand(true);
    scrolled->set_vexpand(true);
    scrolled->show();
    auto view = Gtk::make_managed<Gtk::TextView>();
    view->set_editable(false);
    view->set_cursor_visible(false);
    view->show();
    scrolled->add(*view);
    m_stack->add(*scrolled, basename, basename);

    auto buffer = view->get_buffer();
    try
    {
        char* contents = nullptr;
        gsize length = 0;

        file->load_contents(contents, length);
        buffer->set_text(contents, contents+length);
        g_free(contents);
    }
    catch (const Glib::Error& ex)
    {

```

---

```
std::cout << "ExampleAppWindow::open_file_view(\"" << file-> ↵
    get_parse_name()
    << "\\"):\\n  " << ex.what() << std::endl;
return;
}

auto tag = buffer->create_tag();
m_settings->bind("font", tag->property_font());
buffer->apply_tag(tag, buffer->begin(), buffer->end());

m_search->set_sensitive(true);
}

void ExampleAppWindow::on_search_text_changed()
{
    const auto text = m_searchentry->get_text();
    if (text.empty())
        return;

    auto tab = dynamic_cast<Gtk::ScrolledWindow*>(m_stack->get_visible_child ↵
        ());
    if (!tab)
    {
        std::cout << "ExampleAppWindow::on_search_text_changed(): No visible ↵
            child." << std::endl;
        return;
    }

    auto view = dynamic_cast<Gtk::TextView*>(tab->get_child());
    if (!view)
    {
        std::cout << "ExampleAppWindow::on_search_text_changed(): No visible ↵
            text view." << std::endl;
        return;
    }

    // Very simple-minded search implementation.
    auto buffer = view->get_buffer();
    Gtk::TextIter match_start;
    Gtk::TextIter match_end;
    if (buffer->begin().forward_search(text, Gtk:: ↵
        TEXT_SEARCH_CASE_INSENSITIVE,
        match_start, match_end))
    {
        buffer->select_range(match_start, match_end);
        view->scroll_to(match_start);
    }
}
```

---

```
}

void ExampleAppWindow::on_visible_child_changed()
{
    m_searchbar->set_search_mode(false);
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "../step5/main.cc"
// Equal to the corresponding file in step5
```

**File: window.ui (For use with gtkmm 3)**

```
<?xml version="1.0" encoding="UTF-8"?>
<interface>
  <!-- interface-requires gtk+ 3.8 -->
  <object class="GtkApplicationWindow" id="app_window">
    <property name="title" translatable="yes">Example Application</ ↔
      property>
    <property name="default-width">600</property>
    <property name="default-height">400</property>
    <child>
      <object class="GtkBox" id="content_box">
        <property name="visible">True</property>
        <property name="orientation">vertical</property>
        <child>
          <object class="GtkHeaderBar" id="header">
            <property name="visible">True</property>
            <child type="title">
              <object class="GtkStackSwitcher" id="tabs">
                <property name="visible">True</property>
                <property name="stack">stack</property>
              </object>
            </child>
          </child>
          <child>
            <object class="GtkToggleButton" id="search">
              <property name="visible">True</property>
              <property name="sensitive">False</property>
              <style>
                <class name="image-button"/>
              </style>
              <child>
                <object class="GtkImage" id="search-icon">
                  <property name="visible">True</property>
                  <property name="icon-name">edit-find-symbolic</ ↔
                    property>
```

---

```

        <property name="icon-size">1</property>
      </object>
    </child>
  </object>
  <packing>
    <property name="pack-type">end</property>
  </packing>
</child>
</object>
</child>
<child>
  <object class="GtkSearchBar" id="searchbar">
    <property name="visible">True</property>
    <child>
      <object class="GtkSearchEntry" id="searchentry">
        <property name="visible">True</property>
      </object>
    </child>
  </object>
</child>
<child>
  <object class="GtkStack" id="stack">
    <property name="visible">True</property>
    <property name="transition-duration">500</property>
  </object>
</child>
</object>
</child>
</object>
</interface>

```

## 31.7 Adding a side bar

As another piece of functionality, we are adding a sidebar, which demonstrates `Gtk::MenuButton`, `Gtk::Revealer` and `Gtk::ListBox`. The new widgets are added in the `window.ui` file.

The code to populate the sidebar with buttons for the words found in each file is a little too involved to go into here. But we'll look at the code to add the gears menu. As expected by now, the gears menu is specified in a `Gtk::Builder` ui file, `gears_menu.ui`

To connect the menu item to the new `show-words` setting, we use a `Gio::Action` corresponding to the given `Gio::Settings` key. In `ExampleAppWindow`'s constructor:

```

// Connect the menu to the MenuButton m_gears, and bind the show-words ↔
  setting

```

```
// to the win.show-words action and the "Words" menu item.
// (The connection between action and menu item is specified in gears_menu ←
.ui.)
auto menu_builder = Gtk::Builder::create_from_resource("/org/gtkmm/ ←
exampleapp/gears_menu.ui");
auto object = menu_builder->get_object("menu");
auto menu = Glib::RefPtr<Gio::MenuModel>::cast_dynamic(object);
m_gears->set_menu_model(menu);
add_action(m_settings->create_action("show-words"));
```

What our application looks like now:




Figure 31.7: Adding a side bar

### Source Code

File: exampleapplication.h (For use with gtkmm 3)

```
#include "../step4/exampleapplication.h"
// Equal to the corresponding file in step4
```

File: exampleappprefs.h (For use with gtkmm 3)

```
#include "../step5/exampleappprefs.h"
// Equal to the corresponding file in step5
```



File: exampleappwindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEAPPWINDOW_H_
#define GTKMM_EXAMPLEAPPWINDOW_H_

#include <gtkmm.h>

class ExampleAppWindow : public Gtk::ApplicationWindow
{
public:
    ExampleAppWindow(BaseObjectType* cobject,
        const Glib::RefPtr<Gtk::Builder>& refBuilder);

    static ExampleAppWindow* create();

    void open_file_view(const Glib::RefPtr<Gio::File>& file);

protected:
    // Signal handlers
    void on_search_text_changed();
    void on_visible_child_changed();
    void on_find_word(const Gtk::Button* button);
    void on_reveal_child_changed();

    void update_words();

    Glib::RefPtr<Gtk::Builder> m_refBuilder;
    Glib::RefPtr<Gio::Settings> m_settings;
    Gtk::Stack* m_stack;
    Gtk::ToggleButton* m_search;
    Gtk::SearchBar* m_searchbar;
    Gtk::SearchEntry* m_searchentry;
    Gtk::MenuButton* m_gears;
    Gtk::Revealer* m_sidebar;
    Gtk::ListBox* m_words;
    Glib::RefPtr<Glib::Binding> m_prop_binding;
};

#endif /* GTKMM_EXAMPLEAPPWINDOW_H_ */
```

File: exampleapplication.cc (For use with gtkmm 3)

```
#include "../step5/exampleapplication.cc"
// Equal to the corresponding file in step5
```

File: exampleappprefs.cc (For use with gtkmm 3)

```
#include "../step5/exampleappprefs.cc"
```

---

```
// Equal to the corresponding file in step5
```

File: exampleappwindow.cc (For use with gtkmm 3)

```
#include "exampleappwindow.h"
#include <iostream>
#include <stdexcept>
#include <set>

ExampleAppWindow::ExampleAppWindow(BaseObjectType* cobject,
    const Glib::RefPtr<Gtk::Builder>& refBuilder)
: Gtk::ApplicationWindow(cobject),
  m_refBuilder(refBuilder),
  m_settings(),
  m_stack(nullptr),
  m_search(nullptr),
  m_searchbar(nullptr),
  m_searchentry(nullptr),
  m_gears(nullptr),
  m_sidebar(nullptr),
  m_words(nullptr),
  m_prop_binding()
{
    // Get widgets from the Gtk::Builder file.
    m_refBuilder->get_widget("stack", m_stack);
    if (!m_stack)
        throw std::runtime_error("No \"stack\" object in window.ui");

    m_refBuilder->get_widget("search", m_search);
    if (!m_search)
        throw std::runtime_error("No \"search\" object in window.ui");

    m_refBuilder->get_widget("searchbar", m_searchbar);
    if (!m_searchbar)
        throw std::runtime_error("No \"searchbar\" object in window.ui");

    m_refBuilder->get_widget("searchentry", m_searchentry);
    if (!m_searchentry)
        throw std::runtime_error("No \"searchentry\" object in window.ui");

    m_refBuilder->get_widget("gears", m_gears);
    if (!m_gears)
        throw std::runtime_error("No \"gears\" object in window.ui");

    m_refBuilder->get_widget("sidebar", m_sidebar);
    if (!m_sidebar)
        throw std::runtime_error("No \"sidebar\" object in window.ui");
```

```

m_refBuilder->get_widget("words", m_words);
if (!m_words)
    throw std::runtime_error("No \"words\" object in window.ui");

// Bind settings.
m_settings = Gio::Settings::create("org.gtkmm.exampleapp");
m_settings->bind("transition", m_stack->property_transition_type());
m_settings->bind("show-words", m_sidebar->property_reveal_child());

// Bind properties.
m_prop_binding = Glib::Binding::bind_property(m_search->property_active ↔
(),
    m_searchbar->property_search_mode_enabled(), Glib:: ↔
    BINDING_BIDIRECTIONAL);

// Connect signal handlers.
m_searchentry->signal_search_changed().connect(
    sigc::mem_fun(*this, &ExampleAppWindow::on_search_text_changed));
m_stack->property_visible_child().signal_changed().connect(
    sigc::mem_fun(*this, &ExampleAppWindow::on_visible_child_changed));
m_sidebar->property_reveal_child().signal_changed().connect(
    sigc::mem_fun(*this, &ExampleAppWindow::on_reveal_child_changed));

// Connect the menu to the MenuButton m_gears, and bind the show-words ↔
    setting
// to the win.show-words action and the "Words" menu item.
// (The connection between action and menu item is specified in ↔
    gears_menu.ui.)
auto menu_builder = Gtk::Builder::create_from_resource("/org/gtkmm/ ↔
    exampleapp/gears_menu.ui");
auto object = menu_builder->get_object("menu");
auto menu = Glib::RefPtr<Gio::MenuModel>::cast_dynamic(object);
if (!menu)
    throw std::runtime_error("No \"menu\" object in gears_menu.ui");

m_gears->set_menu_model(menu);
add_action(m_settings->create_action("show-words"));
}

//static
ExampleAppWindow* ExampleAppWindow::create()
{
    // Load the Builder file and instantiate its widgets.
    auto refBuilder = Gtk::Builder::create_from_resource("/org/gtkmm/ ↔
        exampleapp/window.ui");

    ExampleAppWindow* window = nullptr;

```

---

```
refBuilder->get_widget_derived("app_window", window);
if (!window)
    throw std::runtime_error("No \"app_window\" object in window.ui");

return window;
}

void ExampleAppWindow::open_file_view(const Glib::RefPtr<Gio::File>& file)
{
    const Glib::ustring basename = file->get_basename();

    auto scrolled = Gtk::make_managed<Gtk::ScrolledWindow>();
    scrolled->set_hexpand(true);
    scrolled->set_vexpand(true);
    scrolled->show();
    auto view = Gtk::make_managed<Gtk::TextView>();
    view->set_editable(false);
    view->set_cursor_visible(false);
    view->show();
    scrolled->add(*view);
    m_stack->add(*scrolled, basename, basename);

    auto buffer = view->get_buffer();
    try
    {
        char* contents = nullptr;
        gsize length = 0;

        file->load_contents(contents, length);
        buffer->set_text(contents, contents+length);
        g_free(contents);
    }
    catch (const Glib::Error& ex)
    {
        std::cout << "ExampleAppWindow::open_file_view(\"" << file-> ↵
            get_parse_name()
            << "\"): \n " << ex.what() << std::endl;
        return;
    }

    auto tag = buffer->create_tag();
    m_settings->bind("font", tag->property_font());
    buffer->apply_tag(tag, buffer->begin(), buffer->end());

    m_search->set_sensitive(true);
    update_words();
}
```

---

```
void ExampleAppWindow::on_search_text_changed()
{
    const auto text = m_searchentry->get_text();
    if (text.empty())
        return;

    auto tab = dynamic_cast<Gtk::ScrolledWindow*>(m_stack->get_visible_child() ←
        ());
    if (!tab)
    {
        std::cout << "ExampleAppWindow::on_search_text_changed(): No visible ←
            child." << std::endl;
        return;
    }

    auto view = dynamic_cast<Gtk::TextView*>(tab->get_child());
    if (!view)
    {
        std::cout << "ExampleAppWindow::on_search_text_changed(): No visible ←
            text view." << std::endl;
        return;
    }

    // Very simple-minded search implementation.
    auto buffer = view->get_buffer();
    Gtk::TextIter match_start;
    Gtk::TextIter match_end;
    if (buffer->begin().forward_search(text, Gtk::TextSearchFlags:: ←
        TEXT_SEARCH_CASE_INSENSITIVE,
        match_start, match_end))
    {
        buffer->select_range(match_start, match_end);
        view->scroll_to(match_start);
    }
}

void ExampleAppWindow::on_visible_child_changed()
{
    m_searchbar->set_search_mode(false);
    update_words();
}

void ExampleAppWindow::on_find_word(const Gtk::Button* button)
{
    m_searchentry->set_text(button->get_label());
}
```

---

```
void ExampleAppWindow::on_reveal_child_changed()
{
    update_words();
}

void ExampleAppWindow::update_words()
{
    auto tab = dynamic_cast<Gtk::ScrolledWindow*>(m_stack->get_visible_child() ←
        ());
    if (!tab)
        return;

    auto view = dynamic_cast<Gtk::TextView*>(tab->get_child());
    if (!view)
    {
        std::cout << "ExampleAppWindow::update_words(): No visible text view." <←
            << std::endl;
        return;
    }
    auto buffer = view->get_buffer();

    // Find all words in the text buffer.
    std::set<Glib::ustring> words;
    auto start = buffer->begin();
    Gtk::TextIter end;
    while (start)
    {
        while (start && !start.starts_word())
            ++start;

        if (!start)
            break;

        end = start;
        end.forward_word_end();
        if (start == end)
            break;

        auto word = buffer->get_text(start, end, false);
        words.insert(word.lowercase());
        start = end;
    }

    // Remove old children from the ListBox.
    auto old_children = m_words->get_children();
    for (auto child : old_children)
```

---

```
{
    m_words->remove(*child);
    delete child;
}

// Add new child buttons, one per unique word.
for (const auto& word : words)
{
    auto row = Gtk::make_managed<Gtk::Button>(word);
    row->signal_clicked().connect(sigc::bind(sigc::mem_fun(*this,
        &ExampleAppWindow::on_find_word), row));
    row->show();
    m_words->add(*row);
}
}
```

**File:** main.cc (For use with gtkmm 3)

```
#include "../step5/main.cc"
// Equal to the corresponding file in step5
```

**File:** exampleapp.gresource.xml (For use with gtkmm 3)

```
<?xml version="1.0" encoding="UTF-8"?>
<gresources>
  <gresource prefix="/org/gtkmm/exampleapp">
    <file preprocess="xml-stripblanks">window.ui</file>
    <file preprocess="xml-stripblanks">app_menu.ui</file>
    <file preprocess="xml-stripblanks">gears_menu.ui</file>
    <file preprocess="xml-stripblanks">prefs.ui</file>
  </gresource>
</gresources>
```

**File:** gears\_menu.ui (For use with gtkmm 3)

```
<?xml version="1.0"?>
<interface>
  <!-- interface-requires gtk+ 3.0 -->
  <menu id="menu">
    <section>
      <item>
        <attribute name="label" translatable="yes">_Words</attribute>
        <attribute name="action">win.show-words</attribute>
      </item>
    </section>
  </menu>
</interface>
```

---

File: window.ui (For use with gtkmm 3)

```
<?xml version="1.0" encoding="UTF-8"?>
<interface>
  <!-- interface-requires gtk+ 3.8 -->
  <object class="GtkApplicationWindow" id="app_window">
    <property name="title" translatable="yes">Example Application</ ↔
      property>
    <property name="default-width">600</property>
    <property name="default-height">400</property>
    <child>
      <object class="GtkBox" id="content_box">
        <property name="visible">True</property>
        <property name="orientation">vertical</property>
        <child>
          <object class="GtkHeaderBar" id="header">
            <property name="visible">True</property>
            <child type="title">
              <object class="GtkStackSwitcher" id="tabs">
                <property name="visible">True</property>
                <property name="stack">stack</property>
              </object>
            </child>
          </child>
          <child>
            <object class="GtkToggleButton" id="search">
              <property name="visible">True</property>
              <property name="sensitive">False</property>
              <style>
                <class name="image-button"/>
              </style>
              <child>
                <object class="GtkImage" id="search-icon">
                  <property name="visible">True</property>
                  <property name="icon-name">edit-find-symbolic</ ↔
                    property>
                  <property name="icon-size">1</property>
                </object>
              </child>
            </object>
            <packing>
              <property name="pack-type">end</property>
            </packing>
          </child>
          <child>
            <object class="GtkMenuButton" id="gears">
              <property name="visible">True</property>
              <property name="direction">none</property>
              <property name="use-popover">True</property>
            </object>
          </child>
        </child>
      </object>
    </child>
  </object>
</interface>
```



```
        <style>
          <class name="image-button"/>
        </style>
      </object>
    <packing>
      <property name="pack-type">end</property>
    </packing>
  </child>
</object>
</child>
<child>
  <object class="GtkSearchBar" id="searchbar">
    <property name="visible">True</property>
    <child>
      <object class="GtkSearchEntry" id="searchentry">
        <property name="visible">True</property>
      </object>
    </child>
  </object>
</child>
<child>
  <object class="GtkBox" id="hbox">
    <property name="visible">True</property>
    <child>
      <object class="GtkRevealer" id="sidebar">
        <property name="visible">True</property>
        <property name="transition-type">slide-right</property>
        <child>
          <object class="GtkScrolledWindow" id="sidebar-sw">
            <property name="visible">True</property>
            <property name="hscrollbar-policy">never</property>
            <property name="vscrollbar-policy">automatic</property>
            <child>
              <object class="GtkListBox" id="words">
                <property name="visible">True</property>
                <property name="selection-mode">none</property>
              </object>
            </child>
          </object>
        </child>
      </object>
    </child>
  </object>
</child>
<child>
  <object class="GtkStack" id="stack">
    <property name="visible">True</property>
    <property name="transition-duration">500</property>
  </object>
</child>
```

---

```

        </child>
      </object>
    </child>
  </object>
</child>
</object>
</interface>

```

File: `org.gtkmm.exampleapp.gschema.xml` (For use with gtkmm 3)

```

<?xml version="1.0" encoding="UTF-8"?>
<schemalist>
  <schema path="/org/gtkmm/exampleapp/" id="org.gtkmm.exampleapp">
    <key name="font" type="s">
      <default>'Monospace 12'</default>
      <summary>Font</summary>
      <description>The font to be used for content.</description>
    </key>
    <key name="transition" type="s">
      <choices>
        <choice value='none' />
        <choice value='crossfade' />
        <choice value='slide-left-right' />
      </choices>
      <default>'none'</default>
      <summary>Transition</summary>
      <description>The transition to use when switching tabs.</description>
    </key>
    <key name="show-words" type="b">
      <default>false</default>
      <summary>Show words</summary>
      <description>Whether to show a word list in the sidebar.</
      description>
    </key>
  </schema>
</schemalist>

```

## 31.8 Properties

Widgets and other objects have many useful properties. Here we show some ways to use them in new and flexible ways, by wrapping them in actions with `Gio::PropertyAction` or by binding them with `Glib::Binding`. (At the time of writing (october 2016) `Gio::PropertyAction` does not exist. We have to call a glib function directly.)

To set this up, we add two labels to the header bar in our `window.ui` file, named `lines_label` and `lines`, and get pointers to them in the application window's constructor, as we've seen a couple of times by now. We add a new "Lines" menu item to the gears menu, which triggers the `show-lines` action.

To make this menu item do something, we create a property action for the `visible` property of the `lines` label, and add it to the actions of the window. The effect of this is that the visibility of the label gets toggled every time the action is activated. Since we want both labels to appear and disappear together, we bind the `visible` property of the `lines_label` widget to the same property of the `lines` widget. In `ExampleAppWindow`'s constructor:

```
add_action(Glib::wrap((GAction*)
    g_property_action_new("show-lines", m_lines->gobj(), "visible")));
m_binding_lines_visible = Glib::Binding::bind_property(m_lines->
    property_visible(),
    m_lines_label->property_visible());
```

We also need a function that counts the lines of the currently active tab, and updates the `lines` label. See the full source if you are interested in the details.

This brings our example application to this appearance:




Figure 31.8: Properties

### Source Code

File: `exampleapplication.h` (For use with gtkmm 3)

```
#include "../step4/exampleapplication.h"
// Equal to the corresponding file in step4
```

File: exampleappprefs.h (For use with gtkmm 3)

```
#include "../step5/exampleappprefs.h"
// Equal to the corresponding file in step5
```

File: exampleappwindow.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLEAPPWINDOW_H_
#define GTKMM_EXAMPLEAPPWINDOW_H_

#include <gtkmm.h>

class ExampleAppWindow : public Gtk::ApplicationWindow
{
public:
    ExampleAppWindow(BaseObjectType* cobject,
        const Glib::RefPtr<Gtk::Builder>& refBuilder);

    static ExampleAppWindow* create();

    void open_file_view(const Glib::RefPtr<Gio::File>& file);

protected:
    // Signal handlers
    void on_search_text_changed();
    void on_visible_child_changed();
    void on_find_word(const Gtk::Button* button);
    void on_reveal_child_changed();

    void update_words();
    void update_lines();

    Glib::RefPtr<Gtk::Builder> m_refBuilder;
    Glib::RefPtr<Gio::Settings> m_settings;
    Gtk::Stack* m_stack;
    Gtk::ToggleButton* m_search;
    Gtk::SearchBar* m_searchbar;
    Gtk::SearchEntry* m_searchentry;
    Gtk::MenuButton* m_gears;
    Gtk::Revealer* m_sidebar;
    Gtk::ListBox* m_words;
    Gtk::Label* m_lines;
    Gtk::Label* m_lines_label;
    Glib::RefPtr<Glib::Binding> m_binding_search_enabled;
```

```
Glib::RefPtr<Glib::Binding> m_binding_lines_visible;
};

#endif /* GTKMM_EXAMPLEAPPWINDOW_H */
```

File: exampleapplication.cc (For use with gtkmm 3)

```
#include "../step5/exampleapplication.cc"
// Equal to the corresponding file in step5
```

File: exampleappprefs.cc (For use with gtkmm 3)

```
#include "../step5/exampleappprefs.cc"
// Equal to the corresponding file in step5
```

File: exampleappwindow.cc (For use with gtkmm 3)

```
#include "exampleappwindow.h"
#include <iostream>
#include <stdexcept>
#include <set>

ExampleAppWindow::ExampleAppWindow(BaseObjectType* cobject,
    const Glib::RefPtr<Gtk::Builder>& refBuilder)
: Gtk::ApplicationWindow(cobject),
  m_refBuilder(refBuilder),
  m_settings(),
  m_stack(nullptr),
  m_search(nullptr),
  m_searchbar(nullptr),
  m_searchentry(nullptr),
  m_gears(nullptr),
  m_sidebar(nullptr),
  m_words(nullptr),
  m_lines(nullptr),
  m_lines_label(nullptr),
  m_binding_search_enabled(),
  m_binding_lines_visible()
{
    // Get widgets from the Gtk::Builder file.
    m_refBuilder->get_widget("stack", m_stack);
    if (!m_stack)
        throw std::runtime_error("No \"stack\" object in window.ui");

    m_refBuilder->get_widget("search", m_search);
    if (!m_search)
        throw std::runtime_error("No \"search\" object in window.ui");
```

```
m_refBuilder->get_widget("searchbar", m_searchbar);
if (!m_searchbar)
    throw std::runtime_error("No \"searchbar\" object in window.ui");

m_refBuilder->get_widget("searchentry", m_searchentry);
if (!m_searchentry)
    throw std::runtime_error("No \"searchentry\" object in window.ui");

m_refBuilder->get_widget("gears", m_gears);
if (!m_gears)
    throw std::runtime_error("No \"gears\" object in window.ui");

m_refBuilder->get_widget("sidebar", m_sidebar);
if (!m_sidebar)
    throw std::runtime_error("No \"sidebar\" object in window.ui");

m_refBuilder->get_widget("words", m_words);
if (!m_words)
    throw std::runtime_error("No \"words\" object in window.ui");

m_refBuilder->get_widget("lines", m_lines);
if (!m_lines)
    throw std::runtime_error("No \"lines\" object in window.ui");

m_refBuilder->get_widget("lines_label", m_lines_label);
if (!m_lines_label)
    throw std::runtime_error("No \"lines_label\" object in window.ui");

// Bind settings.
m_settings = Gio::Settings::create("org.gtkmm.exampleapp");
m_settings->bind("transition", m_stack->property_transition_type());
m_settings->bind("show-words", m_sidebar->property_reveal_child());

// Bind properties of the search button to the search bar.
m_binding_search_enabled = Glib::Binding::bind_property(m_search->
    property_active(),
    m_searchbar->property_search_mode_enabled(), Glib::
    BINDING_BIDIRECTIONAL);

// Connect signal handlers.
m_searchentry->signal_search_changed().connect(
    sigc::mem_fun(*this, &ExampleAppWindow::on_search_text_changed));
m_stack->property_visible_child().signal_changed().connect(
    sigc::mem_fun(*this, &ExampleAppWindow::on_visible_child_changed));
m_sidebar->property_reveal_child().signal_changed().connect(
    sigc::mem_fun(*this, &ExampleAppWindow::on_reveal_child_changed));
```

---

```

// Connect the menu to the MenuButton m_gears, and bind the show-words ↵
// setting
// to the win.show-words action and the "Words" menu item.
// (The connection between action and menu item is specified in ↵
// gears_menu.ui.)
auto menu_builder = Gtk::Builder::create_from_resource("/org/gtkmm/ ↵
// exampleapp/gears_menu.ui");
auto object = menu_builder->get_object("menu");
auto menu = Glib::RefPtr<Gio::MenuModel>::cast_dynamic(object);
if (!menu)
    throw std::runtime_error("No \"menu\" object in gears_menu.ui");

m_gears->set_menu_model(menu);
add_action(m_settings->create_action("show-words"));

// Bind the "visible" property of m_lines to the win.show-lines action, ↵
// to
// the "Lines" menu item and to the "visible" property of m_lines_label.
// The GPropertyAction class is not wrapped in a glibmm class at the ↵
// time of
// writing (october 2016). We have to call a glib function directly.
add_action(Glib::wrap((GAction*)
    g_property_action_new("show-lines", m_lines->gobj(), "visible")));
m_binding_lines_visible = Glib::Binding::bind_property(m_lines-> ↵
// property_visible(),
// m_lines_label->property_visible());
}

//static
ExampleAppWindow* ExampleAppWindow::create()
{
    // Load the Builder file and instantiate its widgets.
    auto refBuilder = Gtk::Builder::create_from_resource("/org/gtkmm/ ↵
// exampleapp/window.ui");

    ExampleAppWindow* window = nullptr;
    refBuilder->get_widget_derived("app_window", window);
    if (!window)
        throw std::runtime_error("No \"app_window\" object in window.ui");

    return window;
}

void ExampleAppWindow::open_file_view(const Glib::RefPtr<Gio::File>& file)
{
    const Glib::ustring basename = file->get_basename();

```

---

```
auto scrolled = Gtk::make_managed<Gtk::ScrolledWindow>();
scrolled->set_hexpand(true);
scrolled->set_vexpand(true);
scrolled->show();
auto view = Gtk::make_managed<Gtk::TextView>();
view->set_editable(false);
view->set_cursor_visible(false);
view->show();
scrolled->add(*view);
m_stack->add(*scrolled, basename, basename);

auto buffer = view->get_buffer();
try
{
    char* contents = nullptr;
    gsize length = 0;

    file->load_contents(contents, length);
    buffer->set_text(contents, contents+length);
    g_free(contents);
}
catch (const Glib::Error& ex)
{
    std::cout << "ExampleAppWindow::open_file_view(\"" << file-> ↵
        get_parse_name()
        << "\"):\\n " << ex.what() << std::endl;
    return;
}

auto tag = buffer->create_tag();
m_settings->bind("font", tag->property_font());
buffer->apply_tag(tag, buffer->begin(), buffer->end());

m_search->set_sensitive(true);
update_words();
update_lines();
}

void ExampleAppWindow::on_search_text_changed()
{
    const auto text = m_searchentry->get_text();
    if (text.empty())
        return;

    auto tab = dynamic_cast<Gtk::ScrolledWindow*>(m_stack->get_visible_child ↵
        ());
    if (!tab)
```



```
{
    std::cout << "ExampleAppWindow::on_search_text_changed(): No visible ↵
        child." << std::endl;
    return;
}

auto view = dynamic_cast<Gtk::TextView*>(tab->get_child());
if (!view)
{
    std::cout << "ExampleAppWindow::on_search_text_changed(): No visible ↵
        text view." << std::endl;
    return;
}

// Very simple-minded search implementation.
auto buffer = view->get_buffer();
Gtk::TextIter match_start;
Gtk::TextIter match_end;
if (buffer->begin().forward_search(text, Gtk:: ↵
    TEXT_SEARCH_CASE_INSENSITIVE,
    match_start, match_end))
{
    buffer->select_range(match_start, match_end);
    view->scroll_to(match_start);
}
}

void ExampleAppWindow::on_visible_child_changed()
{
    m_searchbar->set_search_mode(false);
    update_words();
    update_lines();
}

void ExampleAppWindow::on_find_word(const Gtk::Button* button)
{
    m_searchentry->set_text(button->get_label());
}

void ExampleAppWindow::on_reveal_child_changed()
{
    update_words();
}

void ExampleAppWindow::update_words()
{
    auto tab = dynamic_cast<Gtk::ScrolledWindow*>(m_stack->get_visible_child ↵
```

```
    ));
    if (!tab)
        return;

    auto view = dynamic_cast<Gtk::TextView*>(tab->get_child());
    if (!view)
    {
        std::cout << "ExampleAppWindow::update_words(): No visible text view." <<
            << std::endl;
        return;
    }
    auto buffer = view->get_buffer();

    // Find all words in the text buffer.
    std::set<Glib::ustring> words;
    auto start = buffer->begin();
    Gtk::TextIter end;
    while (start)
    {
        while (start && !start.starts_word())
            ++start;

        if (!start)
            break;

        end = start;
        end.forward_word_end();
        if (start == end)
            break;

        auto word = buffer->get_text(start, end, false);
        words.insert(word.lowercase());
        start = end;
    }

    // Remove old children from the ListBox.
    auto old_children = m_words->get_children();
    for (auto child : old_children)
    {
        m_words->remove(*child);
        delete child;
    }

    // Add new child buttons, one per unique word.
    for (const auto& word : words)
    {
        auto row = Gtk::make_managed<Gtk::Button>(word);
```

---

```

        row->signal_clicked().connect(sigc::bind(sigc::mem_fun(*this,
            &ExampleAppWindow::on_find_word), row));
        row->show();
        m_words->add(*row);
    }
}

void ExampleAppWindow::update_lines()
{
    auto tab = dynamic_cast<Gtk::ScrolledWindow*>(m_stack->get_visible_child ←
        ());
    if (!tab)
        return;

    auto view = dynamic_cast<Gtk::TextView*>(tab->get_child());
    if (!view)
    {
        std::cout << "ExampleAppWindow::update_lines(): No visible text view." ←
            << std::endl;
        return;
    }
    auto buffer = view->get_buffer();

    int count = 0;
    auto iter = buffer->begin();
    while (iter)
    {
        ++count;
        if (!iter.forward_line())
            break;
    }
    m_lines->set_text(Glib::ustring::format(count));
}

```

**File: main.cc (For use with gtkmm 3)**

```

#include "../step5/main.cc"
// Equal to the corresponding file in step5

```

**File: gears\_menu.ui (For use with gtkmm 3)**

```

<?xml version="1.0"?>
<interface>
  <!-- interface-requires gtk+ 3.0 -->
  <menu id="menu">
    <section>
      <item>
        <attribute name="label" translatable="yes">_Words</attribute>
      </item>
    </section>
  </menu>
</interface>

```

```

        <attribute name="action">win.show-words</attribute>
      </item>
      <item>
        <attribute name="label" translatable="yes">_Lines</attribute>
        <attribute name="action">win.show-lines</attribute>
      </item>
    </section>
  </menu>
</interface>

```

**File: window.ui (For use with gtkmm 3)**

```

<?xml version="1.0" encoding="UTF-8"?>
<interface>
  <!-- interface-requires gtk+ 3.8 -->
  <object class="GtkApplicationWindow" id="app_window">
    <property name="title" translatable="yes">Example Application</ ←
      property>
    <property name="default-width">600</property>
    <property name="default-height">400</property>
    <child>
      <object class="GtkBox" id="content_box">
        <property name="visible">True</property>
        <property name="orientation">vertical</property>
        <child>
          <object class="GtkHeaderBar" id="header">
            <property name="visible">True</property>
            <child>
              <object class="GtkLabel" id="lines_label">
                <property name="visible">False</property>
                <property name="label" translatable="yes">Lines:</property ←
                  >
              </object>
            <packing>
              <property name="pack-type">start</property>
            </packing>
          </child>
          <child>
            <object class="GtkLabel" id="lines">
              <property name="visible">False</property>
            </object>
            <packing>
              <property name="pack-type">start</property>
            </packing>
          </child>
        <child type="title">
          <object class="GtkStackSwitcher" id="tabs">
            <property name="visible">True</property>

```

```
        <property name="stack">stack</property>
      </object>
    </child>
    <child>
      <object class="GtkToggleButton" id="search">
        <property name="visible">True</property>
        <property name="sensitive">False</property>
        <style>
          <class name="image-button"/>
        </style>
        <child>
          <object class="GtkImage" id="search-icon">
            <property name="visible">True</property>
            <property name="icon-name">edit-find-symbolic</ ↵
              property>
            <property name="icon-size">1</property>
          </object>
        </child>
      </object>
      <packing>
        <property name="pack-type">end</property>
      </packing>
    </child>
    <child>
      <object class="GtkMenuButton" id="gears">
        <property name="visible">True</property>
        <property name="direction">none</property>
        <property name="use-popover">True</property>
        <style>
          <class name="image-button"/>
        </style>
      </object>
      <packing>
        <property name="pack-type">end</property>
      </packing>
    </child>
  </object>
</child>
<child>
  <object class="GtkSearchBar" id="searchbar">
    <property name="visible">True</property>
    <child>
      <object class="GtkSearchEntry" id="searchentry">
        <property name="visible">True</property>
      </object>
    </child>
  </object>
</child>
```

---

```
</child>
<child>
  <object class="GtkBox" id="hbox">
    <property name="visible">True</property>
    <child>
      <object class="GtkRevealer" id="sidebar">
        <property name="visible">True</property>
        <property name="transition-type">slide-right</property>
        <child>
          <object class="GtkScrolledWindow" id="sidebar-sw">
            <property name="visible">True</property>
            <property name="hscrollbar-policy">never</property>
            <property name="vscrollbar-policy">automatic</property>
            <child>
              <object class="GtkListBox" id="words">
                <property name="visible">True</property>
                <property name="selection-mode">none</property>
              </object>
            </child>
          </object>
        </child>
      </object>
    </child>
  </object>
</child>
<child>
  <object class="GtkStack" id="stack">
    <property name="visible">True</property>
    <property name="transition-duration">500</property>
  </object>
</child>
</object>
</child>
</object>
</interface>
```

## 31.9 Header bar

Our application already uses a `Gtk::HeaderBar`, but so far it still gets a 'normal' window titlebar on top of that. This is a bit redundant, and we will now tell gtkmm to use the header bar as replacement for the titlebar. To do so, we move it around to be a direct child of the window, and set its type to be `titlebar`. This is done in the `window.ui` file.

A small extra bonus of using a header bar is that we get a fallback application menu button for free. We include an icon in the resource file, and set up this icon as the window icon. Then it is displayed in the

menu button.

Here is how the application now looks, if the fallback menu is used:




Figure 31.9: Header bar

The `window.ui` file sets a header bar title, but this title is not shown. That's because the stack switcher is a child of type `title`. The stack switcher becomes a custom title that hides the title label, as if it had been set with `Gtk::HeaderBar::set_custom_title()`.

#### Source Code

File: `exampleapplication.h` (For use with gtkmm 3)

```

#include "../step4/exampleapplication.h"
// Equal to the corresponding file in step4
  
```

File: `exampleappprefs.h` (For use with gtkmm 3)

```

#include "../step5/exampleappprefs.h"
// Equal to the corresponding file in step5
  
```

File: `exampleappwindow.h` (For use with gtkmm 3)

```

#include "../step8/exampleappwindow.h"
// Equal to the corresponding file in step8
  
```

File: exampleapplication.cc (For use with gtkmm 3)

```
#include "../step5/exampleapplication.cc"
// Equal to the corresponding file in step5
```

File: exampleappprefs.cc (For use with gtkmm 3)

```
#include "../step5/exampleappprefs.cc"
// Equal to the corresponding file in step5
```

File: exampleappwindow.cc (For use with gtkmm 3)

```
#include "exampleappwindow.h"
#include <iostream>
#include <stdexcept>
#include <set>

ExampleAppWindow::ExampleAppWindow(BaseObjectType* cobject,
    const Glib::RefPtr<Gtk::Builder>& refBuilder)
: Gtk::ApplicationWindow(cobject),
  m_refBuilder(refBuilder),
  m_settings(),
  m_stack(nullptr),
  m_search(nullptr),
  m_searchbar(nullptr),
  m_searchentry(nullptr),
  m_gears(nullptr),
  m_sidebar(nullptr),
  m_words(nullptr),
  m_lines(nullptr),
  m_lines_label(nullptr),
  m_binding_search_enabled(),
  m_binding_lines_visible()
{
    // Get widgets from the Gtk::Builder file.
    m_refBuilder->get_widget("stack", m_stack);
    if (!m_stack)
        throw std::runtime_error("No \"stack\" object in window.ui");

    m_refBuilder->get_widget("search", m_search);
    if (!m_search)
        throw std::runtime_error("No \"search\" object in window.ui");

    m_refBuilder->get_widget("searchbar", m_searchbar);
    if (!m_searchbar)
        throw std::runtime_error("No \"searchbar\" object in window.ui");

    m_refBuilder->get_widget("searchentry", m_searchentry);
```



```
if (!m_searchentry)
    throw std::runtime_error("No \"searchentry\" object in window.ui");

m_refBuilder->get_widget("gears", m_gears);
if (!m_gears)
    throw std::runtime_error("No \"gears\" object in window.ui");

m_refBuilder->get_widget("sidebar", m_sidebar);
if (!m_sidebar)
    throw std::runtime_error("No \"sidebar\" object in window.ui");

m_refBuilder->get_widget("words", m_words);
if (!m_words)
    throw std::runtime_error("No \"words\" object in window.ui");

m_refBuilder->get_widget("lines", m_lines);
if (!m_lines)
    throw std::runtime_error("No \"lines\" object in window.ui");

m_refBuilder->get_widget("lines_label", m_lines_label);
if (!m_lines_label)
    throw std::runtime_error("No \"lines_label\" object in window.ui");

// Bind settings.
m_settings = Gio::Settings::create("org.gtkmm.exampleapp");
m_settings->bind("transition", m_stack->property_transition_type());
m_settings->bind("show-words", m_sidebar->property_reveal_child());

// Bind properties of the search button to the search bar.
m_binding_search_enabled = Glib::Binding::bind_property(m_search->
    property_active(),
    m_searchbar->property_search_mode_enabled(), Glib::
    BINDING_BIDIRECTIONAL);

// Connect signal handlers.
m_searchentry->signal_search_changed().connect(
    sigc::mem_fun(*this, &ExampleAppWindow::on_search_text_changed));
m_stack->property_visible_child().signal_changed().connect(
    sigc::mem_fun(*this, &ExampleAppWindow::on_visible_child_changed));
m_sidebar->property_reveal_child().signal_changed().connect(
    sigc::mem_fun(*this, &ExampleAppWindow::on_reveal_child_changed));

// Connect the menu to the MenuButton m_gears, and bind the show-words
    setting
// to the win.show-words action and the "Words" menu item.
// (The connection between action and menu item is specified in
    gears_menu.ui.)
```

---

```

auto menu_builder = Gtk::Builder::create_from_resource("/org/gtkmm/ ↵
    exampleapp/gears_menu.ui");
auto object = menu_builder->get_object("menu");
auto menu = Glib::RefPtr<Gio::MenuModel>::cast_dynamic(object);
if (!menu)
    throw std::runtime_error("No \"menu\" object in gears_menu.ui");

m_gears->set_menu_model(menu);
add_action(m_settings->create_action("show-words"));

// Bind the "visible" property of m_lines to the win.show-lines action, ↵
// to
// the "Lines" menu item and to the "visible" property of m_lines_label.
// The GPropertyAction class is not wrapped in a glibmm class at the ↵
// time of
// writing (october 2016). We have to call a glib function directly.
add_action(Glib::wrap((GAction*)
    g_property_action_new("show-lines", m_lines->gobj(), "visible")));
m_binding_lines_visible = Glib::Binding::bind_property(m_lines-> ↵
    property_visible(),
    m_lines_label->property_visible());

// Display the application menu in the application, not in the desktop ↵
// environment.
auto gtk_settings = Gtk::Settings::get_default();
if (gtk_settings)
    gtk_settings->property_gtk_shell_shows_app_menu() = false;
set_show_menubar(true);

// Set the window icon.
set_icon(Gdk::Pixbuf::create_from_resource("/org/gtkmm/exampleapp/ ↵
    exampleapp.png"));
}

//static
ExampleAppWindow* ExampleAppWindow::create()
{
    // Load the Builder file and instantiate its widgets.
    auto refBuilder = Gtk::Builder::create_from_resource("/org/gtkmm/ ↵
        exampleapp/window.ui");

    ExampleAppWindow* window = nullptr;
    refBuilder->get_widget_derived("app_window", window);
    if (!window)
        throw std::runtime_error("No \"app_window\" object in window.ui");

    return window;
}

```

---

```
}

void ExampleAppWindow::open_file_view(const Glib::RefPtr<Gio::File>& file)
{
    const Glib::ustring basename = file->get_basename();

    auto scrolled = Gtk::make_managed<Gtk::ScrolledWindow>();
    scrolled->set_hexpand(true);
    scrolled->set_vexpand(true);
    scrolled->show();
    auto view = Gtk::make_managed<Gtk::TextView>();
    view->set_editable(false);
    view->set_cursor_visible(false);
    view->show();
    scrolled->add(*view);
    m_stack->add(*scrolled, basename, basename);

    auto buffer = view->get_buffer();
    try
    {
        char* contents = nullptr;
        gsize length = 0;

        file->load_contents(contents, length);
        buffer->set_text(contents, contents+length);
        g_free(contents);
    }
    catch (const Glib::Error& ex)
    {
        std::cout << "ExampleAppWindow::open_file_view(\"" << file->get_parse_name()
            << "\"): \n " << ex.what() << std::endl;
        return;
    }

    auto tag = buffer->create_tag();
    m_settings->bind("font", tag->property_font());
    buffer->apply_tag(tag, buffer->begin(), buffer->end());

    m_search->set_sensitive(true);
    update_words();
    update_lines();
}

void ExampleAppWindow::on_search_text_changed()
{
    const auto text = m_searchentry->get_text();
```

---

```
if (text.empty())
    return;

auto tab = dynamic_cast<Gtk::ScrolledWindow*>(m_stack->get_visible_child ←
    ());
if (!tab)
{
    std::cout << "ExampleAppWindow::on_search_text_changed(): No visible ←
        child." << std::endl;
    return;
}

auto view = dynamic_cast<Gtk::TextView*>(tab->get_child());
if (!view)
{
    std::cout << "ExampleAppWindow::on_search_text_changed(): No visible ←
        text view." << std::endl;
    return;
}

// Very simple-minded search implementation.
auto buffer = view->get_buffer();
Gtk::TextIter match_start;
Gtk::TextIter match_end;
if (buffer->begin().forward_search(text, Gtk::TextIter:: ←
    TEXT_SEARCH_CASE_INSENSITIVE,
    match_start, match_end))
{
    buffer->select_range(match_start, match_end);
    view->scroll_to(match_start);
}
}

void ExampleAppWindow::on_visible_child_changed()
{
    m_searchbar->set_search_mode(false);
    update_words();
    update_lines();
}

void ExampleAppWindow::on_find_word(const Gtk::Button* button)
{
    m_searchentry->set_text(button->get_label());
}

void ExampleAppWindow::on_reveal_child_changed()
{

```

```
    update_words();
}

void ExampleAppWindow::update_words()
{
    auto tab = dynamic_cast<Gtk::ScrolledWindow*>(m_stack->get_visible_child ←
        ());
    if (!tab)
        return;

    auto view = dynamic_cast<Gtk::TextView*>(tab->get_child());
    if (!view)
    {
        std::cout << "ExampleAppWindow::update_words(): No visible text view." <→
            << std::endl;
        return;
    }
    auto buffer = view->get_buffer();

    // Find all words in the text buffer.
    std::set<Glib::ustring> words;
    auto start = buffer->begin();
    Gtk::TextIter end;
    while (start)
    {
        while (start && !start.starts_word())
            ++start;

        if (!start)
            break;

        end = start;
        end.forward_word_end();
        if (start == end)
            break;

        auto word = buffer->get_text(start, end, false);
        words.insert(word.lowercase());
        start = end;
    }

    // Remove old children from the ListBox.
    auto old_children = m_words->get_children();
    for (auto child : old_children)
    {
        m_words->remove(*child);
        delete child;
    }
}
```

---

```

    }

    // Add new child buttons, one per unique word.
    for (const auto& word : words)
    {
        auto row = Gtk::make_managed<Gtk::Button>(word);
        row->signal_clicked().connect(sigc::bind(sigc::mem_fun(*this,
            &ExampleAppWindow::on_find_word), row));
        row->show();
        m_words->add(*row);
    }
}

void ExampleAppWindow::update_lines()
{
    auto tab = dynamic_cast<Gtk::ScrolledWindow*>(m_stack->get_visible_child ←
        ());
    if (!tab)
        return;

    auto view = dynamic_cast<Gtk::TextView*>(tab->get_child());
    if (!view)
    {
        std::cout << "ExampleAppWindow::update_lines(): No visible text view." <←
            << std::endl;
        return;
    }
    auto buffer = view->get_buffer();

    int count = 0;
    auto iter = buffer->begin();
    while (iter)
    {
        ++count;
        if (!iter.forward_line())
            break;
    }
    m_lines->set_text(Glib::ustring::format(count));
}

```

**File: main.cc (For use with gtkmm 3)**

```

#include "../step5/main.cc"
// Equal to the corresponding file in step5

```

**File: exampleapp.gresource.xml (For use with gtkmm 3)**

---

```
<?xml version="1.0" encoding="UTF-8"?>
<gresources>
  <gresource prefix="/org/gtkmm/exampleapp">
    <file preprocess="xml-stripblanks">window.ui</file>
    <file preprocess="xml-stripblanks">app_menu.ui</file>
    <file preprocess="xml-stripblanks">gears_menu.ui</file>
    <file preprocess="xml-stripblanks">prefs.ui</file>
    <file>exampleapp.png</file>
  </gresource>
</gresources>
```

File: window.ui (For use with gtkmm 3)

```
<?xml version="1.0" encoding="UTF-8"?>
<interface>
  <!-- interface-requires gtk+ 3.8 -->
  <object class="GtkApplicationWindow" id="app_window">
    <property name="default-width">600</property>
    <property name="default-height">400</property>
    <child type="titlebar">
      <object class="GtkHeaderBar" id="header">
        <property name="title" translatable="yes">Example Application</ ←
          property>
        <property name="visible">True</property>
        <property name="show-close-button">True</property>
        <property name="decoration-layout">menu:close</property>
      </object>
    </child>
    <child>
      <object class="GtkLabel" id="lines_label">
        <property name="visible">False</property>
        <property name="label" translatable="yes">Lines:</property>
      </object>
      <packing>
        <property name="pack-type">start</property>
      </packing>
    </child>
    <child>
      <object class="GtkLabel" id="lines">
        <property name="visible">False</property>
      </object>
      <packing>
        <property name="pack-type">start</property>
      </packing>
    </child>
    <child type="title">
      <object class="GtkStackSwitcher" id="tabs">
        <property name="visible">True</property>
        <property name="stack">stack</property>
      </object>
```

```
</child>
<child>
  <object class="GtkToggleButton" id="search">
    <property name="visible">True</property>
    <property name="sensitive">False</property>
    <style>
      <class name="image-button"/>
    </style>
    <child>
      <object class="GtkImage" id="search-icon">
        <property name="visible">True</property>
        <property name="icon-name">edit-find-symbolic</property>
        <property name="icon-size">1</property>
      </object>
    </child>
  </object>
</packing>
<property name="pack-type">end</property>
</packing>
</child>
<child>
  <object class="GtkMenuButton" id="gears">
    <property name="visible">True</property>
    <property name="direction">none</property>
    <property name="use-popover">True</property>
    <style>
      <class name="image-button"/>
    </style>
  </object>
</packing>
<property name="pack-type">end</property>
</packing>
</child>
</object>
</child>
<child>
  <object class="GtkBox" id="content_box">
    <property name="visible">True</property>
    <property name="orientation">vertical</property>
    <child>
      <object class="GtkSearchBar" id="searchbar">
        <property name="visible">True</property>
        <child>
          <object class="GtkSearchEntry" id="searchentry">
            <property name="visible">True</property>
          </object>
        </child>
      </object>
    </child>
  </object>
</child>
```

---



```
    </object>
  </child>
  <child>
    <object class="GtkBox" id="hbox">
      <property name="visible">True</property>
      <child>
        <object class="GtkRevealer" id="sidebar">
          <property name="visible">True</property>
          <property name="transition-type">slide-right</property>
          <child>
            <object class="GtkScrolledWindow" id="sidebar-sw">
              <property name="visible">True</property>
              <property name="hscrollbar-policy">never</property>
              <property name="vscrollbar-policy">automatic</property>
              <child>
                <object class="GtkListBox" id="words">
                  <property name="visible">True</property>
                  <property name="selection-mode">none</property>
                </object>
              </child>
            </object>
          </child>
        </object>
      </child>
    </object>
  </child>
  <child>
    <object class="GtkStack" id="stack">
      <property name="visible">True</property>
      <property name="transition-duration">500</property>
    </object>
  </child>
</object>
</child>
</object>
</child>
</interface>
```

---

## Chapter 32

# Contributing

This document, like so much other great software out there, was created for free by volunteers. If you are at all knowledgeable about any aspect of gtkmm that does not already have documentation, please consider contributing to this document.

Ideally, we would like you to [provide a merge request](#) to the `docs/tutorial/C/index-in.docbook` file. This file is in the `gtkmm-documentation` module in GNOME git.

If you do decide to contribute, please post your contribution as an issue or merge request to [GitLab](#). You can also discuss your ideas on GNOME's [Discourse](#) instance, under the [Platform/Language bindings](#) category with a `cplusplus` tag. Also, be aware that the entirety of this document is free, and any addition you provide must also be free. That is, people must be able to use any portion of your examples in their programs, and copies of this document (including your contribution) may be distributed freely.

---

## Appendix A

# The RefPtr smartpointer

`Glib::RefPtr` is a smartpointer. Specifically, it is a reference-counting smartpointer. You might be familiar with `std::auto_ptr<>`, `std::unique_ptr<>` and `std::shared_ptr<>`, which are also smartpointers. `Glib::RefPtr<>` is similar to `std::shared_ptr<>`, which is also reference-counting. `Glib::RefPtr<>` was introduced long before there was a reference-counting smartpointer in the C++ Standard Library.

### Reference

A smartpointer acts much like a normal pointer. Here are a few examples.

## A.1 Copying

You can copy `RefPtrs`, just like normal pointers. But unlike normal pointers, you don't need to worry about deleting the underlying instance.

```
Glib::RefPtr<Gdk::Pixbuf> refPixbuf = Gdk::Pixbuf::create_from_file( ↵  
    filename);  
Glib::RefPtr<Gdk::Pixbuf> refPixbuf2 = refPixbuf;
```

Of course this means that you can store `RefPtrs` in standard containers, such as `std::vector` or `std::list`.

```
std::list< Glib::RefPtr<Gdk::Pixbuf> > listPixbufs;  
Glib::RefPtr<Gdk::Pixbuf> refPixbuf = Gdk::Pixbuf::create_from_file( ↵  
    filename);  
listPixbufs.push_back(refPixbuf);
```

---

## A.2 Dereferencing

You can dereference a smartpointer with the `->` operator, to call the methods of the underlying instance, just like a normal pointer.

```
Glib::RefPtr<Gdk::Pixbuf> refPixbuf = Gdk::Pixbuf::create_from_file( ↵  
    filename);  
int width = refPixbuf->get_width();
```

But unlike most smartpointers, you can't use the `*` operator to access the underlying instance.

```
Glib::RefPtr<Gdk::Pixbuf> refPixbuf = Gdk::Pixbuf::create_from_file( ↵  
    filename);  
Gdk::Pixbuf& underlying = *refPixbuf; //Syntax error - will not compile.
```

## A.3 Casting

You can cast `RefPtrs` to base types, just like normal pointers.

```
Glib::RefPtr<Gtk::TreeStore> refStore = Gtk::TreeStore::create(columns);  
Glib::RefPtr<Gtk::TreeModel> refModel = refStore;
```

This means that any method which takes a `const Glib::RefPtr<BaseType>` argument can also take a `const Glib::RefPtr<DerivedType>`. The cast is implicit, just as it would be for a normal pointer.

You can also cast to a derived type, but the syntax is a little different than with a normal pointer.

```
Glib::RefPtr<Gtk::TreeStore> refStore =  
Glib::RefPtr<Gtk::TreeStore>::cast_dynamic(refModel);  
Glib::RefPtr<Gtk::TreeStore> refStore2 =  
Glib::RefPtr<Gtk::TreeStore>::cast_static(refModel);
```

## A.4 Checking for null

Just like normal pointers, you can check whether a `RefPtr` points to anything.

```
Glib::RefPtr<Gtk::TreeModel> refModel = m_TreeView.get_model();  
if(refModel)  
{  
    int cols_count = refModel->get_n_columns();  
    ...  
}
```

But unlike normal pointers, `RefPtrs` are automatically initialized to null so you don't need to remember to do that yourself.

---

## A.5 Constness

The use of the `const` keyword in C++ is not always clear. You might not realise that `const Something*` declares a pointer to a `const Something`. The pointer can be changed, but not the `Something` that it points to.

Therefore, the `RefPtr` equivalent of `Something*` for a method parameter is `const Glib::RefPtr<Something>&`, and the equivalent of `const Something*` is `const Glib::RefPtr<const Something>&`.

The `const ... &` around both is just for efficiency, like using `const std::string&` instead of `std::string` for a method parameter to avoid unnecessary copying.

## Appendix B

# Signals

### B.1 Connecting signal handlers

gtkmm widget classes have signal accessor methods, such as `Gtk::Button::signal_clicked()`, which allow you to connect your signal handler. Thanks to the flexibility of `libsigc++`, the callback library used by gtkmm, the signal handler can be almost any kind of function, but you will probably want to use a class method. Among GTK+ C coders, these signal handlers are often named callbacks.

Here's an example of a signal handler being connected to a signal:

```
#include <gtkmm/button.h>

void on_button_clicked()
{
    std::cout << "Hello World" << std::endl;
}

int main()
{
    Gtk::Button button("Hello World");
    button.signal_clicked().connect(sigc::ptr_fun(&on_button_clicked));
}
```

There's rather a lot to think about in this (non-functional) code. First let's identify the parties involved:

- The signal handler is `on_button_clicked()`.
  - We're hooking it up to the `Gtk::Button` object called `button`.
  - When the Button emits its `clicked` signal, `on_button_clicked()` will be called.
-

Now let's look at the connection again:

```
...
button.signal_clicked().connect(sigc::ptr_fun(&on_button_clicked));
...
```

Note that we don't pass a pointer to `on_button_clicked()` directly to the signal's `connect()` method. Instead, we call `sigc::ptr_fun()`, and pass the result to `connect()`.

`sigc::ptr_fun()` generates a `sigc::slot`. A slot is an object which looks and feels like a function, but is actually an object. These are also known as function objects, or functors. `sigc::ptr_fun()` generates a slot for a standalone function or static method. `sigc::mem_fun()` generates a slot for a member method of a particular instance.

Here's a slightly larger example of slots in action:

```
void on_button_clicked();

class some_class
{
    void on_button_clicked();
};

some_class some_object;

int main()
{
    Gtk::Button button;
    button.signal_clicked().connect( sigc::ptr_fun(&on_button_clicked) );
    button.signal_clicked().connect( sigc::mem_fun(some_object, &some_class::on_button_clicked) );
}
```

The first call to `connect()` is just like the one we saw last time; nothing new here.

The next is more interesting. `sigc::mem_fun()` is called with two arguments. The first argument is *some\_object*, which is the object that our new slot will be pointing at. The second argument is a pointer to one of its methods. This particular version of `sigc::mem_fun()` creates a slot which will, when "called", call the pointed-to method of the specified object, in this case `some_object.on_button_clicked()`.

Another thing to note about this example is that we made the call to `connect()` twice for the same signal object. This is perfectly fine - when the button is clicked, both signal handlers will be called.

We just told you that the button's `clicked` signal is expecting to call a method with no arguments. All signals have requirements like this - you can't hook a function with two arguments to a signal expecting none (unless you use an adapter, such as `sigc::bind()`, of course). Therefore, it's important to know what type of signal handler you'll be expected to connect to a given signal.

---

## B.2 Writing signal handlers

To find out what type of signal handler you can connect to a signal, you can look it up in the reference documentation or the header file. Here's an example of a signal declaration you might see in the gtkmm headers:

```
Glib::SignalProxy1<bool, Gtk::DirectionType> signal_focus()
```

Other than the signal's name (`focus`), two things are important to note here: the number following the word `SignalProxy` at the beginning (1, in this case), and the types in the list (`bool` and `Gtk::DirectionType`). The number indicates how many arguments the signal handler should have; the first type, `bool`, is the type that the signal handler should return; and the next type, `Gtk::DirectionType`, is the type of this signal's first, and only, argument. By looking at the reference documentation, you can see the names of the arguments too.

The same principles apply for signals which have more arguments. Here's one with three (taken from `<gtkmm/textbuffer.h>`):

```
Glib::SignalProxy3<void, const TextBuffer::iterator&, const Glib::ustrin&, ↵  
int> signal_insert();
```

It follows the same form. The number 3 at the end of the type's name indicates that our signal handler will need three arguments. The first type in the type list is `void`, so that should be our signal handler's return type. The following three types are the argument types, in order. Our signal handler's prototype could look like this:

```
void on_insert(const TextBuffer::iterator& pos, const Glib::ustrin& text, ↵  
int bytes)
```

## B.3 Disconnecting signal handlers

Let's take another look at a `Signal`'s `connect` method:

```
sigc::signal<void,int>::iterator signal<void,int>::connect( const sigc:: ↵  
slot<void,int>& );
```

Notice that the return value is of type `sigc::signal<void,int>::iterator`. This can be implicitly converted into a `sigc::connection` which in turn can be used to control the connection. By keeping a connection object you can disconnect its associated signal handler using the method `sigc::connection::disconnect()`.

---



## B.4 Overriding default signal handlers

So far we've told you to perform actions in response to button-presses and the like by handling signals. That's certainly a good way to do things, but it's not the only way.

Instead of laboriously connecting signal handlers to signals, you can simply make a new class which inherits from a widget - say, a `Button` - and then override the default signal handler, such as `Button::on_clicked()`. This can be a lot simpler than hooking up signal handlers for everything.

Subclassing isn't always the best way to accomplish things. It is only useful when you want the widget to handle its own signal by itself. If you want some other class to handle the signal then you'll need to connect a separate handler. This is even more true if you want several objects to handle the same signal, or if you want one signal handler to respond to the same signal from different objects.

gtkmm classes are designed with overriding in mind; they contain virtual member methods specifically intended to be overridden.

Let's look at an example of overriding:

```
#include <gtkmm/button.h>

class OverriddenButton : public Gtk::Button
{
protected:
    virtual void on_clicked();
}

void OverriddenButton::on_clicked()
{
    std::cout << "Hello World" << std::endl;

    // call the base class's version of the method:
    Gtk::Button::on_clicked();
}
```

Here we define a new class called `OverriddenButton`, which inherits from `Gtk::Button`. The only thing we change is the `on_clicked()` method, which is called whenever `Gtk::Button` emits the `clicked` signal. This method prints "Hello World" to `stdout`, and then calls the original, overridden method, to let `Gtk::Button` do what it would have done had we not overridden.

You don't always need to call the parent's method; there are times when you might not want to. Note that we called the parent method *after* writing "Hello World", but we could have called it before. In this simple example, it hardly matters much, but there are times when it will. With signals, it's not quite so easy to change details like this, and you can do something here which you can't do at all with connected signal handlers: you can call the parent method in the *middle* of your custom code.

---

## B.5 Binding extra arguments

If you use one signal handler to catch the same signal from several widgets, you might like that signal handler to receive some extra information. For instance, you might want to know which button was clicked. You can do this with `sigc::bind()`. Here's some code from the [helloworld2](#) example.

```
m_button1.signal_clicked().connect( sigc::bind<Glib::ustring>( sigc:: ←
    mem_fun(*this, &HelloWorld::on_button_clicked), "button 1") );
```

This says that we want the signal to send an extra `Glib::ustring` argument to the signal handler, and that the value of that argument should be "button 1". Of course we will need to add that extra argument to the declaration of our signal handler:

```
virtual void on_button_clicked(Glib::ustring data);
```

Of course, a normal "clicked" signal handler would have no arguments.

`sigc::bind()` is not commonly used, but you might find it helpful sometimes. If you are familiar with GTK+ programming then you have probably noticed that this is similar to the extra `gpointer data` arguments which all GTK+ callbacks have. This is generally overused in GTK+ to pass information that should be stored as member data in a derived widget, but widget derivation is very difficult in C. We have far less need of this hack in gtkmm.

## B.6 X Event signals

The `Widget` class has some special signals which correspond to the underlying X-Windows events. These are suffixed by `_event`; for instance, `Widget::signal_button_press_event()`.

You might occasionally find it useful to handle X events when there's something you can't accomplish with normal signals. `Gtk::Button`, for example, does not send mouse-pointer coordinates with its `clicked` signal, but you could handle `button_press_event` if you needed this information. X events are also often used to handle key-presses.

These signals behave slightly differently. The value returned from the signal handler indicates whether it has fully "handled" the event. If the value is `false` then gtkmm will pass the event on to the next signal handler. If the value is `true` then no other signal handlers will need to be called.

Handling an X event doesn't affect the `Widget`'s other signals. If you handle `button_press_event` for `Gtk::Button`, you'll still be able to get the `clicked` signal. They are emitted at (nearly) the same time.

Note also that not all widgets receive all X events by default. To receive additional X events, you can use `Gtk::Widget::set_events()` before showing the widget, or `Gtk::Widget::add_events()` after showing the widget. However, some widgets must first be placed inside an `EventBox` widget. See the [Widgets Without X-Windows](#) chapter.

Here's a simple example:

```
bool on_button_press(GdkEventButton* event);
Gtk::Button button("label");
button.signal_button_press_event().connect( sigc::ptr_fun(&on_button_press ←
    ) );
```

When the mouse is over the button and a mouse button is pressed, `on_button_press()` will be called.

`GdkEventButton` is a structure containing the event's parameters, such as the coordinates of the mouse pointer at the time the button was pressed. There are several different types of `GdkEvent` structures for the various events.

### B.6.1 Signal Handler sequence

By default, your signal handlers are called after any previously-connected signal handlers. However, this can be a problem with the X Event signals. For instance, the existing signal handlers, or the default signal handler, might return `true` to stop other signal handlers from being called. To specify that your signal handler should be called before the other signal handlers, so that it will always be called, you can specify `false` for the optional `after` parameter. For instance,

```
button.signal_button_press_event().connect( sigc::ptr_fun(& ←
    on_mywindow_button_press), false );
```

The event is delivered first to the widget the event occurred in. If all signal handlers in that widget return `false` (indicating that the event has not been handled), then the signal will be propagated to the parent widget and emitted there. This continues all the way up to the top-level widget if no one handles the event.

## B.7 Exceptions in signal handlers

When a program is aborted because of an unhandled C++ exception, it's sometimes possible to use a debugger to find the location where the exception was thrown. This is more difficult than usual if the exception was thrown from a signal handler.

This section describes primarily what you can expect on a Linux system, when you use [the gdb debugger](#).

First, let's look at a simple example where an exception is thrown from a normal function (no signal handler).

```
// without_signal.cc
#include <gtkmm.h>

bool throwSomething()
```

```
{
    throw "Something";
    return true;
}

int main(int argc, char** argv)
{
    throwSomething();
    Glib::RefPtr<Gtk::Application> app =
        Gtk::Application::create(argc, argv, "org.gtkmm.without_signal");
    return app->run();
}
```

Here is an excerpt from a gdb session. Only the most interesting parts of the output are shown.

```
> gdb without_signal
(gdb) run
terminate called after throwing an instance of 'char const*'

Program received signal SIGABRT, Aborted.
(gdb) backtrace
#7  0x08048864 in throwSomething () at without_signal.cc:6
#8  0x0804887d in main (argc=1, argv=0xbffec4) at without_signal.cc:12
```

You can see that the exception was thrown from `without_signal.cc`, line 6 (`throw "Something";`).

Now let's see what happens when an exception is thrown from a signal handler. Here's the source code.

```
// with_signal.cc
#include <gtkmm.h>

bool throwSomething()
{
    throw "Something";
    return true;
}

int main(int argc, char** argv)
{
    Glib::signal_timeout().connect(sigc::ptr_fun(throwSomething), 500);
    Glib::RefPtr<Gtk::Application> app =
        Gtk::Application::create(argc, argv, "org.gtkmm.with_signal");
    app->hold();
    return app->run();
}
```

And here's an excerpt from a gdb session.

---

```
> gdb with_signal
(gdb) run
(with_signal:2703): glibmm-ERROR **:
unhandled exception (type unknown) in signal handler

Program received signal SIGTRAP, Trace/breakpoint trap.
(gdb) backtrace
#2  0x0063c6ab in glibmm_unexpected_exception () at exceptionhandler.cc:77
#3  Glib::exception_handlers_invoke () at exceptionhandler.cc:150
#4  0x0063d370 in glibmm_source_callback (data=0x804d620) at main.cc:212
#13 0x002e1b31 in Gtk::Application::run (this=0x804f300) at application.cc ↵
:178
#14 0x08048ccc in main (argc=1, argv=0xbffffcd4) at with_signal.cc:16
```

The exception is caught in glibmm, and the program ends with a call to `g_error()`. Other exceptions may result in different behaviour, but in any case the exception from a signal handler is caught in glibmm or gtkmm, and gdb can't see where it was thrown.

To see where the exception is thrown, you can use the gdb command **catch throw**.

```
> gdb with_signal
(gdb) catch throw
Catchpoint 1 (throw)
(gdb) run
Catchpoint 1 (exception thrown), 0x00714ff0 in __cxa_throw ()
(gdb) backtrace
#0  0x00714ff0 in __cxa_throw () from /usr/lib/i386-linux-gnu/libstdc++.so ↵
.6
#1  0x08048bd4 in throwSomething () at with_signal.cc:6
(gdb) continue
Continuing.
(with_signal:2375): glibmm-ERROR **:
unhandled exception (type unknown) in signal handler

Program received signal SIGTRAP, Trace/breakpoint trap.
```

If there are many caught exceptions before the interesting uncaught one, this method can be tedious. It can be automated with the following gdb commands.

```
(gdb) catch throw
(gdb) commands
(gdb)   backtrace
(gdb)   continue
(gdb)   end
(gdb) set pagination off
(gdb) run
```

These commands will print a backtrace from each `throw` and `continue`. The backtrace from the last (or possibly the last but one) `throw` before the program stops, is the interesting one.

## Appendix C

# Creating your own signals

Now that you've seen signals and signal handlers in gtkmm, you might like to use the same technique to allow interaction between your own classes. That's actually very simple by using the libsigc++ library directly.

This isn't purely a gtkmm or GUI issue. gtkmm uses libsigc++ to implement its proxy wrappers for the GTK+ signal system, but for new, non-GTK+ signals, you can create pure C++ signals, using the `sigc::signal<>` template.

For instance, to create a signal that sends 2 parameters, a bool and an int, just declare a `sigc::signal`, like so:

```
sigc::signal<void, bool, int> signal_something;
```

You could just declare that signal as a public member variable, but some people find that distasteful and prefer to make it available via an accessor method, like so:

```
class Server
{
public:
    //signal accessor:
    typedef sigc::signal<void, bool, int> type_signal_something;
    type_signal_something signal_something();

protected:
    type_signal_something m_signal_something;
};

Server::type_signal_something Server::signal_something()
{
    return m_signal_something;
}
```

You can then connect to the signal using the same syntax used when connecting to gtkmm signals. For instance,

```
server.signal_something().connect (
    sigc::mem_fun(client, &Client::on_server_something) );
```

## C.1 Example

This is a full working example that defines and uses custom signals.

### Source Code

File: client.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_CLIENT_H
#define GTKMM_EXAMPLE_CLIENT_H

#include <sigc++/sigc++.h>

//Client must inherit from sigc::trackable.
//because libsigc++ needs to keep track of the lifetime of signal handlers ←
.
class Client : public sigc::trackable
{
public:
    Client();
    virtual ~Client();

    //Signal handler:
    void on_server_something(bool a, int b);
};

#endif //GTKMM_EXAMPLE_CLIENT_H
```

File: server.h (For use with gtkmm 3)

```
#ifndef GTKMM_EXAMPLE_SERVER_H
#define GTKMM_EXAMPLE_SERVER_H

#include <sigc++/sigc++.h>

class Server
{
public:
    Server();
    virtual ~Server();
```



```
void do_something();

//signal accessor:
typedef sigc::signal<void, bool, int> type_signal_something;
type_signal_something signal_something();

protected:
    type_signal_something m_signal_something;
};

#endif //GTKMM_EXAMPLE_SERVER_H
```

**File: client.cc (For use with gtkmm 3)**

```
#include "client.h"
#include <iostream>

Client::Client()
{
}

Client::~Client()
{
}

void Client::on_server_something(bool a, int b)
{
    std::cout << "Client::on_server_something() called with these parameters ←
        : "
        << a << ", " << b << std::endl;
}
```

**File: main.cc (For use with gtkmm 3)**

```
#include "server.h"
#include "client.h"
#include <iostream>

int main(int, char**)
{
    Server server;
    Client client;

    //Connect a Server signal to the signal handler in Client.
    server.signal_something().connect(sigc::mem_fun(client,
        &Client::on_server_something) );
}
```

---

```
std::cout << "Before Server::do_something()" << std::endl;

//Tell the server to do something that will eventually cause it to emit ↵
the
//"something" signal.
server.do_something();    // Client::on_server_something() will run ↵
before
                           // Server::do_something() has completed.

std::cout << "After Server::do_something()" << std::endl;

return 0;
}
```

File: server.cc (For use with gtkmm 3)

```
#include "server.h"
#include <iostream>

Server::Server()
{
}

Server::~Server()
{
}

Server::type_signal_something Server::signal_something()
{
    return m_signal_something;
}

void Server::do_something()
{
    m_signal_something.emit(false, 5);
}
```

## Appendix D

# Comparison with other signalling systems

(An aside: GTK+ calls this scheme "signalling"; the sharp-eyed reader with GUI toolkit experience will note that this same design is often seen under the name of "broadcaster-listener" (e.g., in Metrowerks' PowerPlant framework for the Macintosh). It works in much the same way: one sets up `broadcasters`, and then connects `listeners` to them; the broadcaster keeps a list of the objects listening to it, and when someone gives the broadcaster a message, it calls all of its objects in its list with the message. In gtkmm, signal objects play the role of broadcasters, and slots play the role of listeners - sort of. More on this later.)

gtkmm signal handlers are strongly-typed, whereas GTK+ C code allows you to connect a callback with the wrong number and type of arguments, leading to a segfault at runtime. And, unlike Qt, gtkmm achieves this without modifying the C++ language.

Re. Overriding signal handlers: You can do this in the straight-C world of GTK+ too; that's what GTK+'s object system is for. But in GTK+, you have to go through some complicated procedures to get object-oriented features like inheritance and overloading. In C++, it's simple, since those features are supported in the language itself; you can let the compiler do the dirty work.

This is one of the places where the beauty of C++ really comes out. One wouldn't think of subclassing a GTK+ widget simply to override its action method; it's just too much trouble. In GTK+, you almost always use signals to get things done, unless you're writing a new widget. But because overriding methods is so easy in C++, it's entirely practical - and sensible - to subclass a button for that purpose.

---

## Appendix E

# gtkmm and Win32

One of the major advantages of gtkmm is that it is crossplatform. gtkmm programs written on other platforms such as GNU/Linux can generally be transferred to Windows (and vice versa) with few modifications to the source.

The latest stable gtkmm currently works with the [MinGW-w64/GCC4.8 compiler](#) and Microsoft Visual C++ 2015 or later (including the freely available express/community editions) on the Windows platform. There is an [installer](#) available for gtkmm on Microsoft Windows, albeit for older versions of gtkmm. Please be aware that although normally it is fine to mix builds done with Visual Studio 2015, 2017 and 2019, please do not do so when building gtkmm with its -mm dependencies.

Refer to the [README.win32](#), as well as the [README](#) files in the gtkmm, pangomm and glibmm for instructions on how to build gtkmm on Windows.

---

## Appendix F

# Working with gtkmm's Source Code

If you are interested in helping out with the development of gtkmm, or fixing a bug in gtkmm, you'll probably need to build the development version of gtkmm. However, you should not install a development version over your stable version. Instead, you should install it alongside your existing gtkmm installation, in a separate path.

The easiest way to do this is using [jhbuild](#). jhbuild is a program that makes building GNOME software much easier by calculating dependencies and building things in the correct order. This section will give a brief explanation of how to set up jhbuild to build and install gtkmm from the source repository (git). For up-to-date information on jhbuild, please refer to the [jhbuild manual](#).

---

**Note**

Note that to build gtkmm from git, you'll often need to build many of its dependencies from git as well. jhbuild makes this easier than it would normally be, but it will take quite a while to build and install them all. You will probably encounter build problems, though these will usually be corrected quickly if you report them.

---

gnome-build-meta is an alternative to jhbuild. It is described at the [Building system components](#) wiki page, but here we concentrate on jhbuild.

### F.1 Setting up jhbuild

To set up jhbuild, follow the basic installation instructions from the [jhbuild manual](#). After you have installed jhbuild, you should copy the sample jhbuild configuration file into your home directory by executing the following command from the jhbuild directory:

---

```
$ cp examples/sample.jhbuildrc ~/.config/jhbuildrc
```

The `gtkmm` module is defined in the `gnome-suited-core-deps-latest.modules` `moduleset`. So edit your `jhbuildrc` file and set your `moduleset` setting like so:

```
moduleset = 'gnome-suited-core-deps-latest'
```

After setting the correct `moduleset`, you need to tell `jhbuild` which module or modules to build. To build `gtkmm 3` and all of its dependencies, set `modules` like so:

```
modules = [ 'gtkmm-3' ]
```

You can build several modules by setting the `modules` variable to a meta-package, e.g. `meta-gnome-core`, or listing more than one module name. The `modules` variable specifies which modules will be built when you don't explicitly specify anything on the command line. You can always build a different `moduleset` later by specifying it on the commandline (e.g. **`jhbuild build gtkmm-3`**).



#### Setting a prefix

By default, `jhbuild`'s configuration is configured to install all software built with `jhbuild` under the `~/jhbuild/install` prefix. You can choose a different prefix, but it is recommended that you keep this prefix different from other software that you've installed (don't set it to `/usr!`) If you've followed the `jhbuild` instructions then this prefix belongs to your user, so you don't need to run `jhbuild` as `root`.

You should also set `buildroot` in `jhbuildrc`. `jhbuild` builds `gtkmm` and many of its dependencies with `Meson`. `Meson` does not allow building in the source tree. `jhbuild`'s default action is to build in a `build` directory directly below the source root directory. Some modules have a `build` directory with files used when building with `Autotools`. Those files can be destroyed if you let `jhbuild` build in that directory.

When you downloaded `jhbuild` from the `git` repository, you got a number of `.modules` files, specifying dependencies between modules. By default `jhbuild` does not use the downloaded versions of these files, but reads the latest versions in the `git` repository. This is usually what you want. If you don't want it, use the `use_local_modulesets` variable in `jhbuildrc`.

## F.2 Installing and Using the git version of gtkmm

Once you've configured `jhbuild` as described above, building `gtkmm` should be relatively straightforward. The first time you run `jhbuild`, you should run the following sequence of commands to ensure that `jhbuild` has the required tools and verify that it is set up correctly:

```
$ jhbuild bootstrap
$ jhbuild sanitycheck
```

### F.2.1 Installing gtkmm with jhbuild

If everything worked correctly, you should be able to build gtkmm and all of its dependencies from git by executing **jhbuild build** (or, if you didn't specify gtkmm in the `modules` variable, with the command **jhbuild build gtkmm-3**).

This command will build and install a series of modules and will probably take quite a long time the first time through. After the first time, however, it should go quite a bit faster since it only needs to rebuild files that changed since the last build. Alternatively, after you've built and installed gtkmm the first time, you can rebuild gtkmm by itself (without rebuilding all of its dependencies) with the command **jhbuild buildone gtkmm-3**.

### F.2.2 Using the git version of gtkmm

After you've installed the git version of gtkmm, you're ready to start using and experimenting with it. In order to use the new version of gtkmm you've just installed, you need to set some environment variables so that your `configure` or `meson.build` script knows where to find the new libraries. Fortunately, jhbuild offers an easy solution to this problem. Executing the command **jhbuild shell** will start a new shell with all of the correct environment variables set. Now if you re-configure and build your project just as you usually do, it should link against the newly installed libraries. To return to your previous environment, simply exit the jhbuild shell.

Once you've built your software, you'll need to run your program within the jhbuild environment as well. To do this, you can again use the **jhbuild shell** command to start a new shell with the jhbuild environment set up. Alternatively, you can execute a one-off command in the jhbuild environment using the following command: **jhbuild run command-name**. In this case, the command will be run with the correct environment variables set, but will return to your previous environment after the program exits.

---

## Appendix G

# Wrapping C Libraries with gmmproc

gtkmm uses the **gmmproc** tool to generate most of its source code, using `.defs` files that define the APIs of GObject-based libraries. So it's quite easy to create additional gtkmm-style wrappers of other glib/GObject-based libraries.

This involves a variety of tools, some of them crafty, but at least they work, and have been used successfully by several projects.

### G.1 The build structure

Generation of the source code for a gtkmm-style wrapper API requires use of tools such as **gmmproc** and `generate_wrap_init.pl`, which are included in `glibmm`. In theory you could write your own build files to use these appropriately, but a much better option is to make use of the build infrastructure provided by the `mm-common` module. To get started, it helps a lot to pick an existing binding module as an example to look at.

For instance, let's pretend that we are wrapping a C library called `libsomething`. It provides a GObject-based API with types named, for instance, `SomeWidget` and `SomeStuff`.

#### G.1.1 Copying the skeleton project

Typically our wrapper library would be called `libsomethingmm`. We can start by copying the **skeleton source tree** from the `mm-common` module. Starting with `mm-common 1.0.0` this skeleton application is built with the **Meson build system**.

```
$ git clone https://gitlab.gnome.org/GNOME/mm-common.git
$ cp -a mm-common/skeletonmm libsomethingmm
```



This provides a directory structure for the source .hg and .ccg files and the hand-written .h and .cc files, with meson.build files that can specify the various files in use, in terms of Meson variables. The directory structure usually looks like this, after we have renamed the directories appropriately:

- libsomethingmm: The top-level directory.
  - libsomething: Contains the main include file and the pkg-config .pc file.
    - \* src: Contains .hg and .ccg source files.
    - \* libsomethingmm: Contains hand-written .h and .cc files.

As well as renaming the directories, we should rename some of the source files. For instance:

```
$ for f in $(find libsomethingmm -depth -name '*skeleton*'); do \
    d="${f%/*}"; b="${f##*/}"; mv "$f" "$d/${b//skeleton/libsomething}"; \
done
```

A number of the skeleton files must still be filled in with project-specific content later.

Note that files ending in .in will be used to generate files with the same name but without the .in suffix, by replacing some variables with actual values during the configure stage.

Generated files are saved in the build tree, which is separated from the source tree when **meson** and **ninja** are used.

## G.1.2 Modifying build files

Now we edit the files to adapt them to our needs. You might prefer to use a multiple-file search-replace utility for this, such as **regexxer**. Note that nearly all of the files provided with the skeleton source tree contain placeholder text. Thus, the substitutions should be performed globally, and not be limited to the Meson files.

All mentions of `skeleton` should be replaced by the correct name of the C library you are wrapping, such as "something" or "libsomething". In the same manner, all instances of `SKELETON` should be replaced by "SOMETHING" or "LIBSOMETHING", and all occurrences of `Skeleton` changed to "Something".

Likewise, replace all instances of `Joe Hacker` by the name of the intended copyright holder, which is probably you. Do the same for the `joe@example.com` email address.

### G.1.2.1 meson.build in the top-level directory

- It is common for binding modules to track the version number of the library they are wrapping. So, for instance, if the C library is at version 1.23.4, then the initial version of the binding module would be 1.23.0. However, avoid starting with an even minor version number as that usually indicates a stable release.

- In the `project()` function, change the license and the C++ version, if necessary.
- You probably need to add more required modules than `glibmm` and `skeleton` (`libsomething`).

#### G.1.2.2 Other meson.build files

Next we must adapt the other `meson.build` files:

- `skeleton/meson.build`: Perhaps not much to change here more than the global name substitutions.
- `skeleton/skeletonmm/meson.build`

**defs\_basefiles** If we have more `.defs` and `docs.xml` files, we add them here.

**hg\_ccg\_basenames** We must mention all of our `.hg` and `.ccg` files here.

**extra\_cc\_files**, **extra\_h\_files** Any additional hand-written `.h` and `.cc` source files go here.

#### G.1.2.3 Creating .hg and .ccg files

We should now create our first `.hg` and `.ccg` files, to wrap one of the objects in the C library. One pair of example source files already exists: `skeleton.ccg` and `skeleton.hg`. Create copies of these files as necessary.

In the [.hg and .ccg files](#) section you can learn about the syntax used in these files.

## G.2 Generating the .defs files.

The `.defs` files are text files, in a lisp format, that describe the API of a C library, including its

- objects (GObjects, widgets, interfaces, boxed-types and plain structs)
  - functions
  - enums
  - signals
  - properties
  - vfuncs
-

At the moment, we have separate tools for generating different parts of these `.defs`, so we split them up into separate files. For instance, in the `gtk/src` directory of the gtkmm sources, you will find these files:

**gtk.defs** Includes the other files.

**gtk\_methods.defs** Objects and functions.

**gtk\_enums.defs** Enumerations.

**gtk\_signals.defs** Signals and properties.

**gtk\_vfuncs.defs** vfuncs (function pointer member fields in structs), written by hand.

The `skeletonmm/tools/generate_defs_and_docs.sh` script generates all `.defs` files and the `*_docs.xml` file, described in the [Documentation](#) section.

### G.2.1 Generating the methods `.defs`

This `.defs` file describes objects and their functions. It is generated by the `h2def.py` script which you can find in glibmm's `tools/defs_gen` directory. For instance,

```
$ ./h2def.py /usr/include/gtk-3.0/gtk/*.h > gtk_methods.defs
```

### G.2.2 Generating the enums `.defs`

This `.defs` file describes enum types and their possible values. It is generated by the `enum.pl` script which you can find in glibmm's `tools` directory, or (if glibmm is version 2.66.1 or newer) the `enumextract.py` script in the `tools/defs_gen` directory. For instance,

```
$ ./enum.pl /usr/include/gtk-3.0/gtk/*.h > gtk_enums.defs
$ ./enumextract.py /usr/include/gtk-3.0/gtk/*.h > gtk_enums.defs
```

### G.2.3 Generating the signals and properties `.defs`

This `.defs` file describes signals and properties. It is generated by the special `generate_extra_defs` utility that is in every wrapping project, such as `gtkmm/tools/extra_defs_gen/`. For instance

```
$ cd tools/extra_defs_gen
$ ./generate_extra_defs > gtk_signals.defs
```

---

You must edit the source code of your own `generate_extra_defs` tool in order to generate the `.defs` for the GObject C types that you wish to wrap. In the skeleton source tree, the source file is named `tools/extra_defs_gen/generate_defs_skeleton.cc`. If not done so already, the file should be renamed, with the basename of your new binding substituted for the `skeleton` placeholder. The `tools/extra_defs_gen/meson.build` file should also mention the new source filename.

Then edit the `.cc` file to specify the correct types. For instance, your `main()` function might look like this:

```
#include <glibmm_generate_extra_defs/generate_extra_defs.h>
#include <libsomething.h>
#include <iostream>

int main(int, char**)
{
    something_init();

    std::cout << get_defs(SOME_TYPE_WIDGET)
              << get_defs(SOME_TYPE_STUFF);
    return 0;
}
```

## G.2.4 Writing the vfuncs .defs

This `.defs` file describes virtual functions (vfuncs). It must be written by hand. There is the skeleton file `skeleton/src/skeleton_vfunc.defs` to start from. You can also look at gtkmm's `gtk/src/gtk_vfuncs.defs` file.

## G.3 The .hg and .ccg files

The `.hg` and `.ccg` source files are very much like `.h` and `.cc` C++ source files, but they contain extra macros, such as `_CLASS_GOBJECT()` and `_WRAP_METHOD()`, from which **gmmproc** generates appropriate C++ source code, usually at the same position in the header. Any additional C++ source code will be copied verbatim into the corresponding `.h` or `.cc` file.

A `.hg` file will typically include some headers and then declare a class, using some macros to add API or behaviour to this class. For instance, gtkmm's `button.hg` looks roughly like this:

```
#include <gtkmm/bin.h>
#include <gtkmm/activatable.h>
_DEFS(gtkmm, gtk)
_PINCLUDE(gtkmm/private/bin_p.h)
```

---

```

namespace Gtk
{
class Button
: public Bin,
  public Activatable // Activatable is deprecated. Will be replaced at ↵
  ABI break.
{
  _CLASS_GTKOBJECT(Button, GtkButton, GTK_BUTTON, Gtk::Bin, GtkBin)
  _IMPLEMENTS_INTERFACE(Activatable)
public:

  _CTOR_DEFAULT
  explicit Button(const Glib::ustring& label, bool mnemonic = false);

  _WRAP_METHOD(void set_label(const Glib::ustring& label), ↵
    gtk_button_set_label)

  ...

  _WRAP_SIGNAL(void clicked(), "clicked")

  ...

  _WRAP_PROPERTY("label", Glib::ustring)
};

} // namespace Gtk

```

The macros in this example do the following:

**\_DEFS ()** Specifies the destination directory for generated sources, and the name of the main .defs file that **gmmproc** should parse.

**\_PINCLUDE ()** Tells **gmmproc** to include a header in the generated private/button\_p.h file.

**\_CLASS\_GTKOBJECT ()** Tells **gmmproc** to add some typedefs, constructors, and standard methods to this class, as appropriate when wrapping a widget.

**\_IMPLEMENTS\_INTERFACE ()** Tells **gmmproc** to add initialization code for the interface.

**\_CTOR\_DEFAULT** Add a default constructor.

**\_WRAP\_METHOD (), \_WRAP\_SIGNAL (), \_WRAP\_PROPERTY (), and \_WRAP\_CHILD\_PROPERTY ()**  
Add methods to wrap parts of the C API.

The .h and .cc files will be generated from the .hg and .ccg files by processing them with **gmmproc** like so, though this happens automatically when using the above build structure:

```
$ cd gtk/src
$ /usr/lib/glibmm-2.4/proc/gmmproc -I ../../tools/m4 --defs . button . ↔
  ../../gtkmm
```

Notice that we provided **gmmproc** with the path to the .m4 convert files, the path to the .defs file, the name of a .hg file, the source directory, and the destination directory.

You should avoid including the C header from your C++ header, to avoid polluting the global namespace, and to avoid exporting unnecessary public API. But you will need to include the necessary C headers from your .ccg file.

The macros are explained in more detail in the following sections.

### G.3.1 m4 Conversions

The macros that you use in the .hg and .ccg files often need to know how to convert a C++ type to a C type, or vice-versa. **gmmproc** takes this information from an .m4 file in your `tools/m4/` directory. This allows it to call a C function in the implementation of your C++ method, passing the appropriate parameters to that C function. For instance, this tells **gmmproc** how to convert a `GtkTreeView` pointer to a `Gtk::TreeView` pointer:

```
_CONVERSION('GtkTreeView*', 'TreeView*', 'Glib::wrap($3)')
```

`$3` will be replaced by the parameter name when this conversion is used by **gmmproc**.

Some extra macros make this easier and consistent. Look in **gtkmm**'s .m4 files for examples. For instance:

```
_CONVERSION('PrintSettings&', 'GtkPrintSettings*', __FR2P)
_CONVERSION('const PrintSettings&', 'GtkPrintSettings*', __FCR2P)
_CONVERSION('const Glib::RefPtr<Printer>&', 'GtkPrinter*', ↔
  __CONVERT_REFPTR_TO_P($3))
```

### G.3.2 m4 Initializations

Often when wrapping methods, it is desirable to store the return of the C function in what is called an output parameter. In this case, the C++ method returns void but an output parameter in which to store the value of the C function is included in the argument list of the C++ method. **gmmproc** allows such functionality, but appropriate initialization macros must be included to tell **gmmproc** how to initialize the C++ parameter from the return of the C function.

For example, if there was a C function that returned a `GtkWidget*` and for some reason, instead of having the C++ method also return the widget, it was desirable to have the C++ method place the widget in a specified output parameter, an initialization macro such as the following would be necessary:

```
_INITIALIZATION('Gtk::Widget&', 'GtkWidget*', '$3 = Glib::wrap($4)')
```

\$3 will be replaced by the output parameter name of the C++ method and \$4 will be replaced by the return of the C function when this initialization is used by gmmproc. For convenience, \$1 will also be replaced by the C++ type without the ampersand (&) and \$2 will be replaced by the C type.

### G.3.3 Class macros

The class macro declares the class itself and its relationship with the underlying C type. It generates some internal constructors, the member `gobject_`, typedefs, the `gobj()` accessors, type registration, and the `Glib::wrap()` method, among other things.

Other macros, such as `_WRAP_METHOD()` and `_WRAP_SIGNAL()` may only be used after a call to a `_CLASS_*` macro.

#### G.3.3.1 \_CLASS\_GOBJECT

This macro declares a wrapper for a type that is derived from `GObject`, but whose wrapper is not derived from `Gtk::Object`.

```
_CLASS_GOBJECT( C++ class, C class, C casting macro, C++ base class, C
base class )
```

For instance, from `accelgroup.hg`:

```
_CLASS_GOBJECT(AccelGroup, GtkAccelGroup, GTK_ACCEL_GROUP, Glib::Object, ←
GObject)
```

#### G.3.3.2 \_CLASS\_GTKOBJECT

This macro declares a wrapper for a type whose wrapper is derived from `Gtk::Object`, such as a widget or dialog.

```
_CLASS_GTKOBJECT( C++ class, C class, C casting macro, C++ base class,
C base class )
```

For instance, from `button.hg`:

```
_CLASS_GTKOBJECT(Button, GtkButton, GTK_BUTTON, Gtk::Bin, GtkBin)
```

You will typically use this macro when the class already derives from `Gtk::Object`. For instance, you will use it when wrapping a GTK+ Widget, because `Gtk::Widget` derives from `Gtk::Object`.

You might also derive non-widget classes from `Gtk::Object` so they can be used without `Glib::RefPtr`. For instance, they could then be instantiated with `Gtk::make_managed()` or on the stack as a member variable. This is convenient, but you should use this only when you are sure that true reference-counting is not needed. We consider it useful for widgets.

### G.3.3.3 `_CLASS_BOXEDTYPE`

This macro declares a wrapper for a non-GObject struct, registered with `g_boxed_type_register_static()`.

```
_CLASS_BOXEDTYPE( C++ class, C class, new function, copy function, free
function )
```

For instance, from `Gdk::RGBA`:

```
_CLASS_BOXEDTYPE(RGBA, GdkRGBA, NONE, gdk_rgba_copy, gdk_rgba_free)
```

### G.3.3.4 `_CLASS_BOXEDTYPE_STATIC`

This macro declares a wrapper for a simple assignable struct such as `GdkRectangle`. It is similar to `_CLASS_BOXEDTYPE`, but the C struct is not allocated dynamically.

```
_CLASS_BOXEDTYPE_STATIC( C++ class, C class )
```

For instance, for `Gdk::Rectangle`:

```
_CLASS_BOXEDTYPE_STATIC(Rectangle, GdkRectangle)
```

### G.3.3.5 `_CLASS_OPAQUE_COPYABLE`

This macro declares a wrapper for an opaque struct that has copy and free functions. The new, copy and free functions will be used to instantiate the default constructor, copy constructor and destructor.

```
_CLASS_OPAQUE_COPYABLE( C++ class, C class, new function, copy function,
free function )
```

For instance, from `Glib::Checksum`:

```
_CLASS_OPAQUE_COPYABLE(Checksum, GChecksum, NONE, g_checksum_copy, ↔
g_checksum_free)
```

### G.3.3.6 `_CLASS_OPAQUE_REFCOUNTED`

This macro declares a wrapper for a reference-counted opaque struct. The C++ wrapper cannot be directly instantiated and can only be used with `Glib::RefPtr`.

```
_CLASS_OPAQUE_REFCOUNTED( C++ class, C class, new function, ref function,
unref function )
```

For instance, for `Pango::Coverage`:

```
_CLASS_OPAQUE_REFCOUNTED(Coverage, PangoCoverage, pango_coverage_new, ↔
pango_coverage_ref, pango_coverage_unref)
```

---



### G.3.3.7 `_CLASS_GENERIC`

This macro can be used to wrap structs which don't fit into any specialized category.

```
_CLASS_GENERIC( C++ class, C class )
```

For instance, for `Pango::AttrIter`:

```
_CLASS_GENERIC(AttrIter, PangoAttrIterator)
```

### G.3.3.8 `_CLASS_INTERFACE`

This macro declares a wrapper for a type that is derived from `GTypeInterface`.

```
_CLASS_INTERFACE( C++ class, C class, C casting macro, C interface struct,
Base C++ class (optional), Base C class (optional) )
```

For instance, from `celleditable.hg`:

```
_CLASS_INTERFACE(CellEditable, GtkCellEditable, GTK_CELL_EDITABLE, ↔
GtkCellEditableIface)
```

Two extra parameters are optional, for the case that the interface derives from another interface, which should be the case when the `GInterface` has another `GInterface` as a prerequisite. For instance, from `loadableicon.hg`:

```
_CLASS_INTERFACE(LoadableIcon, GLoadableIcon, G_LOADABLE_ICON, ↔
GLoadableIconIface, Icon, GIcon)
```

## G.3.4 Constructor macros

The `_CTOR_DEFAULT()` and `_WRAP_CTOR()` macros add constructors, wrapping the specified `*_new()` C functions. These macros assume that the C object has properties with the same names as the function parameters, as is usually the case, so that it can supply the parameters directly to a `g_object_new()` call. These constructors never actually call the `*_new()` C functions, because `gtkmm` must actually instantiate derived GTypes, and the `*_new()` C functions are meant only as convenience functions for C programmers.

When using `_CLASS_GOBJECT()`, the constructors should be protected (rather than public) and each constructor should have a corresponding `_WRAP_CREATE()` in the public section. This prevents the class from being instantiated without using a `RefPtr`. For instance:

```
class TextMark : public Glib::Object
{
    _CLASS_GOBJECT(TextMark, GtkTextMark, GTK_TEXT_MARK, Glib::Object, ↔
GObject)
```

```
protected:
    _WRAP_CTOR(TextMark(const Glib::ustring& name, bool left_gravity = true) ↔
               , gtk_text_mark_new)

public:
    _WRAP_CREATE(const Glib::ustring& name, bool left_gravity = true)
```

#### G.3.4.1 \_CTOR\_DEFAULT

This macro creates a default constructor with no arguments.

#### G.3.4.2 \_WRAP\_CTOR

This macro creates a constructor with arguments, equivalent to a `*_new()` C function. It won't actually call the `*_new()` function, but will simply create an equivalent constructor with the same argument types. It takes a C++ constructor signature, and a C function name.

It also takes an optional extra argument:

**errthrow** This tells gmmproc that the C `*_new()` has a final `GError**` parameter which should be ignored.

#### G.3.4.3 Hand-coding constructors

When a constructor must be partly hand written because, for instance, the `*_new()` C function's parameters do not correspond directly to object properties, or because the `*_new()` C function does more than call `g_object_new()`, the `_CONSTRUCT()` macro may be used in the `.ccg` file to save some work. The `_CONSTRUCT` macro takes a series of property names and values. For instance, from `button.ccg`:

```
Button::Button(const Glib::ustring& label, bool mnemonic)
:
    _CONSTRUCT("label", label.c_str(), "use_underline", gboolean(mnemonic))
{ }
```

### G.3.5 Macros that suppress generation of some code

Some macros suppress the generation of some code when they are used after a `_CLASS_*` macro. Some suppress the definition in the generated `.cc` file, others suppress both the declaration in the `.h` file and the definition in the `.cc` file.

---

#### G.3.5.1 `_CUSTOM_DEFAULT_CTOR`

Suppresses declaration and definition of default constructor in `_CLASS_BOXEDTYPE`, `_CLASS_BOXEDTYPE_STATIC` and `_CLASS_OPAQUE_COPYABLE`.

#### G.3.5.2 `_CUSTOM_CTOR_CAST`

Suppresses declaration and definition of the constructor that takes a pointer to the wrapped C object in `_CLASS_BOXEDTYPE` and `_CLASS_BOXEDTYPE_STATIC`.

Suppresses definition of the constructor that takes a pointer to the wrapped C object in `_CLASS_GOBJECT`, `_CLASS_GTKOBJECT`, `_CLASS_INTERFACE` and `_CLASS_OPAQUE_COPYABLE`.

#### G.3.5.3 `_CUSTOM_DTOR`

Suppresses definition of destructor in `_CLASS_GOBJECT` and `_CLASS_GTKOBJECT`.

#### G.3.5.4 `_CUSTOM_MOVE_OPERATIONS`

Suppresses declaration and definition of move constructor and move assignment operator in `_CLASS_GOBJECT`.

For example:

```
class Derived : public Glib::Object
{
    _CLASS_GOBJECT(Derived, GDerived, G_DERIVED, Glib::Object, GObject)

    _CUSTOM_MOVE_OPERATIONS

public:
    Derived(Derived&& src) noexcept;
    Derived& operator=(Derived&& src) noexcept;
    // ...
};
```

#### G.3.5.5 `_CUSTOM_WRAP_NEW`

Suppresses definition of `Glib::wrap_new()` function in `_CLASS_GOBJECT`.

#### G.3.5.6 `_CUSTOM_WRAP_FUNCTION`

Suppresses definition of `Glib::wrap()` function in `_CLASS_GOBJECT` and `_CLASS_GTKOBJECT`.

---

### G.3.5.7 `_NO_WRAP_FUNCTION`

Suppresses declaration and definition of `Glib::wrap()` function in `_CLASS_GOBJECT`, `_CLASS_BOXEDTYPE`, `_CLASS_BOXEDTYPE_STATIC`, `_CLASS_OPAQUE_COPYABLE`, `_CLASS_INTERFACE` and `_CLASS_GTKOBJECT`.

## G.3.6 Method macros

### G.3.6.1 `_WRAP_METHOD`

This macro generates the C++ method to wrap a C function.

```
_WRAP_METHOD( C++ method signature, C function name)
```

For instance, from `entry.hg`:

```
_WRAP_METHOD(void set_text(const Glib::ustring& text), gtk_entry_set_text)
```

The C function (e.g. `gtk_entry_set_text`) is described more fully in the `.defs` file, and the `convert*.m4` files contain the necessary conversion from the C++ parameter type to the C parameter type. This macro also generates doxygen documentation comments based on the `*_docs.xml` and `*_docs_override.xml` files.

There are some optional extra arguments:

**refreturn** Do an extra `reference()` on the return value, in case the C function does not provide a reference.

**errthrow** Use the last `GError**` parameter of the C function to throw an exception.

**deprecated** ["<text>"] Puts the generated code in `#ifdef` blocks. Text about the deprecation can be specified as an optional parameter.

**ignore\_deprecations** Puts the generated code in the `.cc` file in a `G_GNUC_BEGIN_IGNORE_DEPRECATIONS` / `G_GNUC_END_IGNORE_DEPRECATIONS` block. (Only in glibmm 2.66.x where `x >= 3` and in glibmm `>= 2.70.1`)

**constversion** Just call the non-const version of the same function, instead of generating almost duplicate code.

**newin** "<version>" Adds a `@newin` Doxygen command to the documentation, or replaces the `@newin` command generated from the C documentation.

**ifdef** <identifier> Puts the generated code in `#ifdef` blocks.

**slot\_name** <parameter\_name> Specifies the name of the slot parameter of the method, if it has one. This enables **gmmproc** to generate code to copy the slot and pass the copy on to the C function in its final `gpointer user_data` parameter. The `slot_callback` option must also be used to specify the name of the glue callback function to also pass on to the C function.

**slot\_callback** <function\_name> Used in conjunction with the `slot_name` option to specify the name of the glue callback function that handles extracting the slot and then calling it. The address of this callback is also passed on to the C function that the method wraps.

**no\_slot\_copy** Tells **gmmproc** not to pass a copy of the slot to the C function, if the method has one. Instead the slot itself is passed. The slot parameter name and the glue callback function must have been specified with the `slot_name` and `slot_callback` options respectively.

Selecting which C++ types should be used is also important when wrapping C API. Though it's usually obvious what C++ types should be used in the C++ method, here are some hints:

- **Objects used via RefPtr:** Pass the `RefPtr` as a const reference. For instance, `const Glib::RefPtr<Gtk::FileFilter> filter`.
- **Const Objects used via RefPtr:** If the object should not be changed by the function, then make sure that the object is const, even if the `RefPtr` is already const. For instance, `const Glib::RefPtr<const Gtk::FileFilter>& filter`.
- **Wrapping GList\* and GSList\* parameters:** First, you need to discover what objects are contained in the list's data field for each item, usually by reading the documentation for the C function. The list can then be wrapped by a `std::vector` type. For instance, `std::vector< Glib::RefPtr<Gdk::Pixbuf>>`. You may need to define a Traits type to specify how the C and C++ types should be converted.
- **Wrapping GList\* and GSList\* return types:** You must discover whether the caller should free the list and whether it should release the items in the list, again by reading the documentation of the C function. With this information you can choose the ownership (none, shallow or deep) for the m4 conversion rule, which you should probably put directly into the .hg file because the ownership depends on the function rather than the type. For instance:

```
#m4 _CONVERSION('GSList*', 'std::vector<Widget*>', 'Glib::SListHandler< ↵
Widget*>::slist_to_vector($3, Glib::OWNERSHIP_SHALLOW)')
```

### G.3.6.2 \_WRAP\_METHOD\_DOCS\_ONLY

This macro is like `_WRAP_METHOD()`, but it generates only the documentation for a C++ method that wraps a C function. Use this when you must hand-code the method, but you want to use the documentation that would be generated if the method was generated.

```
_WRAP_METHOD_DOCS_ONLY(C function name)
```

For instance, from `container.hg`:

```
_WRAP_METHOD_DOCS_ONLY(gtk_container_remove)
```

There are some optional extra arguments:

**errthrow** Excludes documentation of the last `GError**` parameter of the C function.

**newin "<version>"** Adds a `@newin` Doxygen command to the documentation, or replaces the `@newin` command generated from the C documentation.

### G.3.6.3 `_IGNORE`, `_IGNORE_SIGNAL`, `_IGNORE_PROPERTY`, `_IGNORE_CHILD_PROPERTY`

**gmmproc** will warn you on stdout about functions, signals, properties and child properties that you have forgotten to wrap, helping to ensure that you are wrapping the complete API. But if you don't want to wrap some functions, signals, properties or child properties, or if you chose to hand-code some methods then you can use the `_IGNORE()`, `_IGNORE_SIGNAL()`, `_IGNORE_PROPERTY()` or `_IGNORE_CHILD_PROPERTY()` macro to make **gmmproc** stop complaining.

```
_IGNORE(C function name 1, C function name 2, etc)
_IGNORE_SIGNAL(C signal name 1, C signal name 2, etc)
_IGNORE_PROPERTY(C property name 1, C property name 2, etc)
_IGNORE_CHILD_PROPERTY(C child property name 1, C child property name 2, etc)
```

For instance, from `flowbox.hg`:

```
_IGNORE(gtk_flow_box_set_filter_func, gtk_flow_box_set_sort_func)
_IGNORE_SIGNAL(activate-cursor-child, toggle-cursor-child, move-cursor)
```

### G.3.6.4 `_WRAP_SIGNAL`

This macro generates the C++ `libsigc++`-style signal to wrap a C GObject signal. It actually generates a public accessor method, such as `signal_clicked()`, which returns a proxy object. **gmmproc** uses the `.defs` file to discover the C parameter types and the `.m4` convert files to discover appropriate type conversions.

```
_WRAP_SIGNAL( C++ signal handler signature, C signal name)
```

For instance, from `button.hg`:

```
_WRAP_SIGNAL(void clicked(), "clicked")
```

Signals usually have function pointers in the GTK struct, with a corresponding enum value and a `g_signal_new()` in the `.c` file.

There are some optional extra arguments:

**no\_default\_handler** Do not generate an `on_something()` virtual method to allow easy overriding of the default signal handler. Use this when adding a signal with a default signal handler would break the ABI by increasing the size of the class's virtual function table.

**custom\_default\_handler** Generate a declaration of the `on_something()` virtual method in the `.h` file, but do not generate a definition in the `.cc` file. Use this when you must generate the definition by hand.

**custom\_c\_callback** Do not generate a C callback function for the signal. Use this when you must generate the callback function by hand.

**refreturn** Do an extra `reference()` on the return value of the `on_something()` virtual method, in case the C function does not provide a reference.

**deprecated ["<text>"]** Puts the generated code in `#ifdef` blocks. Text about the deprecation can be specified as an optional parameter.

**newin "<version>"** Adds a `@newin` Doxygen command to the documentation, or replaces the `@newin` command generated from the C documentation.

**ifdef <identifier>** Puts the generated code in `#ifdef` blocks.

**exception\_handler <method\_name>** Allows to use custom exception handler instead of default one. Exception might be rethrown by user-defined handler, and it will be caught by default handler.

**detail\_name <parameter\_name>** Adds a `const Glib::ustring&` parameter to the `signal_something()` method. Use it, if the signal accepts a detailed signal name, i.e. if the underlying C code registers the signal with the `G_SIGNAL_DETAILED` flag.

**two\_signal\_methods** Used in conjunction with the `detail_name` option to generate two `signal_something()` methods, one without a parameter and one with a parameter without a default value. With only the `detail_name` option one method is generated, with a parameter with default value. Use the `two_signal_methods` option, if it's necessary in order to preserve ABI.

### G.3.6.5 \_WRAP\_PROPERTY

This macro generates the C++ method to wrap a C GObject property. You must specify the property name and the wanted C++ type for the property. **gmmproc** uses the `.defs` file to discover the C type and the `.m4` convert files to discover appropriate type conversions.

```
_WRAP_PROPERTY(C property name, C++ type)
```

For instance, from `button.hg`:

```
_WRAP_PROPERTY("label", Glib::ustring)
```

There are some optional extra arguments:

**deprecated ["<text>"]** Puts the generated code in `#ifdef` blocks. Text about the deprecation can be specified as an optional parameter.

**newin "<version>"** Adds a `@newin` Doxygen command to the documentation, or replaces the `@newin` command generated from the C documentation.

### G.3.6.6 \_WRAP\_VFUNC

This macro generates the C++ method to wrap a virtual C function.

`_WRAP_VFUNC( C++ method signature, C function name)`

For instance, from `widget.hg`:

```
_WRAP_VFUNC(SizeRequestMode get_request_mode() const, get_request_mode)
```

The C function (e.g. `get_request_mode`) is described more fully in the `*_vfuncs.defs` file, and the `convert*.m4` files contain the necessary conversion from the C++ parameter type to the C parameter type. Conversions can also be written in the `.hg` file. Virtual functions often require special conversions that are best kept local to the `.hg` file where they are used.

There are some optional extra arguments:

**refreturn** Do an extra `reference()` on the return value of the `something_vfunc()` function, in case the virtual C function does not provide a reference.

**refreturn\_ctype** Do an extra `reference()` on the return value of an overridden `something_vfunc()` function in the C callback function, in case the calling C function expects it to provide a reference.

**keep\_return** Keep a copy of the return value in the C callback function, in case the calling C function does not expect to get its own reference.

**errthrow** Use the last `GError**` parameter of the C virtual function (if there is one) to throw an exception.

**custom\_vfunc** Do not generate a definition of the vfunc in the `.cc` file. Use this when you must generate the vfunc by hand.

**custom\_vfunc\_callback** Do not generate a C callback function for the vfunc. Use this when you must generate the callback function by hand.

**ifdef <identifier>** Puts the generated code in `#ifdef` blocks.

**slot\_name <parameter\_name>** Specifies the name of the slot parameter of the method, if it has one. This enables **gmmproc** to generate code to copy the slot and pass the copy on to the C function in its final `gpointer user_data` parameter. The `slot_callback` option must also be used to specify the name of the glue callback function to also pass on to the C function.

**slot\_callback <function\_name>** Used in conjunction with the `slot_name` option to specify the name of the glue callback function that handles extracting the slot and then calling it. The address of this callback is also passed on to the C function that the method wraps.

**no\_slot\_copy** Tells **gmmproc** not to pass a copy of the slot to the C function, if the method has one. Instead the slot itself is passed. The slot parameter name and the glue callback function must have been specified with the `slot_name` and `slot_callback` options respectively.



**return\_value <value>** Defines a non-default return value.

**err\_return\_value <value>** Defines a non-default return value, used only if the C++ `something_vfunc()` function throws an exception which is propagated to the C callback function. If `return_value` is specified, but `err_return_value` is not, then `return_value` is used also when an exception is propagated.

**exception\_handler <method\_name>** Allows to use custom exception handler instead of default one. Exception might be rethrown by user-defined handler, and it will be caught by default handler.

A rule to which there may be exceptions: If the virtual C function returns a pointer to an object derived from `GObject`, i.e. a reference-counted object, then the virtual C++ function shall return a `Glib::RefPtr<>` object. One of the extra arguments `refreturn` or `refreturn_ctype` is required.

### G.3.6.7 \_WRAP\_CHILD\_PROPERTY

This macro generates the C++ method to wrap a `GtkContainer` child property. (See [GtkContainer](#) for more information about child properties). Similarly to `_WRAP_PROPERTY`, you must specify the property name and the wanted C++ type for the property. `gmmproc` uses the `.defs` file to discover the C type and the `.m4` convert files to discover appropriate type conversions.

```
_WRAP_CHILD_PROPERTY(C child property name, C++ type)
```

For instance, from `notebook.hg`:

```
_WRAP_CHILD_PROPERTY("tab-expand", bool)
```

`_WRAP_CHILD_PROPERTY()` accepts the same optional arguments as `_WRAP_PROPERTY()`.

## G.3.7 Other macros

### G.3.7.1 \_IMPLEMENTS\_INTERFACE

This macro generates initialization code for the interface.

```
_IMPLEMENTS_INTERFACE(C++ interface name)
```

For instance, from `grid.hg`:

```
_IMPLEMENTS_INTERFACE(Orientable)
```

There is one optional extra argument:

**ifdef <identifier>** Puts the generated code in `#ifdef` blocks.

### G.3.7.2 `_WRAP_ENUM`

This macro generates a C++ enum to wrap a C enum. You must specify the desired C++ name and the name of the underlying C enum.

For instance, from `enums.hg`:

```
_WRAP_ENUM(WindowType, GtkWindowType)
```

There are some optional extra arguments:

**NO\_GTYPE** Use this option, if the enum is not a `GType`. This is the case when there is no `*_get_type()` function for the C enum, but be careful that you don't just need to include an extra header for that function. You should also file a bug against the C API, because all enums should be registered as `GTypes`.

For example, from `icontheme.hg`:

```
_WRAP_ENUM(IconLookupFlags, GtkIconLookupFlags, NO_GTYPE)
```

**s#<from>#<to>#** Substitutes (part of) the name of one or more enum constants. You can add any number of substitutions.

For example, from `iochannel.hg` in `glibmm`:

```
_WRAP_ENUM(SeekType, GSeekType, NO_GTYPE, s#^SEEK_#SEEK_TYPE_#)
```

**deprecated ["<text>"]** Puts the generated code in `#ifdef` blocks. Text about the deprecation can be specified as an optional parameter.

**newin "<version>"** Adds a `@newin` Doxygen command to the documentation, or replaces the `@newin` command generated from the C documentation.

### G.3.7.3 `_WRAP_ENUM_DOCS_ONLY`

This macro just generates a Doxygen documentation block for the enum. This is useful for enums that can't be wrapped with `_WRAP_ENUM()` because they are complexly defined (maybe using C macros) but including the generated enum documentation is still desired. It is used with the same syntax as `_WRAP_ENUM()` and also process the same options (though `NO_GTYPE` is just ignored because it makes no difference when just generating the enum's documentation).

#### G.3.7.4 `_WRAP_GERROR`

This macro generates a C++ exception class, derived from `Glib::Error`, with a `Code` enum and a `code()` method. You must specify the desired C++ name, the name of the corresponding C enum, and the prefix for the C enum values.

This exception can then be thrown by methods which are generated from `_WRAP_METHOD()` with the `errthrow` option.

For instance, from `pixbuf.hg`:

```
_WRAP_GERROR(PixbufError, GdkPixbufError, GDK_PIXBUF_ERROR)
```

`_WRAP_GERROR()` accepts the same optional arguments as `_WRAP_ENUM()`.

#### G.3.7.5 `_MEMBER_GET` / `_MEMBER_SET`

Use these macros if you're wrapping a simple struct or boxed type that provides direct access to its data members, to create getters and setters for the data members.

```
_MEMBER_GET(C++ name, C name, C++ type, C type)
```

```
_MEMBER_SET(C++ name, C name, C++ type, C type)
```

For example, in `rectangle.hg`:

```
_MEMBER_GET(x, x, int, int)
```

#### G.3.7.6 `_MEMBER_GET_PTR` / `_MEMBER_SET_PTR`

Use these macros to automatically provide getters and setters for a data member that is a pointer type. For the getter function, it will create two methods, one `const` and one `non-const`.

```
_MEMBER_GET_PTR(C++ name, C name, C++ type, C type)
```

```
_MEMBER_SET_PTR(C++ name, C name, C++ type, C type)
```

For example, for `Pango::Analysis` in `item.hg`:

```
// _MEMBER_GET_PTR(engine_lang, lang_engine, EngineLang*, PangoEngineLang ↵  
*)  
// It's just a comment. It's difficult to find a real-world example.
```

### G.3.7.7 `_MEMBER_GET_GOBJECT` / `_MEMBER_SET_GOBJECT`

Use these macros to provide getters and setters for a data member that is a `GObject` type that must be referenced before being returned.

```
_MEMBER_GET_GOBJECT(C++ name, C name, C++ type, C type)
```

```
_MEMBER_SET_GOBJECT(C++ name, C name, C++ type, C type)
```

For example, in `Pangomm, layoutline.hg`:

```
_MEMBER_GET_GOBJECT(layout, layout, Pango::Layout, PangoLayout*)
```

## G.3.8 `gmmproc` Parameter Processing

`gmmproc` allows processing the parameters in a method signature for the macros that process method signatures (like `_WRAP_METHOD()`, `_WRAP_CTOR()` and `_WRAP_CREATE()`) in a variety of ways:

### G.3.8.1 Parameter Reordering

For all the macros that process method signatures, it is possible to specify a different order for the C++ parameters than the existing order in the C function, virtual function or signal. For example, say that the following C function were being wrapped as a C++ method for the `Gtk::Widget` class:

```
void gtk_widget_set_device_events(GtkWidget* widget, GdkDevice* ↵
    device,
    GdkEventMask events);
```

However, changing the order of the C++ method's two parameters is necessary. Something like the following would wrap the function as a C++ method with a different order for the two parameters:

```
_WRAP_METHOD(void set_device_events(Gdk::EventMask events{events},
    const Glib::RefPtr<const Gdk::Device>& device{device}),
    gtk_widget_set_device_events)
```

The `{c_param_name}` following the method parameter names tells `gmmproc` to map the C++ parameter to the specified C parameter within the `{}`. Since the C++ parameter names correspond to the C ones, the above could be re-written as:

```
_WRAP_METHOD(void set_device_events(Gdk::EventMask events{.}, ↵
    const
    Glib::RefPtr<const Gdk::Device>& device{.}),
    gtk_widget_set_device_events)
```

**Warning**

Please note that when reordering parameters for a `_WRAP_SIGNAL()` method signature, the C parameter names would always be `p0`, `p1`, etc. because the `generate_extra_defs` utility uses those parameter names no matter what the C API's parameter names may be. It's how the utility is written presently.

**G.3.8.2 Optional Parameter Processing**

For all macros processing method signatures except `_WRAP_SIGNAL()` and `_WRAP_VFUNC()` it is also possible to make the parameters optional so that extra C++ methods are generated without the specified optional parameter. For example, say that the following `*_new()` function were being wrapped as a constructor in the `Gtk::ToolButton` class:

```
GtkToolItem* gtk_tool_button_new(GtkWidget* icon_widget, const ↵
    gchar*
    label);
```

Also, say that the C API allowed `NULL` for the function's `label` parameter so that that parameter is optional. It would be possible to have **gmmproc** generate the original constructor (with all the parameters) along with an additional constructor without that optional parameter by appending a `{?}` to the parameter name like so:

```
_WRAP_CTOR(ToolButton(Widget& icon_widget, const Glib::ustring&
    label{?}), gtk_tool_button_new)
```

In this case, two constructors would be generated: One with the optional parameter and one without it.

**G.3.8.3 Output Parameter Processing**

With `_WRAP_METHOD()` it is also possible for the return of the wrapped C function (if it has one) to be placed in an output parameter of the C++ method instead of having the C++ method also return a value like the C function does. To do that, simply include the output parameter in the C++ method parameter list appending a `{OUT}` to the output parameter name. For example, if `gtk_widget_get_request_mode()` is declared as the following:

```
GtkSizeRequestMode gtk_widget_get_request_mode(GtkWidget* widget);
```

And having the C++ method set an output parameter is desired instead of returning a `SizeRequestMode`, something like the following could be used:

```
_WRAP_METHOD(void get_request_mode(SizeRequestMode& mode{OUT})
    const, gtk_widget_get_request_mode)
```

The `{OUT}` appended to the name of the *mode* output parameter tells **gmmproc** to place the return of the C function in that output parameter. In this case, however, a necessary initialization macro like the following would also have to be specified:

```
_INITIALIZATION('SizeRequestMode&', 'GtkSizeRequestMode', '$3 =
(SizeRequestMode) ($4)')
```

Which could also be written as:

```
_INITIALIZATION('SizeRequestMode&', 'GtkSizeRequestMode', '$3 =
($1) ($4)')
```

`_WRAP_METHOD()` also supports setting C++ output parameters from C output parameters if the C function being wrapped has any. Suppose, for example, that we want to wrap the following C function that returns a value in its C output parameter *rect*:

```
gboolean gtk_icon_view_get_cell_rect(GtkIconView* icon_view,
GtkTreePath* path, GtkCellRenderer* cell, GdkRectangle* rect);
```

To have **gmmproc** place the value returned in the C++ *rect* output parameter, something like the following `_WRAP_METHOD()` directive could be used:

```
_WRAP_METHOD(bool get_cell_rect(const TreeModel::Path& path, const
CellRenderer& cell, Gdk::Rectangle& rect{>>}) const,
gtk_icon_view_get_cell_rect)
```

The `{>>}` following the *rect* parameter name indicates that the C++ output parameter should be set from the value returned in the C parameter from the C function. **gmmproc** will generate a declaration of a temporary variable in which to store the value of the C output parameter and a statement that sets the C++ output parameter from the temporary variable. In this case it may be necessary to have an `_INITIALIZATION()` describing how to set a `Gdk::Rectangle&` from a `GdkRectangle*` such as the following:

```
_INITIALIZATION('Gdk::Rectangle&', 'GdkRectangle', '$3 =
Glib::wrap(&($4))')
```

### G.3.8.4 String Parameter Processing

A string-valued input parameter in a C++ method is usually a `const Glib::ustring&` or a `const std::string&`. In C code it's a `const gchar*`. When an empty string is converted to `const gchar*`, it can be converted either to `nullptr` or to a pointer to an empty string (with `c_str()`). Some parameters in some C functions accept a `nullptr`, and interpret it in a special way. Other parameters must not be `nullptr`.

The default conversion in `_WRAP_METHOD()` and similar directives is

- for mandatory parameters (with or without default values): empty string to empty string,
- for optional parameters (with appended {?}): empty string to `nullptr`.

If the default conversion is not the best conversion, append `{NULL}` to a mandatory parameter or `{?!NULL}` to an optional parameter (`!NULL` = not `NULL`). If you append both a C parameter name and `NULL`, separate them with a space: `{c_param_name NULL}`.

### G.3.9 Basic Types

Some of the basic types that are used in C APIs have better alternatives in C++. For example, there's no need for a `gboolean` type since C++ has `bool`. The following list shows some commonly-used types in C APIs and what you might convert them to in a C++ wrapper library.

*C type:* `gboolean`, *C++ type:* `bool`

*C type:* `gint`, *C++ type:* `int`

*C type:* `guint`, *C++ type:* `guint`

*C type:* `gdouble`, *C++ type:* `double`

*C type:* `gunichar`, *C++ type:* `gunichar`

*C type:* `gchar*`, *C++ type:* `Glib::ustring` (or `std::string` for filenames)

## G.4 Hand-coded source files

You might want to include additional source files that will not be generated by **gmmproc** from `.hg` and `.ccg` files. You can simply place these in your `libsomething/libsomethinggmm` directory and mention them in the `meson.build` in the `extra_h_files` and `extra_cc_files` variables.

## G.5 Initialization

Your library must be initialized before it can be used, to register the new types that it makes available. Also, the C library that you are wrapping might have its own initialization function that you should call. You can do this in an `init()` function that you can place in hand-coded `init.h` and `init.cc` files. This function should initialize your dependencies (such as the C function, and `gtkmm`) and call your generated `wrap_init()` function. For instance:

```
void init()
{
    Gtk::Main::init_gtkmm_internals(); //Sets up the g type system and the ↵
    Glib::wrap() table.
    wrap_init(); //Tells the Glib::wrap() table about the libsomethinggmm ↵
    classes.
}
```

The implementation of the `wrap_init()` method in `wrap_init.cc` is generated by `generate_wrap_init.pl`, but the declaration in `wrap_init.h` is hand-coded, so you will need to adjust `wrap_init.h` so that the `wrap_init()` function appears in the correct C++ namespace.

## G.6 Problems in the C API.

You are likely to encounter some problems in the library that you are wrapping, particularly if it is a new project. Here are some common problems, with solutions.

### G.6.1 Unable to predeclare structs

By convention, structs are declared in glib/GTK+-style headers like so:

```
typedef struct _ExampleWidget ExampleWidget;

struct _ExampleWidget
{
    ...
};
```

The extra typedef allows the struct to be used in a header without including its full definition, simply by predeclaring it, by repeating that typedef. This means that you don't have to include the C library's header in your C++ header, thus keeping it out of your public API. **gmmproc** assumes that this technique was used, so you will see compiler errors if that is not the case.

This compiler error might look like this:

```
example-widget.h:56: error: using typedef-name 'ExampleWidget' after '↵
    struct'
../../libexample/libexamplemm/example-widget.h:34: error: 'ExampleWidget' ↵
    has a previous declaration here
make[4]: *** [example-widget.lo] Error 1
```

or this:

```
example-widget.h:60: error: '_ExampleWidget ExampleWidget' redeclared as ↵
    different kind of symbol
../../libexample/libexamplemm/example-widget.h:34: error: previous ↵
    declaration of 'typedef struct _ExampleWidget ExampleWidget'
```

This is easy to correct in the C library, so do send a patch to the relevant maintainer.



## G.6.2 Lack of properties

By convention, glib/GTK+-style objects have `*_new()` functions, such as `example_widget_new()` that do nothing more than call `g_object_new()` and return the result. The input parameters are supplied to `g_object_new()` along with the names of the properties for which they are values. For instance,

```
GtkWidget* example_widget_new(int something, const char* thing)
{
    return g_object_new (EXAMPLE_TYPE_WIDGET, "something", something, ↵
        "thing", thing, NULL);
}
```

This allows language bindings to implement their own equivalents (such as C++ constructors), without using the `*_new()` function. This is often necessary so that they can actually instantiate a derived GType, to add their own hooks for signal handlers and vfuncs.

At the least, the `_new()` function should not use any private API (functions that are only in a .c file). Even when there are no functions, we can sometimes reimplement 2 or 3 lines of code in a `_new()` function as long as those lines of code use API that is available to us.

Another workaround is to add a `*_construct()` function that the C++ constructor can call after instantiating its own type. For instance,

```
GtkWidget* example_widget_new(int something, const char* thing)
{
    ExampleWidget* widget;
    widget = g_object_new (EXAMPLE_TYPE_WIDGET, NULL);
    example_widget_construct(widget, "something", something, "thing", ↵
        thing);
}

void example_widget_construct(ExampleWidget* widget, int something, const ↵
    char* thing)
{
    //Do stuff that uses private API:
    widget->priv->thing = thing;
    do_something(something);
}
```

Adding properties, and ensuring that they interact properly with each other, is relatively difficult to correct in the C library, but it is possible, so do file a bug and try to send a patch to the relevant maintainer.

## G.7 Documentation

In general, gtkmm-style projects use Doxygen, which reads specially formatted C++ comments and generates HTML documentation. You may write these doxygen comments directly in the header files.

### G.7.1 Reusing C documentation

You might wish to reuse documentation that exists for the C library that you are wrapping. GTK-style C libraries typically use gtk-doc and therefore have source code comments formatted for gtk-doc and some extra documentation in .sgml and .xml files. The `docextract_to_xml.py` script, from glibmm's `tools/defs_gen` directory, can read these files and generate an .xml file that **gmmproc** can use to generate doxygen comments. **gmmproc** will even try to transform the documentation to make it more appropriate for a C++ API.

For instance,

```
./docextract_to_xml.py -s ~/checkout/gnome/gtk+/gtk/ > gtk_docs.xml
```

Because this automatic transformation is not always appropriate, you might want to provide hand-written text for a particular method. You can do this by copying the XML node for the function from your `something_docs.xml` file to the `something_docs_override.xml` file and changing the contents. Alternatively you can write your own documentation in the .hg file.

### G.7.2 Documentation build structure

If you copied the skeleton source tree in mm-common and substituted the placeholder text, then you will already have suitable `meson.build` and `Doxyfile.in` files in the `doc/reference/` directory. You probably need to modify the `tag_file_modules` variable in `meson.build`, though. With the mm-common build setup, the list of Doxygen input files is not defined in the Doxygen configuration file, but passed along from **meson/ninja** to the standard input of **doxygen**.

---